Telephone No. 080 22243926 Fax No. 080 22110134 Website: www.kptcl.com



Email ID: dgmtkptcl@rediffmail.com

## KARNATAKA POWER TRANSMISSION CORPORATION LIMITED CIN No. U40109KA1999SGC025521

No. KPTCL/B25/87066/2018-19

Corporate Office Kaveri Bhavan, K.G Road, Bengaluru - 560 009 Date:

10 FEB 2021

## **CIRCULAR**

**Sub:** Revised Standardized Quality Assurance Plan (QAP) for 110kV and 66kV Power Transformers rated upto 31.5MVA - Reg.

**Ref:** 1. OM No. KPTCL/B25/87066/2018-19 dtd 29.01.2019 2. Circular No. KPTCL/B25/87066/2018-19 dtd 06.11.2019.

3. Proceeding No. CEE(T&P)/SEE/EE(P)/KCO-161/AEEP-1/2020-21/12191 dtd

28.12.2020.

Note of CEE (T&P) approved by the Managing Director 10.01.2021

4. Note of CEE (T&P) approved by the Managing Director on 19.01.2021.5. T.O.Note approved by the Director(Transmission) on 10.02.2021

\*\*\*\*\*

In continuation to Corporate Circular dated 06.11.2019 under ref (2), the standardized Quality Assurance Plan (QAP) for 110kV and 66kV voltage class Power Transformers rated upto 31.5MVA for all procurement of Power Transformers for the works of KPTCL including direct procurement of Power Transformers by KPTCL and for turnkey works supplied through EPC contractors is revised based on the decision of the Committee w.r.t clarifications sought by some of the Power Transformer manufacturers.

In this regard, the existing approved Standardized Quality Assurance Plan (QAP) for 110kV and 66kV voltage class Power Transformers rated upto 31.5MVA issued vide Circular dated 06.11.2019 is hereby withdrawn and the revised Standardized Quality Assurance Plan (QAP) annexed to this Circular shall be adopted henceforth.

All other contents of the Circular dated 06.11.2019 under ref (2) remains unaltered.

Further, any clarification required may be obtained from O/o CEE (T&P), KPTCL, Kaveri Bhavan, Bengaluru.

General Manager (Tech)

KPTCL

## Copy to:

- 1. All Chief Engineers (Electy), KPTCL.
- 2. All Superintending Engineers, El., KPTCL.
- 3. All Executive Engineers, El., KPTCL.
- 4. The Company Secretary, KPTCL, Kaveri Bhavan, Bengaluru.
- 5. SPS to the Managing Director / Director (Transmission) / Director (Finance), KPTCL, Kaveri Bhavan, Bengaluru.

## Copy to:

The Superintending Engineer (Elect.,), IT & MIS, with a request to arrange to upload this Circular in KPTCL website.

					35. 0					
1 1			T		Manufact	turing Quality Plan for 110kV and 66kV power transform	er up to	31.5MV	/А сара	acity. (Revised)
SI. No	Components and Operations						S- Su	viation suppli rform;	ier ; M-	- Transformer manufacturer ; C- Customer (KPTCL). itness ; V- Verification (Review)
								Agenc	y	
		Type of check	Class o Check		Reference document	Accepting norms	s	M	С	Remarks
A	RAW MATERIALS									
1.1	PAPER INSULATED COPPER CONDUCTOR (PICC)			Ť	·			T	T	
1.1.1	Visual & Dimensional check of bare conductor. Thickness & Width of bare conductor, Covered width & Thickness	 Measure	A		IS 1897 IS 13730 IS 7401	Bare conductor Width/thick(mm) Tolerance Up to 3.15 - 0.03 3.16 to 6.30 - 0.05 6.31 to 12.5 - 0.07 12.51 to 16 - 0.10 >16 mm - 0.10 Insulated Conductor Covering thick(mm) Tolerance 0.25 to 0.510 0.51 to 1.257.5 over 1.255	P	w	V	1) Review of sourcing of copper & kraft paper shall be done. Witnessing of thickness of Kraft paper to be carried out by power transformer manufacturer during stage inspection of PICC. Test certificate for aging of paper shall be verified by Power transformer manufacturer.
	Check of Aging of paper						P	V	_ V	2) One sample per lot for each size and for each rating of transformer shall be drawn by the power transformer
1.1.2	Surface Finish	Visual	A		IS 1897 IS 13730		P	v		manufacturer and send for tests at CPRI/ERDA laboratory/ NABL accredited lab and reports of the same shall be submitted
	Number of layers of paper covering	Visual	А		IS 7401 IEC 60317	Technical specification, approved drawings & GTP				during the stage inspection of winding.
	Arrangement of top layers						P	W	· V	The following tests shall be conducted at CPRI/ERDA only: Sl No. 1.1.1] Dimensional check Sl No. 1.1.3] Chemical composition of Copper.
1.1.3	Chemical composition of Copper	Measure	A	One sample for			P	V		Sl No. 1.1.4] Resistivity at 20deg C Sl No. 1.1.5] Tensile strength & elongation test.
1.1.4	Resistivity at 20deg C in ohms mm²/m a) Soft/Annealed Copper			each size for each rating of Transformer			. V		V	The balance tests can be conducted at CPRI/ERDA/NABL
	b) Work hard copper	Measure	Α	Transionmen	IS 13730	a) 0.01727/0.017241 ohms/mm <sup>2</sup> /m(max) at 20 deg b) 0.017777 ohms/mm <sup>2</sup> /m(max)	P	w	v	accredited lab.
√.1.5	Tensile strength and elongation test( For normal Conductor)	Measure	A		IS 13730 IS 7404	Thickness Tensile strength Elongation (mm) Nm/m2 % Up to 2.5 205-265 30min >2.5-5.6 205-255 32min	P	w	v	
1.1.6	Proof Stress for work hardened conductor (if applicable)	Measure	Α		IS 7404 IS-13730	As per design requirement	<b>P</b>	w	V	
1.1.7	Corner radius	Measure	A		IS 13730	As per design requirement	P	w	v	
1.1.8	Insulation test for bunched conductor ( if applicable) a) No. of Conductors b)Thickness & width of bare conductor, Covered width & thickness c) Voltage test between strands	Measure	Α		IS 13730	As per IS 13730	P	W	v	<del>"</del> ,
1.1.9	Hardness Test	Measure	A		IS 7404 IS 13730	Max hardness should be RF 65, when measured in Rockwell "F" scale	P	w	v	

ಹು.ಇಂ. (ವಿ) ಮುಖ್ಯ ಇಂಜಿನಿಯರ್ (ವಿಡ್ಯುತ್)ರ್.೩೬೬ ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾವೇರಿ ಭವನ, ಬೆಂಗಳೂರು–560 009

Property of the second

	and the second s		٠			ng Quality Plan for 110kV and 66kV power transformer u	ap to 31.5	MVA ca	.pacity. (P	(Revised)
a.		·			Manufacturi	ig Quality Plan for 222-	Abbreviat	tions:		`
							1		M- Transf Witness	nsformer manufacturer; C- Customer (KPTCL). s; V- Verification (Review)
	Connections		1				; <b>A</b> :	gency		Remarks
S1. No.	Components and Operations			<del></del>	f Reference	Accepting norms	s	M	С	
		Type of check	Class of Check	Quantum of check	document					
1.2	CONTINUOUSLY TRANSPOSED COPPER CONDUCTOR (CTC)		<u> </u>	,			P	w	v ·	
	Visual Inspection, Check for Number of conductors, Ageing of paper	_ '			IEC 60317	As per design requirement & Technical specification	P	v	v	
		Visual	A		IS 60317	As per doses		-		
1.2.1	Arrangement of paper covering	-					P	V	V	
	Check for adherence of enamel		+	-	IEC 60317	As per design requirement & Technical specification	P	w	v	l
1.2.2		Measure	A		IS 60317	a)0.01727 ohm/mm2 / m(max) at 20 deg		w	V	Review of sourcing of copper & kraft paper shall be done.
	- Axial width  Resistivity at 20deg C in ohms mm²/m	Measure	e A		IEC 60317 IS 60317 IS 13730	b) 0.01777 ohm-mm2/ m (max)	P		-	Witnessing of thickness of Kraft paper to be carried out by power transformer manufacturer during stage inspection (
1.2.3				One sample each size each ratio	ple for ze for IS 7404	Thickness Tensile strength Elongation (mm) Nm/m2 %  Up to 2.5 205-265 30min	P	o.   W	v	One sample of CTC per lot shall be drawn by the power transformer manufacturer and send for tests at CPRI/ERI
1.2.	2.4 Tensile strength and elongation test (For anneled Conductor)	Measure	re A	A each ratu	IS 13730 ormer IS 7404	>2.5-5.6 205-253 52	P	P W	, v	and reports of the same shall be submitted during the staginspection of winding.
:	2.5 Proof Stress for work hardened conductor (if applicable)	Measure	e /	Α	IS 1373	30 Technical specification	on I	P W	v v	
1.2		Measure	re	A	IEC 603 IS 6031	17	1	P W	w v	
1.	1.2.6 Breakdown Voltage test on enameled conductor	Test	i	A	IEC 603	117				-
1	1.2.7 Flexibility				IEC 603		ion		w v	
1	1.2.8 Insulation test	Test	51	A	IS191/	requirement & Technical specificat	ion	P W	W V	
	1.2.9 Chemical Analysis	1000			IEC 60			P	w	
	Insulation test for bunched CTC a) No. of Conductors b)Thickness & width of bare conductor, Covered width & thick c) Voltage test between strands (if applicable)	ckness Measu	ıre	. A	IS 60	Max hardness should be RF 65, when measured	ed in	P	w	7
	1.2.11 Hardness Test	Meas	sure	A	IS 1	3730 Rockwell F Scale				

ಮು.ಇಂ. (ಎ) ಮುಖ್ಯ ಇಂಜಿನಯರ್ (ವಿದ್ಯುತ್) ಆರ್.ಟಿ. ಮತ್ತು ಆೀ. १४ ಟೆ. ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ.

		<u> </u>					· · · · · · · · · · · · · · · · · · ·			· .
			T		Manufactu	ring Quality Plan for 110kV and 66kV power transformer	up to	31.5MV	А сара	city. (Revised)
Sl. No.	Components and Operations						S- Sub	viation suppli	er ; M-	Transformer manufacturer ; C- Customer (KPTCL). tness ; V- Verification (Review)
51. No.	Components and Operations		1				-			
								Agenc	y	, ,
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	M	С	Remarks
1.3	KRAFT INSULATING PAPER (FOR COVERING OF PICC & CTC)									
1.3.1	Checks for paper healthiness	Visual	A			Paper to be smooth, unglazed surface &	P	v	v	
1.3.2	Thickness	Measure	A	_		free from dust particles / No surface defects Within specified value ± 10%	. P	W	V	
1.3.3	Apparent Density	Measure	A			min 0.75gm/ cm <sup>3</sup> , max 0.85gm cm <sup>3</sup> or	Р	v	v	<u> </u>
1.3.4	Moisture Content	Measure	A	-		0.8 ±0.05 gm/ cm <sup>3</sup> 8 % max	P		V	
	Tensile Index			1			P	V	<del>                                     </del>	-
1.3.5	a) Machine direction (MD) min b) Cross Machine direction (CMD) Min	Measure	A	One sample per each size per lot		93 NM/gm (min) 35 NM/gm (min)	P	V	V	Record review by KPTCL at the time of stage inspection of
	Electrical strength in air	Measure	A	]	IEC 60554-3-1	Min 7kV/mm	P	H v	V	winding. Test certificate of aging of paper is to be furnished
	Ash Content	Measure	A	]	IEC 60554-3-5	1 % max	P	V	V	
	Conductivity of 5% aqueous water extract PH of 5% aqueous extract	Measure Measure	A	-	IEC 60554-2,	10 mS/m (max) 6 to 8	P	V	V	Witnessing of thickness of Vactorian
	BDV test at air	Measure	^	1	Methods of Test	5 mN m2/g (min) / 6 mN m2/g (min)	P	V	V	Witnessing of thickness of Kraft paper to be carried out by power transformer manufacturer during stage inspection of
	Tear Index(MD/CMD), Air permeability, Water absorption, Elongation Heat stability	Measure	A		IS 9335	0.5 to 1.0 μm/Pa.s 10 %	P	V	v	PICC & CTC.
1211	a) Reduction of degree of polymerization     b.) Reduction of Bursting Strength	Measure	A			According to type test report	P	v	v	
	c.) Increase of Conductivity of Aqueous extract.				4	Thick (μm) Sub (g/cm3) Tolerance		ļ	ļ	
	•					50 40 10				
1.3.12	Substance (grammage)	Measure	Α			65 52 05	P	V	V	
						75 60 05 90 72 05				
	PRECOMPRESSED PRESSBOARD	777 1	_							
1.4.1	Check for healthiness, Appearance Check for thickness of various sizes, Dimensions	Visual measure	A			No visible surface defect Within tolerance	P	V	V	
	Density	Measure	A	1		1 to 1.3 g/cm <sup>3</sup>	P	V W	V	
	Oil absorption	Measure	Α			Min 7% to 11% (depending on the thickness)	P	V	V	-
1.4.5	Moisture Content	Measure	A			Max 6%	P	V	V	]
	Shrinkage in air MD, CD & PD	Measure	Α			IEC 60641/MD - 0.5 % max, CD- 0.7 % max, Thick -5 % max	P	V	V	
	Cohesion between plies	Measure	A			The split shall not show a rupture in one or more piles	P	V	V	
1.4.8	Tensile Index a) Machine direction b) Cross direction	Measure	Α			a) Min 100 to 110 Mpa b) Min 75 to 85 Mpa	P	v	v	If this inspection is offered at Manufacturer's premises, the
1.4.9	Elongation a) Machine direction b) Cross direction	Measure	Α		Technical	a) Min 3% b)Min 4%	P	V	V	Thickness of press boards to be verified by KPTCL during stage
1.4.10	Compressibility in air a) Max compressibility b)Reversible compressibility	Measure	A	One sample of each size per lot	specification & IS 1576 IEC 60641	a) Max: 4 to 10% b) Min: 45 to 50%	P	v	V	inspection of Core & windings.  Reports of all tests to be submitted during stage inspection of core and windings. Record review by KPTCL at the time of stage
1.4.11	Dielectric strength (BDV) a) Electric strength in air b) Electric strength in oil	Measure	A			Min 30 to 40kV/mm in oil depending on thickness	P	V	V	inspection of core & winding
1.4.12	Ash Content	Measure	A			Max 1%	P	V	V	
1.4.13	PH Value of aqueous extract	Measure	A			6 to 9	P	V	V	1
1.4.14	Conductivity of aqueous extract	Measure	A			Max 5 to 10 mS/m	Р	V	V	
1.4.15	Ply Bond Resistance	Measure	Α				Р	V	V	
1.4.16	Flexural strength MD, CD (Laminated Boards)	Measure	A /		(3)		Р	V	V	
				4 5 5 4 - 3						

ಮುಖ್ಯ ಇಂಜನಿಯರ್ (ವಿದ್ಯುತ್) ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾವೇರಿ ಭವನ, ಬೆಂಗಳೂರು–560 009

		· · · · · · · · · · · · · · · · · · ·			Manufacturii	ng Quality Plan for 110kV and 66kV power transforme	r up to 31	.5MVA	capacit	ty. (Revised)
							Abbrevi S- Sub s P - Perfe	upplier	; M- Tı V- Witn	ransformer manufacturer ; C- Customer (KPTCL). ess ; V- Verification (Review)
S1. No.	Components and Operations						1 ,	Agency		* #
		Type of check	Class of	Quantum of check	Reference document	Accepting norms	s	м	С	Remarks
			Check							
1.5	UNIMPREGNATED DENSIFIED LAMINATED WOOD (PERMAWOOD)			i						
1.5.1	Visual inspections - Surface finish & Dimensional Check for thickness, width & length, shrinkage in oil.	Visual/ Measure	A			Dimension within tolerance	P	v	v v	
1.5.2	Density	Measure	A			0.9 to 1.25 g/cm <sup>3</sup>	P		V	
1.5.3	Moisture Content	Measure	Α .		·	Max 7%	P	V		If this inspection is offered at Manufacturer's premises, the same shall be performed by the Manufacturer. Reports of a
1.5.4	Oil absorption at 90 °C	Measure	A			Min 6%	P	V		tests to be submitted during stage inspection of core an
1.5.5	Electrical proof strength in oil at 90 0C a) Along grain b) Edge wise	Measure	A	One sample of each size per lot	Technical specification, IEC 61061	a) Min 4 kV/mm b) Min 60kV per 25mm	P	V		windings. Record review by KPTCL at the time of stagenspection of core & winding
1.5.6	Tensile strength	Measure	A		IEC 01001	Min: 96 Mpa	P	V	V	- Annie P
1.5.7	Cross breaking strength along grain & across grain	Measure	А			a) Min: 110 Mpa(Along grain) b) Min: 85 Mpa(Across grain)	P	v	V	
1.5.8	Compress perp to laminate	Measure	A			Max: 2.5 to 5% as per grade	P	V	V	
1.5.9	Shear strength age-wise	Measure	A	1		Min for LD - 450 KV /cm <sup>2</sup>	P	V	V	
1.5.10	Compressive strength test	Measure	A			Min for LD - 1400 KV /cm <sup>2</sup>	P	V	V	
1.6	CRGO STEEL (MOTHER COIL)									
1.6.1	Inspection of CRGO coil  - Visual inspection for external damages, waviness, dimensions and thickness,  - Manufacturer's identification slip/unique numbering of CRGO coil  - Mills test certificates, surface finish, burr level/bow check, bend test.  Inspection of prime CRGO coil check for coil width and thickness from name plate	Visual	A	One sample per lot	Technical specification, IEC 60404	Technical specification, approved drawings, GTP IEC 60404 IS 3024	-	w	V	One sample per CRGO lot shall be drawn by the power transformer manufacturer and to be sent to CPRI/ERDA Laboratory for all tests. The report of the same shall.
1.6.2	Specific core loss, Magnetic characteristics.	Measure	A		IS 3024	GTP/specific grade Min 95%	P P	W	V	furnished to KPTCL officers at the time of core building inspection
1.6.3	Stacking Factor	Measure	A .	-		Avg value min $10 \Omega \text{ cm}^2$	P	w	v	
1.6.4	Surface Insulation Resistivity (ohms-cm²)	Measure	A	One sample per		Individual value min 5Ω cm <sup>2</sup> Min: 1.78 for CGO	P	w	v	
1.6.5	Minimum polarisation in Tesla at field strength of 800 A/m	Measure	A	lot		Min 1.85 for HPGO Max 4% increase in specific total losses	P	w	V	
1.6.6	Accelerated ageing test  Check of core insulation	Measure Measure	A A	1		As per GTP IEC 60404 IS 3024	Р	w	v	
1.7	CONDENSER BUSHING							<del> </del>	V	
1.7.1	Visual check of fittings and all accessories, Surface Condition and	Visual	A				P	W	<u>'</u>	4
1.7.2	Scaling Creepage distance and dimension check	Measure	A .		Technical	As per approved GTP	P	w	v	All tests shall be witnessed by Power transformer manufactur  Any variation in the test values or discrepancies observed, su
1.7.3	Routine Test: a) Measure of Capacitance & <u>Tan delta at room temperature at 2KV 5KV and 10KV and voltage dependency factor</u> b) Dry PF voltage withstand test c) Measure of PD quantity d) Lightening impulse withstand e) Test tap insulation test f) sealing g) <u>Tightness test</u>	Measure	A	100%	specification, approved drawing, GTP IS 2099 IS 12676 IEC 60137	a) Tan Delta - 66 kV - 0.7% Above 66 kV - 0.4% b)As per approved GTP c)As per IEC - No flash-over/ puncture d) As per IS/IEC e) As per IS/IEC f) No leakage g) As per approved drawing h) No leakage	P	w	v	hy variation in the test values of discrepancies observed, of bushings shall be rejected by the Power Transformer manufacturer.  KPTCL shall verify test reports during final inspection.
L					Pag	ge 4 of 15			, .	Mark of the second

			•		Manufactu	ring Quality Plan for 110kV and 66kV power transformer	up to	31.5MV	А сарас	city. (Revised)
Sl. No.	Components and Operations						S- Sut	viation suppli rform;	er ; M-	Transformer manufacturer ; C- Customer (KPTCL). ness ; V- Verification (Review)
								Agenc	<b>y</b>	
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	M	С	Remarks
1.8	PORCELAIN BUSHING									
1.8.1	Visual Check	Visual	В	·			P	T <sub>V</sub>	V	
1.8.2	Creepage distance check	Measure	В				P	l v	V	1
1.8.3	Dimension Check	Measure	. В	]	Tech spec Approved	Tech spec	P	v	v	.
1.8.4	Routine test including PF volt withstand	Measure	В		drawings	Approved drawings GTP	P	l v	v	Record review at the time of final inspection.
				100%	GTP IS 3347	As per IS 3347	<u> </u>	<b> </b>	<del>  '</del> -	LV bushing has to be replaced free of cost to KPTCL, if it is
1.8.5	Test Certificate a) Insulation resistance measurement with 2kV Megger b) Dry Power Frequency voltage withstand test to be furnished at the time of final inspection	Measure	В		IS 2099 IS 5621 IEC 60137	IS 2099 IS 5621 IEC 60137	P	v	v	found punctured at site or if found that the LV bushing is not as per KPTCL requirement
1.9	CURRENT TRANSFORMER (Bushing CT)									
1.9.1	Visual check of healthiness	Visual	В				P	V	V	
1.9.2	Check for dimension (ID/OD, thickness)	Measure	В	-			P	V	V	
1.9.3	Test/ Check of a) Accuracy, Ratio b) Dry PF Withstand test on secondary c) Over voltage inter turn test d) Verification of terminal marking e) Polarity f) Knee point voltage g) Exciting current test for PS class h) Sec winding resistance for PS class	Measure	В	100%	IEC 60044- 1:2003 IS 2705	Technical spec, Approved drawings, GTP, IEC 60044-1:2003 IS 2705	P	V	V	Record review at the time of final testing  CT ratio to be witnessed by KPTCL during final inspection
	NITRILE GASKET	3.5		100/						
	Dimension Check, Thickness	Measure	A .	10% at random		Within tolerance	P	V	V	
	Shore Hardness check Tensile strength	Measure Measure	Α	-	Technical spec,	70 ± 5 IRHD	P	V	V	
	Elongation at break	Measure Measure	A A	1	ISO 7619-1	12.5 N/mm <sup>2</sup> min 250% min	P P	V	V	
	Compression Set test	Measure	A	]	ISO 815 ISO 37	20% max	P	V		Physical verification and record review at the time tanking stage
1.10.6	Accelerated aging in air&oil at 100±2 °C for 72 Hrs.	Measure	<b>A</b> '	One sample per lot per size	ISO 37 ISO 3865 IS 11149 —IS 2751 IS 4253	Max change in harness - 10 IRHD/Change in weight - 5 to 8.5%  Change in thickness - 4% max  Change in width & length - 0.2% max	P	V	v	inspection
1.10.7	Resistance to insulating oil	Measure	A		-,	As per IS 4253	Р	v	V	
1.11	TERMINAL CONNECTOR									
1.11.1	Visual Check	Visual	В	100%		No surface defects	P	V	V	
1.11.2	Check for dimension	Measure	В	100%	Technical spec,	Dimension within tolerance	P	V	v	
1.11.3	Routine Test a) Tensile test b) Resistance test c) Galvanising test (if required)	Measure	В	One sample of each size per lot	Approved drawings, GTP, IS 5561	as per IS 5561	P	V	v	Record review at the time of final testing

	·	•			Manufacturii	ng Quality Plan for 110kV and 66kV power transformer	up to 31	.5MVA	capacit	y. (Revised)
							Abbrevia	ations:	· : M - T	ransformer manufacturer ; C- Customer (KPTCL). ess ; V- Verification (Review)
Sl. No.	Components and Operations	,					, <i>I</i>	Agency		
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	М	С	Remarks
1.12	MARSHELLING BOX/COOLER CONTROL CABINET			·						
1.12.1	Check workmanship of inside, ferruling, labeling, paint shade, internal arrangement, Check of BOM etc.	Visual	В			As per approved drawing	Р	V	V	
1.12.2	Dimension, paint thickness, adhesion test, paint shade etc. check of dry film thickness.	Measure	В	100%	Technical spec, Approved	As per approved drawing	P	V	V	Record review at the time of final testing. Type test report from any NABL lab not older than 5 years for Degree of
1.12.3	Routine Test a) HV test at 2kV for 1 min between live terminal/earth b)IR at 500V for 60 sec c) Functional test & verify wiring d) Accuracy of indication	Measure	В		drawings, GTP	a)1 min withstand c)Firm and aesthetic other all as per approved drawing	Р	V	v	Protection (IP 55) shall be verified during Final isspection.  Performance to be checked during final inspection.
1.12.4	Degree of Protection (IP 55) for Marshalling Box						P	V	V	
1.13	a) RTCC b) Digital RTCC relay if applicable:-						P	V	v	
1.13.1	Surface cleaning before painting	Visual	В			No surface defects				
1.13.2	Verification of BoQ&Dimension check	Visual	В			As per approved BoQ & dimensions within tolerance	P	V	V	
1.13.3	Check of paint shade, paint film thickness and paint film adhesion	Measure	В		Technical spec,	Shade as per approved drawing and GTP	P	V	V	Record review at the time of final testing.
1 10 4	Functional check- manual and electrical operation as per scheme	Visual	В	100%	Approved drawings &	Operation satisfactory	P	V	V	Record review of transformer monitoring device (ITCS) at the time of final inspection.
1.13.4		Visual	В		GTP	As per approved drawing	P	V	V	
	Checking for wiring routing	Visual	В	1		As per approved drawing	P	V	V	-
1.13.6	Make/type of instrument/component	Measure	В	-		Withstand 2kV for 1 min	P	v	V	
1.13.7		Measure	В	-		More than 100 Kilo ohm	P	V	V	· · · · · · · · · · · · · · · · · · ·
1.13.8	Measurement of IR by 500 Volt IR test  Check on Digital RTCC Relay/automatic voltage regulating relay (VAR) if applicable	Modesure					P	v	V	
1.13.9.1	Voltage and current measurement	Measure	В		Technical spec,		P	T v	$\frac{v}{v}$	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	Check of panel switches	Measure	В	100%	Approved	Technical spec, Approved drawings & GTP	P	V	V	Record review at the time of final testing
1.13.9.3	Check for function of communication interface	Measure	B -	100,0	drawings & GTP	GIF	P	v	v	
1.13.9.4	Test of complete function including tap, position indicator & raise and lower command and all other functionality check.	Measure	В						1	
1.14	AIR CELL - if applicable								<del>                                     </del>	†
1.14.1	Check of make & surface finish of complete air cell	Visual	В			No surface defects	P	V	V	-
1.14.2	Check of dimension & leakages	Measure	В	100%	Technical spec,	Dimension within tolerance	P	V	V	-
1.14.3	a) 10 times Inflation and deflation @ 10kpa.	Measure	B		Approved drawings & GTP IS 3400	No leak, no opening of joints	P	V	V	Record review at the time of final testing
1.14.4	Routine tests on basic fabric a) Oil side coating compound b) Air side inner/outer coating c) Rubber coating inner/outer d) Coated fabric	Measure	В	One sample per lot of raw material	BS 903		P	V	V	ಮು.ಇಂ. (ವಿ)

ಮು.ಇಂ. (ವಿ) ಮುಖ್ಯ ಇಂಜಿಸಿಯರ್ (ಬೆದ್ಯುತ್ತು ಆರ್.೩ಡಿ ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾವೇರಿ ಭವನ, ಬೆಂಗಳೂರು-560 000

\$ A					Manufacturi	ing Quality Plan for 110kV and 66kV power transfo	rmer up t	o 31.5N	IVA cap	pacity. (Revised)
Sl. No.	Components and Operations						Abb:	reviatio ub supr	ns: lier : M	I- Transformer manufacturer ; C- Customer (KPTCL). Vitness ; V- Verification (Review)
								Ager	ıcv	) p
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	T	T	Remarks
1.15	ROLLER ASSEMBLY									
1.15.1	Visual & paint check	Visual	В			Free from surface defect	p			
1.15.2	Dimensional check	Measure	В	One sample per lot	Approved drawings & GTP	Within tolerance	P	+	V	·
1.15.3	Mechanical properties and chemical composition of raw material used for shaft and roller forging	Measure	В	1 sample /heat treatment batch	IS 5517/IS 2004 IS 28 IS 8500	For shaft as per MS EN8, BS 970-1 For roller wheel of cast iron IS 210 For roller wheel of Cast steel IS 1030	P	v	v	Record review at the time of final testing
10.07	OIL & WINDING TEMPERATURE INDICATOR (LOCAL & REMOTE)									
	Check of Type, Make & healthiness	Visual	В			N				
1.16.2	Dimensional check	Measure	В		-	No visible surface defect	P	V	V	
1.16.3	Calibration check & verify accuracy <sup>0</sup> C	Measure	В		_	within tolerance as per approved drawing	P	V	V	
1.16.4	2kV HV test @ 1 min for terminals & earth	Measure	В	100%	Technical spec, Approved drawings & GTP	Accuracy better than ±3/ ± 1,5% of FSD (ieema)	P	v	v	Record review at the time of final testing
1.16.5	Switch operation check Continuity of contacts for Alarm & Trip and all other contacts.	Measure	В			Should withstand for 1 min  Should be ±2.5 °C of switch setting	P	V	V	- Total Total at the time of final testing
	RTD TYPE REMOTE AND WINDING TEMPERATURE INDICATOR					Colouid be 12.3 Col switch setting	P	V	v	
1.17.1	Check of healthiness	Visual								
1.17.2	Dimensional check	Measure	В			No visible damage	P	V	V	
1.17.3	a) Calibration check b) HV Test (2000 V for one minute) c) Insulation resistance at 500V for 60 sec d) Sensor resistance/switch contact operation	Measure	В	100%	Technical spec, Approved drawings & GTP	Dimension within tolerance  a) 2. ± 1.5% of FSD  b). Withstand for 1 min  c) withstand for 1 min.	P	v	v	Record review at the time of final testing
1.18 I	PRESSURE RELIEF VALVE  ype & Make					d)operation within ± 2° C of setting				
	organization of the control of the c	Visual Measure	В			As per approved drawing & GTP				
1.18.3	peration check- Air pressure and Liquid pressure test		В			within tolerance as per approved drawing	P P	V	V	
	eakage test 75% operating pressure	Measure Measure	В		Technical spec,	Operate at specified pressure ±0.07 kg/cm <sup>2</sup>	Р	w	v	Power Transformer manufacture
	witch contact operation test	Measure	В В	100%	Approved lrawings & GTP	No leak for 24 Hrs.	P	V	V	Power Transformer manufacturer has to witness the air pressure test, switch contact operation test and Dielectric Test
			- D		IS 2500	To be checked after operation	Р	W	v	Record review by KPTCL at the time of final testing
1.18.6 D	rielectric test between each terminals & body of PRV	Measure	В			Withstand 2kV for 1 min	P	w	v	Configuration of contacts for alarm & trip to be carried out  during final inspection
1.19 <b>M</b>	AGNETIC OIL LEVEL GAUGE									
1.19.1 Ту	/pe & make	Visual	В			As per approved drawing & free from defect	P	v		
1.19.2 Di	imension check, check for pointer movement	Measure	В			within tolerance as per approved drawing	P	v	V	
	anctional Check- Calibration check by empty and full contact	Measure	В	100%	echnical spec, Approved rawings & GTP	Check pointer position for Max, Min and center level	P	v	v	Record review at the time of final testing
1.19.4 2k	V HV test for 1 min (terminals & body)	Measure	В	er 20 (	۵)					
1.19.5 Sw	ritch/contact operation test	Measure	1	eof.13. 203	15.33	Withstand for 1 minute	P	V	V	
		2,12003011	Д	CO. 10. 11 7		Operate at Min level indication	Р	V	V	

ಮುಖ್ಯ ಇಂಜಿಸಿಯರ್ (ವಿಷ್ಯಾಸ್) ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾವೇರಿ ಭವನ, ಬೆಂಗಳೂರು–560 009

					Manufacturi	ng Quality Plan for 110kV and 66kV power transforme	r up to 31	L.5MVA	capacit	y. (Revised)
							Abbrevi	iations:	: M- Tr	ansformer manufacturer; C- Customer (KPTCL). ess; V- Verification (Review)
S1. No.	Components and Operations							Agency		3- p
		Type of check	Class of	Quantum of check	Reference document	Accepting norms	s	M	С	Remarks
1.20	BUCHHOLZ RELAY & OIL SURGE RELAY					As per approved drawing & free from defect	P	V	v	
	Type & make	Visual	В			within tolerance as per approved drawing	P	V	V	
1.20.2	Dimension check	Measure	B B			Withstand for 1 minute	P	V	V	
1	2kV HV test for 1 min (terminals & body)	Measure Measure	В				P	V	V	
	Routine Test a) Porosity & element test b) High voltage c)Insulation resistance d)Gas volume test at 5° ascending towards conservator	Measure	В	100%	Technical spec, GTP, IS 3637- 1966 (Re affirmed 2007)	<ul> <li>a) No leakage</li> <li>b) 2 KV for 1 min. withstand</li> <li>c) Min 10 MΩ by 500 V DC megger</li> <li>d) GOR - 1: 90 to 165 CC</li> <li>GOR - 2: 175 to 225 CC</li> <li>GOR - 3: 200 to 300 CC</li> <li>e) GOR - 1: 70 to 130 CC</li> </ul>	P	v	v	Record review at the time of final inspection. Continuity for alarm and trip test to be carried out during final inspection.
	e)Loss of oil & surge test/float operation f)Continuity of contacts for alarm & trip					GOR - 2: 75 to 140 CC				
	i)Continuity of contacts for alarm & trip					GOR - 3: 90 to 160 CC				
	GAS COLLECTING DEVICE	Measure	В			within tolerance as per approved drawing	P	V	V	Record review at the time of final testing
1.21.1	Dimension Check  Pressure test/leak test	Measure	В	100%	Technical spec, Approved drawings & GTP	No leak at 0.75 kg/cm <sup>2</sup>	P	v	V	Record review at the time of infairtesting
1.00	GATE VALVE					within tolerance as per approved drawing	P	V	V	
1.22	Dimension Check	Measure	В	1 sample of one			Р	v	v	
1.22.2	Check for raw material for valve body, gate wedge, spindle & gland	Visual	В	size per lot	CBIP manual/ Technical spec,	as per CBIP manual/Approved drawings & GTP	P	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	ľ	Record review at the time of final testing
1.22.3	a) Body test at 1.5 Mpa for 2 min b) Seat test at 1.0 Mpa for 2 min	Measure by using water	В	a) 100% b) 100% c) 1%	Approved drawings & GTP		P	V	V	
1 22 1	c) Seepage at 2 kg/cm <sup>2</sup> for 12 Hr	Measure	Α	100%		As per CBIP manual & IS 778	P	V	a.V	
1.22.4	Pressure test BUTTERFLY VALVE							+	.,	
		Measure	В	1 sample per lot	:	Within tolerance	P	V	V	
1.23.1	Dimensional Check	Visual	В		AS per CBIP	No visible defects	P	V	V	
1.23.2	Visual inspection	Measure	В	1	manual,	No leak at 5kg/cm <sup>2</sup> for 30 min	P	V	V	Record review at the time of final testing
1.23.3	Pressure test through body and spindle		В	100%	Technical spec, Approved	Max o drops/ mm	P	V	V	Record review at the time of man resample
1.23.4	Pressure test diaphragm	Measure			drawings & GTF	No leak from body & spindle	P	v	v	
1.23.5	Oil seepage test (oil at 105 ±5 °C & pressure of 2kg/cm² (for 24 hrs)		В	1 sample per lo	t	Max 6 drops /min from disc  As per approved drawing	P	V	V	
1.23.6	Material composition (Disc/Housing)	Measure	В			As per approved drawing				
1.24	SILICAGEL BREATHER	Visual	В			Within tolerance	Р	v	". <b>V</b>	
1.24.1	Dimension, Type and model check, Silica gel capacity and Quality  Check of health/colour of silicagel	Measure	В	100%	Technical spec Approved	SilicaGel is blue	P	V	V	Record review at the time of final testing
1.24.2	1 1 1 1 m marting labour	Measure	В	1	drawings & GTI	No leak for 30min at 0.35 kg/cm <sup>2</sup>	P	v	v	
1.24.3	RADIATOR									
	a table in a languifications	Visual	В	1 sample per lo	t		P	V	+ v	4
1.25.1		Visual	В			No welding defect	<u>Р</u>	V	$\frac{1}{v}$	1
1.25.2	The state of the s	Measure	В			As per approved drawing	P	V	V	
1.25.3	Air procesure test on elements & Radiator assembly	Measure	В	$\exists$	Technical spec		<del>-</del> -	V	T v	Record review at the time of final testing
1.25.4	Surface cleaning of header support & bracing details by shot	Visual	В	100%	Approved drawings & GT	P Free from surface defect	P		V	4
1.25.5	blasting	Visual	В				P	V		-
1.25.6	Visual check of finish of weld and paint - Paint shade, Paint	Visual	В			As per tech spec, coating thickness more than 70 micron	P	V	V	ಮು.ಇಂ. (ವಿ) ಇಂಡಿಎಯರ್ (ವಿದ್ಯುತ್)
	thickness, DFT & Outside initi addressor core	Visual	В			No leakage	<u> </u>	ر <u>v</u>		ල දුරු දුරු (විස්) ම
1.25.8	Leakage Test				Pa	age 8 of 15		5	ian ,	3/40m - 1 2 7 2 2

ಮುಖ್ಯ ಇಂಡಿಯರ್ (ವಿದ್ಯುತ್) ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾನೇಗಿ ಜವನ, ಬೆಂಗಳೂರು–560 009

					-re-re-re-re-re-re-re-re-re-re-re-re-re-					
					Manufact	turing Quality Plan for 110kV and 66kV power transform	er up to	31.5M	VA cap	acity. (Revised)
Sl. No.	Components and Operations						Abbr S- Su	eviatio b supp	ns: lier ; M	- Transformer manufacturer ; C- Customer (KPTCL). itness ; V- Verification (Review)
								Agen	сy	, ,
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	М	С	Remarks
1.26	INSULATING OIL							-	-	
1.26.1 1.26.2	Appearance	Visual	A			Clear & transparent				
1.26.3	Viscosity at 100 °C Viscosity at 40 °C	Measure	A	,		Clear & transparent	P	V V		
1.26.4	Viscosity at 40°C Viscosity at -20°C	Measure	A				P	V	W	Transformer manufacturer oil supplier where store increation
1.26.5	Pour Point <sup>o</sup> C and Flash point deg C	Measure	A			·	P	$\frac{1}{v}$		
	Water Content	Measure	A	1			P	$\frac{1}{v}$		in the date of
1.26.6	a) For bulk supply b) For delivery in Drums	Measure	A				P	V	w	All other tests shall be witnessed by KPTCL at Transformer
1.26.7	Electric Strength (Break down voltage) a) Unfiltered	Measure	Α.	Sample per lot IEC:60296	Technical spec	&		<del> </del>	<del> </del>	manufacturer /Sub vendor premises
2.26.8	After Filtration  Density at 20 °C		A	IS 6855 & IS 6858 for	GTP IEC 60296	Parameters as per IEC 60296	P	v	w	Record review by KPTCL at the time of final testing
	Dielectric dissipation factor (Tan Delta)at 90 deg C	Measure	A	barrel			P	v	<del> </del> w	Record review by KFTCL at the time of final testing
1.26.10	Resistivity at 90 °C ohm-cm and 27 degC	Measure Measure	<u>A</u>	-			P	$\frac{1}{V}$		-
1.26.11	Total Acidity (Neutralisation value )	Measure	A	-			P	v	W	-
1.26.12	Interfacial tension at 27 °C	Measure	<u>А</u> А	1			P	V	W	
1.26.13	Total Sulphur content	Measure	A	1		•	P	V	W	7
1.26.14	Corrosive Sulphur (IEC 62535)	Measure	A	1			P	V	W	
	Oxidation stability test and presence of oxidation inhibitor  STEEL FOR FABRICATED PARTS (RAW MATERIAL)	Measure	A				P	W	V	
1.27.1	Check for finish	Visual						<del>                                     </del>		
1.27.2	Check for dimension	Measure	A A	One commis			P	l v	l v	<del>-</del>
1.27.3	Chemical composition	Measure	A	One sample per lot	Technical spec	Technical spec, Approved drawings & GTP	P	V	V	Record review at the time of tank stage inspection
1.27.4	Mechanical properties	Measure	A			1 / 11	P	V	V	and of the stage hispection
	FABRICATION OF TANK AND ACCESSORIES Welding procedure Spec (WPS) & welder qualification (for						P	V	V	
	fabrication)	Visual	Α	For all jobs		ASME Sec IX	P	v	v	
	Visual check for welding electrode (for all steel fabricated items)  Check for fit up for butt welds on tank walls, base & cover	Visual	A	1 sample of each type	Technical spec, Approved	No defect as per report	Р	v	v	
		Visual	A	100%	drawings & GTP	Check for proper welding	P	V	v	1
	DP test on load bearing welds / members.  Visual check of welding joint	Visual	A	Each Tank		Check for proper welding	P	v	w	
ı		Visual	A	5%	·	No visual defects	P	V	v	1
	Dimension check after final welding including rim flatness, position of guides & earth connection, matching of tank & cover	Measure	A	100%		As per approved GTP and drawings & CBIP standards	P	v	w	
1.28.7	Air Leakage test on assembled tank with turrets and on conservator separately	Measure	A	100%		No leakage	P	v	w	
	^,				~,					
1.28.8 d	Air pressure test and Vacuum test (AV/VT) on tank only with deflection measurement	Measure	A	Each Tank	Technical spec, Approved drawings & GTP	As per approved GTP and drawings & CBIP standards	P	V	w	To be done during tank stage inspection and Customer Inspection Point (CIP). It is required to offer tank and core coil assembly for inspection at the same time in order to save time and hence plan accordingly. All the check points and checking for proper finish of tank inside surface and checking for non existence of particles shall be compulsorily checked.
	Check for nitrogen injection points (if applicable)	Visual	Α	Each Tank		,	P	v	w	
tı	Dimension of roller mounting pad with std. fixture of roller by urning by 90 °C	Measure	A	100%			P	v	v	
	urface clearing by shot blasting	Visual	Α	100%			-		·	1
1.28.12 a)	Pheck of Paint shade Paint film thickness (inside & outside) Film adhesion test	Visual	A	100%		As per approved GTP and drawings & CBIP standards	P P	V	v	Record review at the time of final testing During <u>tank inspection</u> test at Sl No 4,7, 9,10 &11 to be witnessed and results of the other tests needs to be verified
1-/	Par / Assert 52 cts at 1475	0 5				·	1			

		•			Manufacturi	ng Quality Plan for 110kV and 66kV power transforme	er up to 31	.5MVA	capacit	y. (Revised)
							Abbrevi S- Sub s P - Perf	unnliet	r ; M- Tı W- Witn	ransformer manufacturer ; C- Customer (KPTCL). ess ; V- Verification (Review)
S1. No.	Components and Operations						<del>                                     </del>	Agency		
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	M	С	Remarks
1.00	RESIN COATED GLASS TAPE						P	v	v	
1.29	Visual and Dimension check	Visual	В	100%		Free from visual defect	P	V	V	
1.29.2	Elongation	Measure	B B		Technical	Min 200 N/mm	P	V	V	Record review at the time of core building/Core Coil Assembly
	Tensile strength, Cross Breaking strength	Measure Measure	В	One sample per	specifications,	12 months	P	V	· V	stage inspection
1.29.4	Curing Test Resin Content	Measure	В	lot	IS 15208	27 (± 3%)	P	V	V	
1.29.5	Softening point of resin	Measure	В	-		Max 200 °C	r	<u> </u>		
1.30	COOLING FAN & MOTOR ASSEMBLY						P	V	V	
	Type & Make	Visual	B				P	V	V	
1.30.2	Check of healthiness	Visual Measure	В	1	Technical	As per approved GTP and drawing	P	V	V	
	Dimensional check	Measure	В	1,000/	specifications,		P	v	V	Record review at the time of final testing
1.30.4	Routine and acceptance test	Measure	В	100%	approved GTP and drawings		P		<u> </u>	
1.30.5	Power consumption, rating test	Measure	В	1	IS2312/IS6272	1.3 kV for 1 min or 1.8 kV for 5 sec	P	V	V	***************************************
1.30.6	HV test		В	1	,	10 MΩ min with 500 V DC megger	P	V	V	
1.30.7	Insulation resistance value	Measure	В							
1.31	CONSERVATOR							v	v	
1.31.1	Properties of Material	Measure	В		, ·		P	v	v	
1.31.2	Dimensions	Measure	В		Technical specifications,		P	v	v	Record review at the time of final testing
1.31.3	Leakage Test	Test	В	1 Sample per lot	approved GTP and drawings		P	v	v	
1.31.4	Air Pressure Test	Test	В	-	and drawn go		P	v	V	
1.31.5	Check for finish of weld and paint, paint thickness	Visual	В	•						
1.32	FIBER OPTIC SENSOR ( If provided) (applicable to 66kV, 31.5MVA class power transformers)						P	V	V	
1.32.1	Visual check, check of range & dimension	Visual	В	100%	KPTCL tech spec		P	V	V	1
1.32.2	Negative full wave LI test (type test) without breakdown or flashover	Measure	В	_	2413	500kVp, gap of 25mm	P		-	Record review at the time of inspection of core coil assembly.
1.32.3	Impulse creep test (type test) without breakdown or flashover	Measure	В	One sample	ASTM D149	360 kVp gap of 25mm	P	V	V	Record review at the time of hispection of core con assembly.
1.32.4	a) PD measurement less than electric field strength of 4.7 kV/mm b) AC withstand test	Measure	В		ASTM D 2413	a) less than 10pC b) 70kV on 15 mm gap 140kV on 30 mm gap	P	v	V.	
1.33	ON LOAD TAP CHANGER*						Р	v	w	
1.33.1	Mechanical operation test of diverter switch (Endurance Test)	Measure	A				P	V	w	
1.33.2	Transition time & Sequence test	Measure	A	_		Switching time within permissible limit	P	V	w w	* Customer Inspection Point (CIP)
1.33.3	Pressure leak test, vacuum test and gas tightness test of diverter switch compartment	Measure	A		Tech spec	No leakage Satisfactory operation for 1 complete cycle	P	V	w	1) Type test reports not older than 5 years for having conducte tests @ CPRI/ERDA as per relevant IEC/IS shall be submitted
1.33.4	Mechanical test of tap selector with motor drive	Measure Measure	A A	Each OLTC	Approved drawings		P	V	W	at the time of inspection
1.33.5	Operation test and Endurance test of complete OLTC including functional check of driving mechanism.	Measure	A		GTP IEC 60214 IS:8468	Satisfactory working as per drawing Approved Satisfactory working of trip & reset	P	V	w	2) If type test reports are older than 5 years or there is change in design it is to be repeated at no extra cost to KPTCL @ CPRI/ERDA without affecting delivery schedule.  3) All routine tests and type tests shall be carried out as per
1.33.7	HV test on auxiliary circuit	Measure	A		IS:8478	Withstand 2kV for 1 min	P	V	w	KPTCL specifications
		Measure	$\frac{1}{A}$		_	Free from defects	P	V	W	-
1.33.8	Visual check of paint shade & thickness and adhesion on motor	Visual	A	Each OLTC		As per approved drawing & GTP	P	v	w	
1.33.9	drive panel									1

					Manufactu	ring Quality Plan for 110kV and 66kV power transformer	up to	31.5MV	<sup>7</sup> А сара	city. (Revised)
Sl. No.	Components and Operations						Abbre S- Sub P - Per	suppli	ier ; M-	Transformer manufacturer ; C- Customer (KPTCL). tness ; V- Verification (Review)
								Agenc	·y	
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	м	С	Remarks
1.34	Nitrogen Injection Fire Protection Systems (applicable for 10MVA and above rating power transformers)			Ċ						Witness by KPTCL at sub vendor premises.
1.34.1	All functional test	Measure	A	Each unit	-	As per Technical specification, approved drawing & GTP	P	v	w	
В	IN PROCESS INSPECTION						I	<u> </u>		
2.1	WINDING (Built up)									
2.1.1	Measure of conductor Size	Measure	A				-	P	w	Witness during Winding stage inspection and Record review at the time of final testing.
2.1.2	Check inside & Outside Diameter, unshrunk height & radial thickness	Measure	A				_	P	w	During stage inspection of winding, the following records need to be reviewed by KPTCL:  1) Test reports of CPRI/ERDA pertaining to samples of PICC/CTC drawn by power transformer manufacturer and sent
2.1.3	Calculate current density of each coil	Calculate					-	P	w	to CPRI/ERDA for all tests.  2) Test certificate of ageing of paper.  3) Thickness of press boards & permawood to be verified by
2.1.4	Weight of the windings	Weigh/ Measure		Each Winding			-	P	w	KPTCL and review of test reports on press boards & permawood.  4) The inspecting officers of KPTCL shall make dimensional
2.1.5	Check of insulation arrangement, winding direction and Transposition	Visual	A		Technical spec,		-	P	w	checks physically on each and every transformer on its winding during stage inspection at manufacturer's place and the values shall be recorded by the inspecting officers as per Annexure -1 attached to this standardized MOP
2.1.6	Check arrangement of Fibre Optic Sensor (FOS)	Visual	В		drawing & GTP		-	P	w	
2.1.7	Testing of winding: Continuity tests on winding	Visual	Α				-	P	w	
2.1.8	Brazing procedure & Brazer qualification	Verification	В	All Brazers		Technical specification & GTP	-	P	w	
2.1.9	Check brazing of tap leads, if finished (Else same shall be witnessed during core coil assembly stage)	Visual	A				-	P	W	
2.1.10	Check on the finished coil a) Chemical composition of copper b) Tensile strength c) elongation d) Resistivity	Measure	A	Each Winding			-	Р	V*	V* - Customer Inspection Point (CIP): PICC/CTC Samples for each transformer shall be taken in presence of customer during winding stage inspection and sent to CPRI/ERDA for all tests including chemical composition, Tensile strength,
2.1.11	Resistance of the winding	Measure	A	Each Winding	Technical spec & GTP		-	Р	w	elongation & Resistivity . Manufacturer has to submit test reports to KPTCL for verification during final inspection. Any excuses from the manufacturer refraining from submission of test reports during final inspection will not be entertained.
2.1.12	Visual inspection of brazed joints & transposition	Visual	A				-	Р	w	Assessment of I <sup>2</sup> R loss at 75°C is to be carried out during this
2.1.13	Lead & coil identification & marking	Measure	A				-	Р	w	stage inspection. Winding resistance of all the windings shall be measured and I <sup>2</sup> R loss to be assessed by calculation, for all transformers
2.1.14	I <sup>2</sup> R loss assessment	Calculate	A,				-	Р	w	

ಮುಖ್ಯ ಇಂಜನಿಯರ್ (ವಿದ್ಯುತ್) ಆರ್.ಟಿ. ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಕಾವೇರಿ ಭವನ, ಬೆಂಗಳೂರು–560 009

					Manufacturi	ng Quality Plan for 110kV and 66kV power transformer	up to 31	.5MVA	capacit	ty. (Revised)
	•						Abbrevi	ations:	· : M- T	ransformer manufacturer; C- Customer (KPTCL). less; V- Verification (Review)
Sl. No.	Components and Operations							Agency		
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	M	С	. Remarks
2.2	CORE BUILDING AND FRAME ASSEMBLY									
2.2.1	Check of frame assembly/core assembly, straightness	Visual	В	· v			-	P		During stage inspection of core assembly, the following records need to be reviewed by KPTCL:  1) Test reports of CPRI/ERDA pertaining to samples of CRGO
2.2.2	Check arrangement of Insulation	Visual	В		٤		-	P	W	drawn by power transformer manufacturer and sent to CPRI/ERDA for all tests.
2.2.3	Check window width and window height and diagonal of frame and position of oil ducts	Measure	В				-	P	W	2) Thickness of press boards & permawood to be verified by KPTCL and review of test reports on press boards & permawood.
2.2.4	Check core stacking operation, Individual step stack dimensions, Number of steps	Measure	A				-	P	w	3) Record review of resin coated glass tapes 4) The inspecting officers of KPTCL shall make dimensional checks physically on each and every transformer on its core.
2.2.5	Check of compressed stack height/ thickness	Measure	В	Each	· ·			P	<del></del>	during stage inspection at manufacturer's place and the v
2.2.6	Check assembly of tensile bolt	Visual	В	Transformer			-	P P	w	shall be recorded by inspecting officers as per Annexure -1 attached to this standardized MQP
2.2.7	Check binding of adhesive tape	Visual	В				-	P	W	
2.2.8	Check of waviness of core yoke, burr	Measure	В		As per approved				w	V* - Customer Inspection Point (CIP) - CRGO Samples for
2.2.9	Visual Check of overall dimension of built up core	Measure	В		design,		-	Р	w	each transformer shall be taken in presence of customer during
2.2.10	Check of insulation resistance of core & frame by 2kV IR Tester/core bolt insulation test/HV test between core and clamps	Measure	A		Technical specification & GTP	As per approved design, Technical specification& GTP	-	P	w	core assembly stage inspection and sent to CPRI/ERDA for all tests. Any excuses from the manufacturer refraining from submission of test reports during final inspection will not be
2.2.11	No load loss/ core loss assessment	Calculate	A		_		-	P	W	entertained.
2.2.11	Calculation of Flux density.	Calculate	A				-	P	W	Assessment of core loss shall be carried out.
2.2.13	Assessment of preliminary core loss by calculation.	Measure	A		]		-	P	W	
2.2.14	a) Check of damages to core b) Specific core loss c) Stacking factor d) Surface IR e) Minimum Polarisation in Tesla @ field strength	Measure	A				-	Р	V*	shall be carried out during the Sample test at CPRI/ERDA for the samples drawn by KPTCL inspecting officers.
	Accelerated aging test	Visual	A				-	P	W	
2.2.15	Assembly of limb Insulation & plates Rectangularity of Core Assembly	Visual	A				-	P P	W W	4
2.2.16	Check for Overlaps & air gap at joints	Visual	A		-			P	W	
2.2.18	Leaning of Core	Visual Visual	A A		7			P	W	4
2.2.19	Earthing of Core Limb Clamping & Binding	Visual	A				<del>  -</del>	P	W	
2.2.20	CORE & COIL ASSEMBLY				<del> </del>		1		W	Customer Inspection Point (CIP) -
2.3.1	Check of level of bottom yoke, coil dimension, bottom insulation,	Visual	В				-	P		To be witnessed by KPTCL and Record review of resin
2.3.2	top insulation Check Auxiliary limb support assembly ( if applicable)	Visual	В	]			-	P P	W	coated glass tapes.
2.3.3	Check winding assembly	Visual	В	-			-	P	W	1
2.3.4	Check assembly of the top voke and core joints	Visual Visual	B B	-				P	W	It is required to offer tank and core coil assembly for inspection at the same time in order to save time and
2.3.5	Check assembly of the magnetic shields (if applicable) Check insulation parts, lead cable and copper tube	Visual	В	1				P	W	mapection at the same time in order to save time and
2.3.7	Check insulation parts, read cashe and expertures  Check insulation resistance between core and frame by 2kV IR tester, insulation between coil, coil to earth insulation, core and frame to yoke bolts (if applicable), yoke insulation test	Measure	A	Each Transformer			-	P	w	
2.3.8	Overall Dimensions, clearance between the coils, Lead termination, Lead placements & clearances, Lead lengths, coil dimensions.	Measure	A		As per approved design	d As per approved design		P	w	



			***************************************		Manufactu	ring Quality Plan for 110kV and 66kV power transforme	er up to	31.5MV	А сара	acity. (Revised)
Sl. No.	Components and Operations						Abbre S- Sui	viation suppli	s: er;M	Transformer manufacturer; C- Customer (KPTCL).
							Agency			3 0
		Type of check	Class of Check	Quantum of check	Reference document	Accepting norms	s	М	С	Remarks
2.3.9	Final inspection of core & coil assembly  - Check for completeness  - Check for cleanliness  - Check for absence of sharp edges  - Check placement of lead support assembly  - Check of insulating distance between low  voltage connections and other parts to earth  - Final locking	Visual .	A				-	Р	w	Customer Inspection Point (CIP) To be witnessed by KPTCL
2.3.10	Visual check for intercoil insulation	Visual	Α	Each			-	P	W	-
2.3.11	Lead & coil identification & marking.	Visual	Α	Transformer			-	P	w	
2.3.12	Brazing / Crimping of Joints/coil support	Visual	Α		As per brazing procedure	Shall be smooth and no sharped age	-		w	
2.3.13	Ratio test with tap switch	Measure	A				-	P	w	-
2.3.14	Magnetic balance test	Measure	A		As per IS 2026 / IEC 60076		-	P	w	
2.3.15	Magnetizing current test	Measure	Α				-	P	w	
2.3.16	Alignment of Spacers/Blocks & Tightness	Visual	Α			Aligned	-	P	w	7
2.4	DRYING OF ACTIVE PARTS AND TANKING									
2.4.1	Verification of vacuum achieved	Measure	В				<del>  -</del>	P	v	
2.4.2	Verification of temperature achieved/oven temp, vapour temp	Measure	В				-	P	V	
2.4.3	Check for intermediate pressure reduction	Measure	В	Each	As per approved	er en	-	P	V	1
2.4.4	Check degree and duration of fine vacuum	Measure	В	Transformer	design & drawings		-	P	v	
2.4.5	Moisture extraction rate / amount of water extracted	Measure	В				-	Р	V	
	Check VPD final parameter	Measure	В			•	-	P	V	
	Cleanliness of the Tank	Visual	В			_	P	v	V	Record review at the time of pre-Tanking and assembly
	Electrical clearances	Measure	В			-	P	v	v	
2.4.9	Height of outer coil after pressing	Measure	В		ath (	<u>-</u>	P	v	v	~,
2.4.10	Clamping of coils	Measure	В			-	Р	v	V	*
	Core Coil Assembly locking  Clearances with Tank, dimensions	Measure	В			-	Р	V	V	
2.4.13	Quantity of oil	Measure Measure	B B			- <u>-</u>	P P	V	V	
2.4.14	Earthing connections	Measure	В				P	V		
2.5	SETTLING TIME & OIL LEAK TEST									
2.5.1	Before start of high voltage test	Visual	В	Each Transformer	As per approved design & drawings & GTP	As per approved design & drawings & GTP	-	Р	V	Record review at the time of final testing

					Manufacturi	ng Quality Plan for 110kV and 66kV power transfo	ormer up to 31.5	5MVA c	apacity	7. (Revised)
							Abbrevia	tions:	. W. Two	ansformer manufacturer ; C- Customer (KPTCL). ss ; V- Verification (Review)
No.	Components and Operations						; <b>A</b> ;	gency		3 0
		Type of check	Class of	Quantum of check	Reference document	Accepting norms	s	М	С	Remarks
			CHCCE							
C F	INAL INSPECTION TESTING	Measure	A							
.1 F	ROUTINE TESTS			i.			-	P	w	
1.1 I	Dimension check as per the approved assembly drawing, Minimum clearance between phase bushings and each bushing to earth.	Measure	А				-	P	w	Customer Inspection Point (CIP):  1) All routine tests and acceptance tests shall be condu
		Measure	A					P P	$\frac{w}{w}$	as per relevant IS/IEC/Technical specification of KPTC
1.2	Measure of winding resistance all windings	Measure	A	-				P	w	
.3	Measure of PI and IR values  Measure of voltage ratio of all taps, Polarity	Measure	A	{						
.4	Measure of voltage ratio of all taps, Folkers Vector Group verification for 3 phase Transformers	Measure	A	1			-	P		2) The inspecting officers of KPTCL after satisfying
1.6	Magnetic balance test at 415 Volta ( for 3 ph transformers only)	Measure	A	-				Р	w	the dimensional check may take up the mai accept
_	Measure of insulation power factor (Tan delta) and capacitance of	Measure	A					P	W	on each of the subsequent transformer should be with that of the type tested transformer as per Annex
1./ 1	winding Measure of insulation power factor (Tan delta) and capacitance of	Measure	A					P	W	attached to this standardized MQP.
.8	hushing	Measure	В	7				P	w	3) Test reports of CPRI/ERDA for testing sample
	Measure of no load current with 415V, 50Hz AC supply  No load loss & current measure at 90, 100, 110% excitation	Measure	A	1			-	P	vv	PICC/CTC & CRGO drawn by KPTCL officers dufing
	of Lord loose and impedance voltage at normal and	Measure	A				-	P	w	inspecting officers for verification and any excuses the manufacturer refraining from submission of test r during final inspection will not be entertained.
11	larger tank and Positive phase sequences impedance						-	P	<u> </u>	during must inspection will not be entered
	measurement on three phase transformers.	Measure	A					P	W	4) The following is to be verified:-
.12	Tests on OLTC	Measure	A				-	P	w	Desching CT ratio is to be witnessed.
.13	Separate source voltage withstand test Lightening impulse test on line terminals (applicable for power	Measure	A					P	w	h) Marshalling box performance and IP 55 test report and
1.14	Lightening impulse test on line terminas (applicable to pour transformers above 72.5kV voltage class)			-					w	d controlling how is to be checked.
	Induced over voltage withstand test.	Measure	A	<b>-</b>		+ 0	-	P	\ <u> </u>	c) Configuration of contacts for alarm and trip of pressur
1.15	Repeat no load loss test, IR value, Tan delta test after HV test	Measure	A					_	117	valve is to be carried out. d) Record review of air pressure test and switch
	Repeat no load loss test, in value, rail detected sample as per Tests on transformer oil including DGA on selected sample as per IS:9434/IEC:567, before and after temp rise test and at final stage	Measure	A	Each	IS 2026/		-	P		operation test of Pressure Relief valve  e) Record review of test reports in respect of the following
1.17	IS:9434/IEC:567, before and after temp rise test and at 2kV before dispatch.  Isolation test of core to frame, core and tank, frame to tank at 2kV	Measure	A	Transformer	IEC 60076		-	P	w	i) Condenser bushing. ii) Porcelain bushing.
1.18	Isolation test of core to frame, core and talk, frame to talk, frame to AC for 1 min  Sweep Frequency response Test (SFRA) - Intially SFRA test to be conducted at power transforme									iii) Bushing CT iv) Buchholz relay & Oil surge relay.
1.19	manufacturer's premises during final inspection.  Manufacturer shall arrange to repeat SFRA test at site at his cos Manufacturer shall arrange to repeat SFRA test at site at his cos Manufacturer shall arrange to repeat SFRA test at site at his cos	Measure	A					P	w	vi) Marshalling box/ Cooler control cabinet vii) RTCC and digital RTCC relay. viii) Air cell. ix) Roller assembly.
	both of the SFRA tests also to be collected for lutture competers and handed over to the concerned SEE(RT) of respective							+-	$\frac{1}{w}$	x) oil and winding temperature indicator (Local and remo
	Transmission Zone.  HV withstand test on auxiliary equipment wiring after assembly by		В	~, :			-	P	w	xii) pressure relief valve xiii) Magnetic oil level guage
.1.20	applying 2kV  Oil leakage test on main tank as per CBIP (Tank leak test at 5 psi		A				-	P	w	xiv) Gas collecting device.  xv) Gate, Globe and butterfly valves
.1.21	(35 kN/m2) for 12 hrs with oil.)						-	P	w	xviii) Insulating oil.
3.1.22	Calculation of regulation at rated and at unity, 0.9 and 0.8 lagging pf.	Measure	A	_			-	P	w	xix) cooling fans and motor assembly.  (xx) oil circulating pump
3.1.23	Auxiliary losses (fans)	Measure	A			`				xxi) oil flow indicator xxii) Fiber optic sensor( if provided) xxiii) Settling time and oil leak test.
	Zero Sequence impedance test	Measure	. A				-	F	w   v	xxiv) Test certificate received from supplier for tests on xxv) Test reports for corrosive sulphur detection test ASTM D 1275 subjecting oil for 150 deg C for 48 hrs.
3.1.24	Zeio Sequence Impounded				· ·					ಮು.ಇಂ. (ವಿ)
	Page 14 of 15							Ĉ	ಯುಖ್ಯ	ಇಂಜಿನೆಯರ್ (ವಿದ್ಯುತ್ತಾ) ಆರ್.೩೩ ಮತ್ತು ಆರ್.೩ಡಿ, ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ.
								6	೨ರ್.ಟಿ. ಇವೇಗಿ	. ಮತ್ತು ಆರ್.&ಡ, ಕ.ವ.ಪ್ರ.ಹ.ಡ. ಭವನ, ಬೆಂಗಳೂರು–560 009

* * * * * * * * * * * * * * * * * * *					Manufacturing Quality Plan for 110kV and 66kV power transformer up to 31.5MVA capacity. (Revised)						
Sl. No.	Components and Operations						S- Sub	riations supplic form;	er ; M-	Transformer manufacturer ; C- Customer (KPTCL). ness ; V- Verification (Review)	
			L					Agenc	у		
			Class of Check	Quantum of check	Reference document	Accepting norms	s	s m c		Remarks	
3.2	TYPE TESTS AND SPECIAL TESTS							ļ			
3.2.1	Temperature rise test at min tap (DGA before and after test)	Measure	A	100% to be conducted at manufacturer's premises and witnessed by KPTCL authorities.			-	Þ	w	(*) Customer Inspection Point (CIP) :- Type test and Special test:- 1) Dynamic short circuit test 2) Temperature rise test 3) Lightning impluse voltage withstand test (for power transformers upto 72.5kV)	
3.2.2	Measure of harmonics of no load current	Measure	A	100% to be conducted at manufacturer's premises and witnessed by KPTCL authorities.	IS 2026/ IEC 60076		-	Р	w	The above mentioned Type test reports and Special test report (Dynamic Short circuit test) of the power transformers of the same rating and voltage class as that of the offered transformer and not older than 5 years issued by CPRI/ERDA laboratory shall be furnished at the time of Final inspection.  The design similarity of offered transformers and the tested	
3.2.3	Measure of Noise level	Measure	A	100% to be conducted at manufacturer's premises and witnessed by KPTCL authorities.	t t	.3	-	P	w	transformer whose Tests reports are furnished has to be proved by the power transformer manufacturer. In case, the design similarity of offered transformers and the tested transformer whose Test reports are furnished could not be proved by power transformer manufacturer, then manufacturer has to conduct the Type Tests and special test on 1st Unit of offered Transformers at KEMA/CPRI/ERDA Laboratory without affecting the Delivery Schedule and at no extra cost to KPTCL.	
3.2.4	Dynamic short circuit withstand test	Measure	A	One no. on each rating*			-	P	w	In case the facility for conducting temperature rise test at	
3.2.5	Lightening impulse voltage withstand test (with chopped wave) (applicable for power transformers upto 72.5kV voltage class)	Measure	A	One no. on each rating*			-	Р	w	CPRI/ERDA laboratory is not available, the temperature rise test reports witnessed by Authorities of CPRI/ ERDA/State or central utilities at the manufacturer's facility will be accepted	
3.3	SPECIAL TESTS (OPTIONAL)									In case type test reports / Dynamic short circuit test are older than five years, type tests and dynamic short circuit test shall	
3.3.1	Degree of Protection (IP 55) for control cabinets and RTCC panels, OLTC driving mechanism, terminal boxes of PRV, MOG, Buchholtz relay, pump motors, fans etc.						-	Р	v	be conducted on the first unit at CPRI/ERDA without affecting the delivery schedule and at no extra cost to KPTCL.  Further, Temperature rise test shall be carried out on all the transformers at manufacturer's premises and witnessed by KPTCL authorities without affecting the delivery schedule and at no extra cost to KPTCL.	
D	PACKING AND DESPATCH									,	
4.1	Pre shipment check- oil tightness, proper blanking of all opening.			, ,		`	-	Р	-		
4.2	Installation and checking of electronic impact recorder						-	P			
4.3	Verification of completeness of all accessories and check for soundness of packing of all accessories and fittings						-	P	-		
4.4	Level of insulating oil along with recording temperature							P			

Chief Engineer (Electy)

RT & R&D, KPTCL and

Chairman, MQP standardization Committee

enist pala disease di mandra di				*
				*