

**KPTCL's Response to Preliminary  
Observations of KERC on APR FY18  
and ARR for FY20-22 (MYT Period)**

**(KERC Letter dated 12.12.2018)**

BEFORE THE KARNATAKA ELECTRICITY REGULATORY COMMISSION  
AT BANGALORE

IN THE MATTER OF:

Providing response to the Preliminary Observations of KERC on the Annual Performance Review for FY-18 and Annual Revenue Requirement and Expected Revenue from Charges of the Transmission Licensee for FY20, FY21, FY22 and Transmission Tariff Applications of KPTCL.

AND

IN THE MATTER OF

Karnataka Power Transmission Corporation Limited (KPTCL)  
Kaveri Bhavan,  
Bengaluru-560 009

..... Applicant

AFFIDAVIT

1. I, H. Manjunath, S/o A.R.Hanumanthappa, aged 59 years, working as Financial Advisor(Regulatory Affairs), KPTCL, Kaveri Bhavan, Bengaluru-560009 do hereby solemnly affirm and state as follows:-
2. I am incharge of Regulatory Affairs section, KPTCL, Corporate Office, Kaveri Bhavan, Bangalore-560009 duly authorized to make this affidavit.
3. The Statement made in schedule " A" annexed to the Preliminary Observations of KERC on the Annual Performance Review for FY-18 and Annual Revenue Requirement and Expected Revenue from Charges of the Transmission Licensee for FY20, FY21, FY22 and Transmission Tariff Applications of KPTCL. having pages from 1-101, is now shown to me and marked with letter " A" are true to my knowledge and statements made in schedule "A" are based on information I believe to be true .
4. Solemnly affirm at Bengaluru on this day 22<sup>nd</sup> December 2018 that the contents of above affidavit are true to my knowledge, No part of it is false and no material concealed there from.

Bengaluru - 560009  
Dated: 22.12.2018.


SWORN TO BEFORE ME

*H. Manjunath*  
B. CHITRA, B.A.L., LL.B.,  
ADVOCATE & NOTARY PUBLIC  
GOVT. OF INDIA  
# 5/1, 1st Floor, 3rd Cross  
Eerappa Reddy Layout, Banaswadi Road  
BANGALORE - 560 033.

Deponent

*H. Manjunath*  
ಆರ್ಥಿಕ ಸಲಹೆಗಾರರು  
ನಿಯಂತ್ರಣ ವ್ಯವಹಾರಗಳು  
ಕವಿಪ್ರನಿನಿ, ಕಾವೇರಿ ಭವನ,  
ಬೆಂಗಳೂರು - 560 009

22 DEC 2018



**KARNATAKA POWER TRANSMISSION CORPORATION LIMITED**

<b>Sl. No</b>	<b>Clause No</b>	<b>Preliminary Observations made by KERC</b>	<b>KPTCL Response</b>
<b>A. Observations on APR for FY18:</b>			
1.	1.a	<p><b>Reactive Power Compensation and restoration of failed Capacitors:</b> The No. of capacitors not working has remained at 162 at end of 2nd Quarter of FY19 which is the same as that of the previous quarter. There is no improvement in restoration of failed capacitors. KPTCL shall prioritize repairs and replacements of capacitors not working. KPTCL is not complying to the directions issued. Action plan in this aspect shall be submitted.</p>	<p>KPTCL is giving priority for replacement of capacitor banks as can be seen from the statistics provided by KPTCL in the Review meetings. In the first quarter KPTCL has restored 39 Nos (259.82 MVar) against 33 failed. In the Second Quarter 35 Nos are restored (148.86 MVar) as against 35 failed. At the same time No of Installed capacitors have increased from 1247 Nos at the end of first Quarter to 1309 Nos at the end second quarter and 1344 Nos. at the end of the third quarter.</p> <p>It is a coincidence that the capacitor banks not working remained at the same level for both the Quarters. Further, the improvement in the status of working capacitors in the last seven quarters is indicated in the Table as per <b>Annexure-1</b>.</p>
2	1.b	<p><b>Transmission System Availability (TSA)-Monthly report:</b> The Commission has noted that though the availability is over 99%, some of the wind generators in Basavanabagewadi and Itagi have brought to the notice of the Commission that due to non-</p>	<p>The issues pertaining to Basavanabagewadi has been resolved and subsequently there are no such cases of forced outage of generators on account of transmission network availability. In the case of Itagi, KPTCL has taken up improvement works to reduce overloading of Itagi Station.</p>

		<p>availability of the Transmission network, the wind generators are directed to shut down the generation, resulting in huge loss in generation of energy. Hence developers have requested the Commission to direct KPTCL to make good the loss in generation.</p> <p>Therefore, the KPTCL shall examine and provide details of all such cases (Transmission line or Sub-Stations) of forced outages of the generators for want of transmission network and submit suitable action plan to address them suitably.</p>	<p>This will also ensure evacuation of wind generation. Further, it is to be noted that the availability is worked on annual basis as per KERC regulation. Also KPTCL is taking up green corridor projects to facilitate evacuation of green power in the State as indicated in replies to para B (9a).</p>
3	1.c	<p><b>Implementation of Intra State ABT:</b> KPTCL has to furnish the financial adjustments made between ESCOMs during the implementation of intra-State ABT.</p>	<p>The details furnished by CEE (SLDC) is enclosed as per <b>Annexure-2</b>.</p>
4.	1.d	<p><b>Study conducted (Man Power study):</b> KPTCL has been furnishing the same status for the last couple of years. The explanation provided by KPTCL is not satisfactory and it shall submit a time bound action plan.</p>	<p>KPTCL has already reviewed the recommendations made by the Internal Committee and is in the process of finalising the same. KPTCL will be implementing the recommendations as per the Report by 31st March 2019.</p>
5	1.e	<p><b>Prevention of Electrical Accidents:</b> It is submitted by the KPTCL that, it has rectified 164 hazardous locations as against 779 identified locations at the end of the 2nd Quarter of FY19. The Commission notes that only 21%</p>	<p>As per the directions of the Hon'ble Commission in the proceedings of review meeting for the second quarter of FY19, KPTCL is taking necessary action to rectify hazardous locations</p>

		of identified hazardous locations have been rectified. KPTCL shall provide suitable action plan to rectify all the hazardous locations, in order to avoid accidents.	to avoid accidents. The Zonal Chief engineers are regularly reviewing the works as per the action plan already submitted to KERC.
6.	2	<b>Revenue Gap/ Surplus for FY18:</b>	
	2.(i)	<p>The KPTCL, in its application filed for approval of the Annual Performance Review for FY 18, has claimed a net gap of Rs.417.82 Crores as per Table-21 and Table-22 and has requested the Commission to allow recovery of the gap from the ESCOMs by carrying forward the gap to the ARR of FY20.</p> <p>The same is not included in the ARR for FY20. Further, as per Format-A1, the KPTCL has arrived at a surplus of Rs.212.14 Crores for FY18, but the same has not been carried forward to the ARR of FY 20.</p> <p>Thus, there is inconsistency in arriving at the deficit/surplus for FY18. KPTCL shall furnish the correct amount to be considered for the approval of APR for FY18.</p>	<p>The Format A1 is as per the Standard Format provided in KERC (Tariff) Regulations, 2000. However the deficit of Rs 417.82 Cr arrived for FY 18 is shown in Table 27 in page No. 44 of the MYT application.</p> <p>The correct amount of ARR for FY 18 Rs.3277.35 Cr as filed in the APR application, Table 21, Page 35. As such there is no inconsistency in filing.</p>

7	2.(ii)	<p><b>Additional Employee Cost:</b></p> <p>The KPTCL, in its application for approval of APR for FY18, has claimed an amount of Rs.333.65 Crores towards additional employees cost for FY18. This amount includes an amount of Rs.140.91 Crores as arrears of pay revision with effective from 01.04.2017. As per the audited account of KPTCL for FY18, out of Rs.712.06 Crores of salary expenditure, an amount of Rs.140.91 Crores has been included as provisions towards arrears of revision of pay scale with effect from 01.04.17. The KPTCL shall furnish the details of actual amount of additional employee cost incurred towards payment of pay revision arrears from 1.4.17 to 31.3.18, besides furnishing the computation sheet for the claims of Rs.140.91 Crores, included in the salary account during FY18.</p>	<p>KPTCL has revised its employees and Officers pay with effect from 01/04/2017. The provision has been made to that effect in the Accounts based on the information obtained from each accounting Unit. KPTCL has designed a separate Annexure to March Final Accounts to collect group-wise Officials details with respect to existing pay and revised pay. Based on the data obtained from Accounting Units provision towards arrears of pay has been made. Computation of Provision amount is enclosed as <b>Annexure-3</b>.</p> <p>As against the provision made, actual amount paid towards arrears of pay is Rs.158.57 Crore. Zone-wise and administrative Office-wise arrears paid details are enclosed as <b>Annexure-4</b>.</p>
8.	2.(iii)	<p><b>Provision for Taxation:</b> The KPTCL, in its filing as per the audited accounts, for FY18, has claimed an amount of Rs.574.52 Crores towards provision for taxation by including an amount of Rs.170.02 Crores as current year's income tax and Rs.414.50 Crores against deferred tax liability. The KPTCL shall furnish the details of actual amount of income tax</p>	<p>The Corporate Income Tax has been computed based on Income Tax Act, 1961 during the 3rd week of Sept 2018 ie., after the finalisation of Accounts. The Actual Income Tax paid against the provision made is Rs.170.89 Crore and the challan-wise payment details are enclosed as <b>Annexure-5</b>. Further, an amount of Rs. 414.50 Cr is provided as deferred</p>

		paid to the Income Tax Department, during FY18 along with proof of payment.	tax liability (As 12) as detailed under Note 17 of the Audited accounts for FY 18. Hence KPTCL has claimed Rs. 584.52 Cr as per Table 21 in page 35 of APR filing document.
9.	2(iv)	<p><b>Contribution towards P &amp; G Trust:</b> As per the audited accounts for FY18, KPTCL has claimed an amount of Rs.167.66 Crores towards contribution to P&amp;G Trust for FY18. KPTCL shall furnish the details for claiming this amount in the APR for FY18 along with the relevant Actuarial Valuation Report.</p>	<p>Actuary on behalf of KPTCL and ESCOMs in the matter of Actuarial valuation of Pension &amp; Gratuity contribution. Based on the Actuarial valuation Report, KEPGT intimates KPTCL and ESCOMs the rates at which contribution towards Pension &amp; Gratuity has to be made by KPTCL and ESCOMs. <b>KEPGT vide its letter No.KEPGT/P7/2018-19/cys-2 dated 07/06/2018</b> has indicated the rates of contribution for FY 2017-18. In the said letter, rates of Pension and Gratuity contribution for FY 2017-18 has been indicated as 42.53%, 6.08% respectively, In respect of employees appointed after 01/04/2006 under New Defined Contributory Pension Scheme (NDCPS), contribution at 10% on Basic+DP+DA has been accounted. Details are as provided in <b>Annexure 6.</b></p>
<b>B.</b>	<b>Observation on ARR for FY 20-22:</b>		
10.	1.	<p><b>Transmission Capacity:</b> As per the audited accounts of KPTCL for FY18, the installed Transmission</p>	The Capacity of 20570 MW indicated in A1 is the approved capacity which is the basis for collection of

		<p>capacity for FY18 is indicated as 19763 MW. The same is shown also in Table-1 of the ARR filing. However, as per Format-A1, both under APR and ARR proposals, the installed Transmission capacity for FY18 is indicated as 20570 MW. The KPTCL shall examine the anomaly and submit correct figure in the revised Format- A1, in respect of APR for FY18 and ARR for FY20 to FY22.</p>	<p>transmission tariff from ESCOMs for FY 18. The same is indicated in format T2 also. The Transmission capacity indicated in the Audited accounts is 19763 MW which is the Actual capacity for the year. Hence there is no anomaly. Transmission Capacity for the years 18-19 and the MYT period 20-22 based on the Actuals of FY 18 are indicated in Table 26 of MYT application , page no. 44.</p>
11.	2.	<p><b>Projected Transmission Losses:</b> KPTCL in its application for approval of ARR for FY20-22, has projected the transmission losses of 3.19%, 3.17% and 3.15% respectively for FY20-22. As per the audited accounts of KPTCL for FY18, the actual transmission losses are indicated as 3.283% for FY17 and 3.222% for FY 18 and there is a reduction of 0.061 percentage points over FY17. Considering the huge capex proposed for the control period, the projected transmission losses, with a reduction of the 0.02 percentage point uniformly for all the years of the control period, is not justifiable. KPTCL shall furnish the justification for considering the reduction of 0.02 percentage point for each year of the control period and may reconsider the projected transmission losses for FY20-22.</p>	<p>Reduction in transmission losses is a continuous process. Losses are also dependent on the source of generation and load demand of ESCOMs which is spread across the state. KPTCL has been making sustained efforts in reduction of losses besides providing evacuation for generation and meeting load demands of ESCOMs. However KPTCL in its proposal has projected an optimal range of losses for each year of the control period and KPTCL would strive to achieve better reduction in losses.</p>



12.	3	<p><b>Transmission load forecast for the Fifth Control Period:</b></p> <p>a) The source-wise details of the existing and year-wise addition of generation capacity considered, shall be furnished.</p> <p>b) The ESCOM-wise details of Demand considered and methodology adopted in arriving at the Demand Forecast shall be provided.</p> <p>c) On the State map, Pictorial representation of existing and planned addition of Transmission capacity, indicating the details in sub para(a) and sub para(b) above, shall be provided.</p>	<p>The details are enclosed as per <b>Annexure 7(a), 7(b) and 7(c).</b></p>
13.	4	<p><b>Actual system Availability for 2017-18:</b></p> <p>Zone-wise availability in soft copy form shall be furnished. Further, the details of Transmission constraints, if any, shall be provided along with an action plan for overcoming such constraints.</p>	<p>Soft copy of Zone wise availability is furnished to the Commission on 20.12.18. Details of Transmission constraints and the action plan to mitigate the constraints are provided in the rolling plan submitted to the Hon'ble Commission in page Nos 15-19 for FY 19, Page Nos 27-30 for FY 20, page Nos 37-39 for FY 21 and Page Nos 48-55 for FY 22.</p>
14.	5	<p><b>System Availability Projections for FY 20, FY21 and FY22:</b></p> <p>The methodology adopted to arrive at the system availability and the measures for improving the system</p>	<p>The Actual System Availability for the previous three years i.e FY16 - FY 18 is 99.43% .99.60% and 99.43% with an average of 99.49%. Hence the availability for the base year FY 19 is</p>

		availability, year on year, by 0.05 percentage point shall be provided.	considered at 99.48%. The projections for the control period is made with an increase of 0 .05% for each year. This projection of System availability is based on the proposed system improvement through augmentation of network, new stations and new lines.
15	6	<p><b>Energy handled during the control period:</b></p> <p>It is observed that the energy required by the ESCOMs for the next Control Period also includes the following:</p> <ul style="list-style-type: none"> <li>i. Energy exported under open Access;</li> <li>ii. Energy handled under Wheeling &amp; Banking Agreement;</li> <li>iii. Energy imported by ESCOMs and the Open Access customers;</li> </ul> <p>In the tariff application filed by the KPTCL, the energy to be handled has been clubbed into one figure and furnished as the ESCOMS requirement after deducting the transmission losses. In order to arrive at the actual requirement of ESCOMs (which is based on their sales), KPTCL shall segregate the energy requirement figures and furnish the same in the following format:</p>	<p>KPTCL is a transmission Comapny providing its network for all types of users including ESCOMS and Open Access Consumers. KPTCL has considered the energy handled based on the energy requirement furnished by ESCOMs. The open access import and export transactions, wheeling and banking transactions occur during the year on case to case basis depending on priorities of the consumer/generators .</p> <p>Hence the same is not projected. However, if the ESCOMs have done any such projections , the same could be made use of.</p>

16	7	<p><b>Contribution to Pension Fund:</b> The KPTCL, in its ARR application for FY20-22, has claimed an amount of Rs.287.73 Crores, Rs.332.50 crores and Rs.380.68 Crores towards contribution to the Pension and Gratuity Trust for FY 20 to FY22 respectively. KPTCL shall furnish the computation sheet for the claims made for FY20-22 supported by the relevant Actuarial Valuation Report.</p>	<p>Computation sheet as required by the Commission is enclosed as <b>Annexure 8.</b></p>												
17.	8	<p><b>Provision for Income Tax:</b> KPTCL in its application for approval of ARR for FY20-22, while projecting a net revenue gap of Rs.843.81 Crores, Rs.1242.22 Crores and Rs.1332.69 Crores for FY20, FY21 and FY22 respectively, has made a provision for income tax of Rs.162.11 Crores, Rs.190.55 Crores and Rs.223.39 Crores for FY20-22 respectively. KPTCL shall furnish the reason for claiming the income tax even while projecting a huge amount of revenue deficit for FY20-22.</p>	<p>The income tax provisions are made on the RoE as per the provisions of the MYT Regulations. The deficit indicated is based on the revenue from existing tariff.</p>												
18.	9	<p><b>Capex for FY20 to FY22</b></p> <p>KPTCL has proposed the following amounts towards capex for the next control period as follows:</p> <table border="1" data-bbox="363 1756 863 1942"> <thead> <tr> <th>Fin. Year</th> <th>No.of works</th> <th>Capex proposed (Rs. Crores)</th> </tr> </thead> <tbody> <tr> <td>FY20</td> <td>667</td> <td>3207.97</td> </tr> <tr> <td>FY21</td> <td>573</td> <td>3269.64</td> </tr> <tr> <td>FY22</td> <td>419</td> <td>3287.77</td> </tr> </tbody> </table>	Fin. Year	No.of works	Capex proposed (Rs. Crores)	FY20	667	3207.97	FY21	573	3269.64	FY22	419	3287.77	
Fin. Year	No.of works	Capex proposed (Rs. Crores)													
FY20	667	3207.97													
FY21	573	3269.64													
FY22	419	3287.77													

		The Commission notes that the number of works and the capex amounts proposed is towards the works that are completed and which are likely to be completed during the control period FY20 to FY22. On a review of the list of proposed capex, the following observations are made:	
19.	9.(a)	<p><b>Rationale for Capital Investment Programme for FY 20, FY 21 and FY 22:</b></p> <p>i. The addition of RE capacity in the State is much more than what was planned when the Power Grid conducted the study for Green Energy Corridors. The KPTCL shall provide the details of its planning and implementation of the Green Corridor in the State considering the present status of RE and future growth in RE capacity, by revising its earlier plan. KPTCL shall also provide complete details of works being carried out and to be carried out, to meet the anticipated RE Additions.</p> <p>ii. The '24X7 Power for All' Programme initiated by the Government of India began few years ago. Whether KPTCL network, as existing now, is adequate to provide '24X7 Power for All' throughout the State, without any constraints, during the Control Period</p>	<p>Reply in respect of B(9)(a) (i) (ii) and (iii) are furnished in <b>Annexure 9.</b></p> <p>In respect of B(9)(a) (iv), KPTCL is reviewing the projects regularly for ensuring timely completion to reduce any time over run/ cost over-run. Further, post commissioning analysis of the completed works is also carried out and prudence check by third party is conducted by the commission.</p>

FY20-FY22, needs to be examined. If it is not adequate, the KPTCL shall indicate the measures already initiated and the action plan to provide 24X7 Power for all during the said Control Period.

The KPTCL has to assess the network capability for harnessing the solar power by shifting the 11kV Agricultural feeders simultaneously during the solar peak generation period and take necessary action to cater the loads without any constraints. Action taken in this regard may be furnished.

iii. Whether the KPTCL has done any study to know the percentage of utilisation of Transmission lines meant for evacuation of RE Power? And whether it has considered any cost-effective and efficient methods for evacuation of Power from RE Power depending upon the requirement? If so details thereof may please be provided.

iv. Whether KPTCL has done Analysis on impact of delay in projects on increase in cost and increase in per unit of cost of transmission.

20.	9(b)	<p><b>List of capital Works:</b></p> <p>It is seen from the tariff application that a list containing 667 number of capital works (prepared in a chronological order), which are planned to be undertaken/ executed during next control period, is furnished. From the list so prepared, the Commission is unable to categorise the works into completed works, ongoing works and works to be taken up in the near future. It is not clear from the list as to how the KPTCL will prioritise the works to be undertaken / executed. Therefore, the KPTCL shall prepare the list as per the Annexures enclosed to the observations and submit it with the its compliance to the observations.</p>	<p>Details as per <b>Annexures A ,B and C</b> are enclosed.</p>
21.	9(c)	<p><b>Financing of the Capex:</b></p> <p>Though huge amounts of over Rs.3200 crores, for each of the years of the control period, are proposed to be incurred, KPTCL has not indicated the sources of funding the capex. As per Format T-9, new loans to be raised from commercial banks to the tune of over Rs.2600 crores annually, are indicated. This indicates that the financing of future capex as specified in the MYT Regulations (Debt: Equity norm of 70:30) is not being complied with. Hence, KPTCL shall furnish the</p>	<p>The Details of Funding the Capex for the control period is enclosed as per <b>Annexure 10.</b></p>


		<p>details of funding of capex for the control period, duly considering the internal resources such as depreciation, retained earnings, consumer contribution/grants etc. to arrive at the net requirement of funding the capex.</p>	
22.	9(d)	<p><b>Budget for Completed works:</b></p> <p>The budget for the completed works is indicated as Rs.371.19 Crores, Rs. 665.32 Crores and Rs. 752 Crores for FY20, FY21 and FY22 respectively. It is understandable that for the completed works, any outstanding amount towards non-submission of bills, disputes in the quantification of additional works/ deviations etc. would be paid in the immediate next year of completion of work, by providing the budget, in the immediate next year i.e. FY20. But the purpose for providing budgets towards completed works for the subsequent two years (FY21 &amp; FY22) that too by providing huge amounts of Rs. 665.32 Crores and Rs. 752 Crores respectively, is not clear. KPTCL shall suitably clarify the same</p>	<p>The budget indicated for completed works Rs. 371.19 Crores, Rs. 665.32 Crores and Rs.752 Crores for FY20, FY21 &amp; FY22 respectively are the amount required for the works which are completed during previous financial year.</p> <p><b>For example:</b> No. of works intended to be completed during FY-19 is 312, out of which 217 will achieve physical and financial completion during FY19 itself while 95 is expected to be completed physically for which a budget of Rs.317.19 Crores is earmarked in FY20 for achieving financial completion. Similarly, an amount of Rs. 665.32 Crores is earmarked for achieving financial completion of 54 works in FY21 and an amount of Rs.743 Crores is earmarked for achieving financial completion of 42 works in FY22.</p>

23.	9(e)	<p><b>Inclusion of R &amp; M works under capex:</b></p> <p>In the proposed list of capex, works pertaining to R &amp; M have been included vide Sl. Nos. 27, 28, 31 and 33. The expenses on these works are chargeable to Revenue Expenditure, but KPTCL has classified these works under capex. The reasons thereof need to be explained. If these works are to be undertaken under R &amp; M, the same shall be excluded from the list of proposed capex.</p>	<p>The R&amp;M Works included under CAPEX is the work towards Renovation &amp; Modernization of existing sub-stations wherein all the major equipments, C&amp;R panels, bus bar are replaced with new equipments, C&amp;R panels and bus bar. As seen from the nature of work, by taking up the Renovation &amp; Modernization of existing sub-stations, the life of asset is increased and hence the life of project. Therefore these R&amp;M works has been classified under CAPEX.</p>
24	9(f)	<p><b>Incomplete works brought forward from the previous control period and huge amount of works in progress to be converted into assets:</b></p> <p>From the list of capex works, it is observed that many works that were included in the earlier control period i.e. FY17 to FY19 have been included in the current list for FY20-FY22 also (Example: Sl. Nos. 10, 11,12,20, 21). This would mean that, these works have not been completed during the previous control period but again included in the current list and are likely to be completed in this control period. As a result of non-completion</p>	<p>Details of works in prescribed format and reasons for delay are indicated in <b>Annexure A ,B and C.</b></p> <p>All efforts will be made for capitalization of works completed within scheduled time.</p> <p>Necessary corporate direction will be issued to all CEE, Transmission zones to prepare age-wise analysis of list of works in progress and remedial action initiated to reduce the inventory.</p>



of works, the money already spent would remain as idle investment till the assets are put to use.

Further, it is seen from the audited accounts for FY18 that as on 31.03.2018, an amount of Rs. 3,033 Crores is remaining under the head of account 'Work in Progress'. This is a huge amount representing the money which is already spent but the assets thereon are not yet commissioned. It is to be pointed out here that, the capital works taken up shall be completed in a time bound manner by addressing all the issues (like RoW etc.) and if the assets are not put to use despite incurring huge capex, the capital investment will become idle and the consumers are made to bear the interest burden without deriving any benefit from such works, for an indefinite period. The KPTCL shall analyse the work-in-progress by preparing an age-wise analysis and explain the reasons for the keeping such a huge amount under work in progress besides taking remedial action to reduce the huge balance under the 'Work In Progress'.

  
**Financial Advisor (RA)**  
**FINANCIAL ADVISOR**  
Regulatory Affairs  
KPTCL, Kaveri Bhavan  
Bangalore - 560 009

## Annexure-1

**MVAR AVAILABILITY TO THE GRID FROM WORKING CAPACITOR BANKS**

Quarter	Installed		Working		% working vis-à-vis the installed	
	No's.	MVAR	No's.	MVAR	No's.	MVAR
1 <sup>st</sup> of F.Y-2018	1047	6175.54	877	4528.29	83.76%	73.32 %
2 <sup>nd</sup> of F.Y-2018	1076	6259.74	919	4626.07	85.41%	73.90 %
3 <sup>rd</sup> of F.Y-2018	1131	6418.87	970	4756.41	85.76 %	74.10 %
4 <sup>th</sup> of F.Y-2018	1196	6607.98	1036	5011.84	86.62 %	75.84 %
1 <sup>st</sup> of F.Y-2019	1247	6757.77	1085	5163.19	87.00 %	76.40 %
2 <sup>nd</sup> of F.Y-2019	1309	6945.61	1147	5344.65	87.62 %	76.95 %
3 <sup>rd</sup> of F.Y-2019 (Oct-18 to Nov-18)	1344	7015.11	1176	5478.70	87.50 %	78.09 %

No. CEE/SLDC/CA/TBC/

12448-51



O/O Chief Engineer Ele.

State Load Dispatch Center, KPTCL

Race course Cross Road, A.R.Circle

Bangalore-560001. 11 DEC 2018

Bill Date: 07.12.2018

Due Date: 17.12.2018

**INTRA STATE ABT FOR CGS DEVIATION BILL**

Ref: SRPC Invoice dated 25.09.2018.

BILL NO. 2 /07.12.2018

BILL TOWARDS PAYMENT OF DEVIATION SETTLEMENT ACCOUNT PAYABLE/RECEIVABLE BY KPTCL TO ABT BASED UI POOL ACCOUNT ON BEHALF OF ESCOMS FOR THE PERIOD FROM 10/09/2018 to 16/09/2018

**Abstract of UI Energy for the week from 10/09/2018 to 16/09/2018**

	TOTAL	BESCOM	MESCOM	HESCOM	GESCOM	CESC	REMARKS
	In MWh						
CGS	-9021.052	236.038	-126.640	2356.661	-8761.456	-2725.655	CGS portion of deviation settlement for ESCOMS
ESCOM	0	19325.446	2901.854	37785.000	-55085.636	-4926.664	State portion of Deviation settlement amount
<b>TOTAL</b>	<b>-9021.052</b>	<b>19561.484</b>	<b>2775.214</b>	<b>40141.661</b>	<b>-63847.092</b>	<b>-7652.319</b>	

**Abstract of amount to be paid for the week from 10/09/2018 to 16/09/2018**

	CGS portion of deviation settlement for ESCOMS	State portion of Deviation settlement amount	Total amount in Rs.	Payable to ESCOMS/Receivable from ESCOMS
	In Rupees			
BESCOM	261084	53642901	53903985	Receivable
MESCOM	-554679	8073015	7518336	Receivable
HESCOM	7528448	109023774	116552222	Receivable
GESCOM	-22596453	-156676035	-179272488	Payable
CESC	-8307547	-14063655	-22371202	Payable
<b>TOTAL</b>	<b>-23669147</b>	<b>0</b>	<b>-23669147</b>	

NOTE:(+)INDICATES AMOUNT RECEIVABLE BY KPTCL FROM ESCOMS.

(-)INDICATES AMOUNT PAYABLE BY KPTCL TO THE ESCOMS.

Chief Engineer(Elec)  
 SLDC, KPTCL, B'LORE

TO  
 Managing Director.,  
 BESCOM/MESCOM/GESCOM  
 HESCOM/CESC

\*Please pay through DD or through RTGS in favour of "Chief Engineer (Ele),SLDC,KPTCL, Bangalore

RTGS (IFSC) Code of State Bank of Mysore, Madhavanagar, Bangalore:SBIN0040196

Current Account No: 64022936516

No. CEE/SLDC/CA/TBC/

9847-52



O/O Chief Engineer Ele.

State Load Despatch Center, KPTCL'

Race course Cross Road, A.R.Circle

Bangalore-560001.

Bill Date: 29.10.2018

Due Date: 08.11.2018

**INTRA STATE ABT FOR CGS DEVIATION BILL**

Ref: SRPC Invoice dated 18.09.2018.

BILL NO. 1 /29.10.2018

BILL TOWARDS PAYMENT OF DEVIATION SETTLEMENT ACCOUNT PAYABLE/RECEIVABLE BY KPTCL TO ABT BASED UI POOL ACCOUNT ON BEHALF OF ESCOMS FOR THE PERIOD FROM 03/09/2018 to 09/09/2018

**Abstract of UI Energy for the week from 03/09/2018 to 09/09/2018**

CGS	16618638	18383065	1871328	-1148620	-3163382	676247	CGS portion of deviation settlement for ESCOMS
ESCOM	0	117892610	4917420	-45903885	-73866717	-3039427	State portion of Deviation settlement amount
<b>TOTAL</b>	<b>16618638</b>	<b>136275675</b>	<b>6788748</b>	<b>-47052505</b>	<b>-77030099</b>	<b>-2363180</b>	

**Abstract of amount to be paid for the week from 03/09/2018 to 09/09/2018**

49632993	331226266	381061259	Receivable
5084148	13259395	18343543	Receivable
-2849468	-129469617	-132319085	Payable
-7226463	-206380463	-213606926	Payable
1794056	-8637581	-6843525	Payable
46635266	0	46635266	

Chief Engineer(Elec)  
SLDC, KPTCL, B'LORE

29/10/18

TO  
Managing Director.,  
BESCOM/MESCOM/GESCOM  
HESCOM/CESC

Please pay through DD or through RTGS in favour of "Chief Engineer (Ele), SLDC, KPTCL, Bangalore

RTGS (IFSC) Code of State Bank of Mysore, Madhavanagar, Bangalore: SBIN0040196

Current Account No: 64022936516

KPTCL

ANNEXURE - 3

SALARY

Group	Employee No.	Existing Pay	Revised Basic	DA on existing pay	DA on Revised Pay	HRA on existing pay	HRA on revised pay	CCA on existing pay	CCA on revised pay	Additional Basic	Additional DA	Additional HRA	Additional CCA	Total Arrears
A	1132	719940785	909880755	322323130	407132544	137498292	174417968	4172794	4172794	189539971	84809226	36919677		0
B	1150	168127328	204278888	22888372	27205915	75497171	97325182	2536886	2536886	136151638	60327344	21828011		0
C	1378	142319513	172018213	66718572	71629087	179441745	228500141	5668101	5668101	334707199	149536414	49058396		0
D	2751	588607510	738610701	263325674	331120385	87387087	110093870	3535137	3535137	150002881	67794712	22706783		0
Total	9020	3056995246	3869396935	1371081237	1733548931	479824295	610337161	15932918	15932918	810401690	362467696	130512866		0


ELS														
Group	Employee No.	Existing Pay	Revised Basic	DA on existing pay	DA on Revised Pay	HRA on existing pay	HRA on revised pay	CCA on existing pay	CCA on revised pay	Additional Basic	Additional DA	Additional HRA	Additional CCA	Total Arrears
A	943	57844532	76044708	26580342	34836793	12045015	15916214	138281	138281	18200176	8256450	3871199		0
B	889	24986589	32859492	10806698	14515204	4476459	6378247	85247	85247	7872904	3708506	1901787		0
C	2147	85491196	110293919	37262966	49548373	12135760	16910588	262519	262519	24802723	12285407	4774828		0
D	1596	39751887	51677635	17288043	22909754	6008656	8546423	154209	154209	11925748	5621711	2537768		0
Total	5575	208074204	270875755	91938049	121810123	34665890	47751471	640256	640256	62801550	29872074	13085582		0

## KARNATAKA POWER TRANSMISSION CORPORATION LIMITED

### 2017-18 Pay Scale Arrears Payment

Unit Name	BP	DP	DA	HRA	ELS	Total
IM Section	5,29,08,879.00	-	2,47,31,507.00	1,57,41,252.00	99,87,816.00	10,33,69,454.00
SLDC	1,69,40,469.00	-	82,74,038.00	52,67,548.00	9,71,981.00	3,14,54,036.00
Cash and Accounts	2,42,50,838.00		1,08,45,221.00	71,14,806.00	33,59,705.00	4,55,70,570.00
Bangalore Zone	20,05,20,052.00	2,59,77,031.00	5,01,21,770.00	3,82,23,976.00	1,60,31,814.00	33,08,74,643.00
Mysore Zone	9,12,49,603.00	3,31,593.00	4,03,85,013.00	1,34,06,561.00	79,70,559.00	15,33,43,329.00
Tumkur Zone	10,62,13,265.00	2,95,87,322.00	1,74,33,855.00	1,03,49,569.00	1,05,75,511.00	17,41,59,522.00
Hassan Zone	12,74,32,256.00	2,45,92,763.00	3,55,24,387.00	1,36,17,409.00	1,62,34,310.00	21,74,01,125.00
Bagalkot Zone	17,33,40,202.00	2,09,73,973.00	5,22,24,286.00	2,41,56,210.00	1,40,35,604.00	28,47,30,275.00
Gulbarga Zone	17,15,09,404.00	71,22,280.00	4,32,24,291.00	1,30,75,984.00	98,79,983.00	24,48,11,942.00
<b>Grand Total</b>	<b>96,43,64,968.00</b>	<b>10,85,84,962.00</b>	<b>28,27,64,368.00</b>	<b>14,09,53,315.00</b>	<b>8,90,47,283.00</b>	<b>1,58,57,14,896.00</b>

Details of actual amount of Income Tax Paid to Income Tax department for the Financial Year-2017-18						
S.I. No	Period	Quarter	Income Tax Paid (Amount in Crs)	Challan No. & Date	Remitted at	Cheque No. & Date
1	01.04.2017-30.06.2017	1st Quarter	39,40,00,000	15-06-2017	Vijaya Bank	720461 /14-06-2017
2	01.07.2017-30.09.2017	2nd Quarter	28,61,00,000	14-09-2017	Vijaya Bank	564805/15-09-2017
3	01.10.2017-31.12.2017	3rd Quarter	25,70,00,000	00003/14-12-2017	Vijaya Bank	558289/14-12-2017
4	01.01.2017-31.03.2017	4th Quarter	28,88,00,000	0001/14-03-2018	Vijaya Bank	553485/14-03-2018
5	Self Assesment Income Tax-2017-18		48,29,96,370	00002/28-09-2018	Vijaya Bank	549697/28-09-2018
<b>Total</b>			<b>170,88,96,370</b>			

  
 Controller (C&T) 15/12/18

Annexure 5

**Taxpayers Counterfoil** (To be filled up by the Taxpayer)

PAN: **A A B C K 7 2 8 1 M**

Received from: **KARNATAKA POWER TRANSMISSION CORPORATION LIMITED**  
(Name)

Cash/ Debit to A/c /Cheque No. **720461** For Rs. **39,40,00,000**

Rs. (in words) **Thirty Nine Crores Forty Lakhs only.**

Drawn on **VIJAYA BANK, K.G ROAD BRANCH, BENGALURU**  
(Name of the Bank and Branch)

on account of **Companies/Other than Companies/Tax**  
(Strike out whichever is not applicable)

Income Tax on **Companies/Other than Companies/Tax**  
(Strike out whichever is not applicable)

Type of Payment **Companies/Other than Companies/Tax**  
(To be filled up by person making the payment)

for the Assessment Year **2018 - 19**

**VIJAYA BANK**

**5 / VIJAYA BANK**

K.G. Road Br., BANGALORE-4  
B.S.R. CODE : 03990008

Deposit Date: **15 JUN 2017**

Realisation Dt. : \_\_\_\_\_  
Serial No. : \_\_\_\_\_

Rs. **₹ 39,40,00,000**

**ನಿಯಂತ್ರಕಾರ್ಥಿ**  
(ಇನ್‌ಚಾರ್ಜ್ ಆಫ್ ಟ್ಯಾಕ್ಸ್)





Taxpayers Counterfoil (To be filled up by tax payer)		Signature of person making payment	
PAN <b>AABCK7281M</b>		<b>KPTCL Kaveri Bhavan,</b>	
Received from <b>CONTROLLER (A.P &amp; A) K P T C L CORPORATE OFFICE, THIRU</b>		(Name)	
Cash/ Debit to A/c /Cheque No.	<b>564805</b>	For Rs.	<b>286100000</b>
Rs. (in words)	<b>Rupees twenty eight crore sixty one lac only</b>		
Drawn on	<b>VIJAYA BANK, K.G ROAD BRANCH</b>		
(Name of the Bank and Branch)			
on account of	Companies/Other than Companies/Tax		
Income Tax on	(Strike out whichever is not applicable)		
Type of Payment	(To be filled up by person making the payment)		
for the Assessment Year	<b>2018</b>	-	<b>19</b>

RECEIVED  
 VIJAYA BANK  
 K.G. ROAD BRANCH  
 THIRU  
 15-08-2018  
 Rs. **286100000**

Finotax

Annexure - A - IV - II


Computer generated receipt	
<div style="display: flex; justify-content: space-between; align-items: center;"> <span> PRINT</span> </div>	
Name of the bank collecting tax	VIJAYA BANK
Full name of Taxpayer	KPTCL
PAN of Taxpayer	AABCK7281M
Amount deposited :	
(i) Income Tax	257000000
(ii) Surcharge	--
(iii) Education Cess	--
(iv) Penalty	--
v) Interest amount	--
vi) Other amount	--
Total amount deposited : (in figure)	257000000
Mode of deposit of tax ( by cash / debit to account / by cheque bearing No. )	Transfer - Debit A/C No - 111800300005318
Date of encashment of cheque (dd/mm/yy)	14/12/17
On account of Income Tax Deducted / collected from Companies (0020) / Other than Companies(0021)	0020-CORPORATION TAX
Minor head - Type of payment	100-ADVANCE TAX
Assessment Year (yyyy - yy)	2018-19
<b>Challan Identification Number (CIN)</b>	
BSR code of collecting bank branch	0390009
Date of tender of cheque (dd/mm/yyyy)	14/12/2017
Challan Serial Number	00003
Signature & seal of authorised signatory of collecting bank branch  	

Close

Annexure - A - IV - II

Computer generated receipt	
Name of the bank collecting tax	VIJAYA BANK
Full name of Taxpayer	KARNATKA POWER TRANSMISSION CORPORA
PAN of Taxpayer	AABCK7281M
Amount deposited :	
(i) Income Tax	288800000
(ii) Surcharge	--
(iii) Education Cess	--
(iv) Penalty	--
v) Interest amount	--
vi) Other amount	--
Total amount deposited : (in figure)	288800000
Mode of deposit of tax ( by cash / debit to account / by cheque bearing No. )	Transfer - Debit A/C No - 111800300005318
Date of encashment of cheque (dd/mm/yy)	14/03/18
On account of Income Tax Deducted / collected from Companies (0020) / Other than Companies(0021)	0020-CORPORATION TAX
Minor head - Type of payment	100-ADVANCE TAX
Assessment Year (yyyy - yy)	2018-19
<b>Challan Identification Number (CIN)</b>	
BSR code of collecting bank branch	0390009
Date of tender of cheque (dd/mm/yyyy)	14/03/2018
Challan Serial Number	00001
Signature & seal of authorised signatory of collecting bank branch	
<p>कृते विजया बँक / For Vijaya Bank</p> <p>सहायक शाखा प्रबन्धक / Asst. Br. Manager  क.जी. रोड, बंगलूर -560 009  K.G. Road, BANGALORE-9</p>	

Close

<b>Computer generated receipt</b>	
Name of the bank collecting tax	VIJAYA BANK
Full name of Taxpayer	KPTCL
PAN of Taxpayer	AABCK7281M
<b>Amount deposited :</b>	
(i) Income Tax	482996370
(ii) Surcharge	--
(iii) Education Cess	--
(iv) Penalty	--
v) Interest amount	--
vi) Other amount	--
<b>Total amount deposited : (in figure)</b>	482996370
<b>Mode of deposit of tax ( by cash / debit to account / by cheque bearing No. )</b>	Transfer - Debit A/C No - 111800300005318
<b>Date of encashment of cheque (dd/mm/yy)</b>	28/09/18
<b>On account of Income Tax Deducted / collected from Companies (0020) / Other than Companies(0021)</b>	0020-CORPORATION TAX
<b>Minor head - Type of payment</b>	300-SELF ASSESMENT TAX
<b>Assessment Year (yyyy - yy)</b>	2018-19
<b>Challan Identification Number (CIN)</b>	
<b>BSR code of collecting bank branch</b>	0390009
<b>Date of tender of cheque (dd/mm/yyyy)</b>	28/09/2018
<b>Challan Serial Number</b>	00002
<b>Signature &amp; seal of authorised signatory of collecting bank branch</b>	
	

Back

**CONTRIBUTION TOWARDS P & G TRUST:**

(1) Pension & Gratuity Contribution in respect of Employees appointed prior to 01/04/2006	
(a) Pension Contribution@ 42.53% on Basic+DP+DA for FY 2017-18	102 23 00 791
(b) Gratuity Contribution@ 6.08% on Basic+DP for FY 2017-18	10 05 39 714
(c) Pension Contribution@ 42.53% on Basic+DP+DA towards arrears of pay	21 95 29 737
(d) Gratuity Contribution@ 6.08% on Basic+DP towards arrears of pay	2 16 81 183
<b>Total</b>	<b>136 40 51 425</b>
(2) Pension Contribution in respect of employees appointed on or after 01/04/2006	
(a) KPTCL's Pension contribution at 10% on Basic+DP+DA to New Pension Scheme(NDCPS)	24 60 43 366
(b) NDCPS contribution towards arrears of pay	6 57 21 614
(c) NDCPS contribution in respect of employees deputed to TBHE, Munirabad	8 30 295
<b>Total</b>	<b>167 66 46 700</b>

ಕ.ವಿ.ಪ್ರ.ನಿ.ನಿ. ಮತ್ತು ವಿಸಕಂಗಳ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಟ್ರಸ್ಟ್  
KPTCL AND ESCOMs PENSION AND GRATUITY TRUSTS

Ph No. 080-22291150  
Fax No. 080-2223558  
E-mail: pgtrustkptcl@yahoo.com

6<sup>th</sup> Floor,  
Kaveri Bhavan,  
Bangalore-560009.

ಸಂಖ್ಯೆ: ಕೆಇಪಿಜಿಟಿ/ಪಿ7/2018-19/೮೪೨-೨

ದಿನಾಂಕ: 07 JUN 2018

ಲಗತ್ತು: 2 ಅನುಬಂಧಗಳು

ಗೆ,

ಎಲ್ಲಾ ಟ್ರಸ್ಟಿಗಳು,

ಕವಿಪ್ರನಿ ಮತ್ತು ವಿಸಕಂಗಳ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಟ್ರಸ್ಟ್,

ಮಾನ್ಯರೇ,

ವಿಷಯ: 31.03.2017ರ ಅಂತ್ಯಕ್ಕೆ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪನಕ್ಕೆ (Actuarial Funding Report) ಸಂಬಂಧಿಸಿದಂತೆ ಕ್ರೋಢೀಕೃತ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ವರದಿಗಳನ್ನು ಕಳುಹಿಸುವ ಕುರಿತು.

- ಉಲ್ಲೇಖ: 1. ಈ ಕಛೇರಿ ಪತ್ರ ಸಂಖ್ಯೆ: ಕೆಇಪಿಜಿಟಿ/ಕೆಸಿ೩/23/ಪಿ7/2016-17/1465-71 ದಿನಾಂಕ 20.02.2017.  
2. ಈ ಕಛೇರಿ ಕಾರ್ಯದೇಶ ಸಂಖ್ಯೆ: ಕೆಇಪಿಜಿಟಿ/ಕೆಸಿ೩/23/ಪಿ7/2016-17/40-43 ದಿನಾಂಕ 07.04.2017.  
3. ಈ ಕಛೇರಿ ಪತ್ರ ದಿನಾಂಕ 16.05.2018.  
4. ಈ ಕಛೇರಿ ಪತ್ರ ಸಂಖ್ಯೆ: ಕೆಇಪಿಜಿಟಿ/ಕೆಸಿ೩/23/ಪಿ7/2018-19/210 ದಿನಾಂಕ 11.05.2018.  
5. ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕರ ಪತ್ರ ದಿನಾಂಕ 14.05.2018.

\* \* \* \* \*

1. ಮೇಲಿನ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ತಮ್ಮ ಗಮನಕ್ಕೆ ತರಬಯಸುವುದೇನೆಂದರೆ, ದಿನಾಂಕ 31.03.2017ರ ಅಂತ್ಯಕ್ಕೆ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪನಕ್ಕೆ (Actuarial Valuation) ಸಂಬಂಧಿಸಿದಂತೆ ಪ್ರೊಫಾರ್ಮ್ 1 ರಿಂದ 7 ರ ಪಟ್ಟಿಗಳನ್ನು Excel Format ನಲ್ಲಿ ಸಿಬ್ಬಂದಿ/ನಿವೃತ್ತಿದಾರರ ಮಾಹಿತಿಗಳನ್ನು ಸಲ್ಲಿಸುವಂತೆ ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳು/ಪಿಸಿಕೆಎಲ್‌ಗಳನ್ನು ಉಲ್ಲೇಖ-1ರ ಪತ್ರದಲ್ಲಿ ಕೋರಲಾಗಿತ್ತು.
2. ಬೋರ್ಡ್ ಆಫ್ ಟ್ರಸ್ಟೀಸ್ ಸಭೆಯಲ್ಲಿ ಅನುಮೋದಿಸಿದಂತೆ, ಉಲ್ಲೇಖ-2ರಲ್ಲಿ ದಿನಾಂಕ 31.03.2017ರ ಅಂತ್ಯಕ್ಕೆ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪನ (Actuarial Valuation) ಕಾರ್ಯವನ್ನು M/s Kapadia Actuaries & Consultants, Mumbai ರವರಿಗೆ ವಹಿಸಲಾಗಿರುತ್ತದೆ.
3. ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳು/ಪಿಸಿಕೆಎಲ್‌ಗಳು ನೀಡಲ್ಪಟ್ಟ ಪ್ರೊಫಾರ್ಮ್ 1 ರಿಂದ 7ರ ಮಾಹಿತಿಗಳನ್ನು IND AS 19 ಪ್ರಕಾರ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕರಿಗೆ ಒದಗಿಸಲಾಗಿದ್ದು, ಅವರು ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ವರದಿ (IND AS 19) ಗಳನ್ನು ಈ ಕಛೇರಿಗೆ ಸಲ್ಲಿಸಿರುತ್ತಾರೆ.
4. ಕಂಡಿಕೆ-3ರಲ್ಲಿ ತಿಳಿಸಿದ ಕಂಪನಿಗಳ ಕರಡು ವರದಿಯ (Actuarial Valuation Report as per IND AS 19) ಪ್ರತಿಗಳನ್ನು ಮುಂದಿನ ಸೂಕ್ತ ಕ್ರಮಕ್ಕಾಗಿ ಉಲ್ಲೇಖ-3ರ ಪತ್ರಕ್ಕೆ ಲಗತ್ತಿಸಿ ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳು/ಪಿಸಿಕೆಎಲ್‌ಗಳಿಗೆ ಕಳುಹಿಸಿಕೊಡಲಾಗಿದೆ.
5. ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನದ ಹೊಣೆ ಮತ್ತು ತತ್ಸಂಬಂಧ ಹೊಂದಿರಬೇಕಾದ ನಿಧಿಯ ಅಂದಾಜು ಮೊತ್ತವನ್ನು ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕರು Actuarial Valuation Funding Report ಮುಖೇನ ಲೆಕ್ಕಹಾಕಿ ಸಲ್ಲಿಸುತ್ತಾರೆ. ಇದರ ಆಧಾರದ ಮೇಲೆ ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳು/ಪಿಸಿಕೆಎಲ್‌ಗಳಿಂದ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ವಂತಿಗೆ ಪಾವತಿಸಲು ದರವನ್ನು ನಿಗದಿಪಡಿಸಲಾಗುತ್ತದೆ. ಇದುವರೆವಿಗೂ ವಂತಿಗೆ ದರವನ್ನು ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕರ ವರದಿಯನ್ನು ಆಧರಿಸಿ ನಿಗದಿಪಡಿಸಲಾಗಿದೆ. ಅದೇ ರೀತಿ ದಿನಾಂಕ 31.03.2017ಕ್ಕೆ ಕರಡು ಕ್ರೋಢೀಕೃತ ವರದಿಯನ್ನು ಆಧರಿಸಿ ಆರ್ಥಿಕ ವರ್ಷ 2017-18ಕ್ಕೆ ಪೂರ್ವಾನ್ವಯವಾಗುವಂತೆ ವಂತಿಗೆ ದರಗಳನ್ನು ಪರಿಷ್ಕರಿಸುವ ಆಗತ್ಯವಿರುತ್ತದೆ. ಸದರಿ ಕ್ರೋಢೀಕೃತ ವರದಿಯ (ಅನುಬಂಧ-1) ಕರಡು ಪ್ರತಿಯನ್ನು ಈ ಪತ್ರಕ್ಕೆ ಲಗತ್ತಿಸಿದ್ದು, ಮುಖ್ಯಾಂಶಗಳನ್ನು ಅವಗಾಹಿಸಲು ಕೋರಿದೆ.

- i. 31.03.2017ರ ಅಂತ್ಯಕ್ಕೆ ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಫಲಿತಾಂಶವನ್ನು (Valuation Results) ವರದಿಯ ಕಂಡಿಕೆ-5ರಲ್ಲಿ ಒಟ್ಟು ಸೇವಾ ಹೊಣೆ (Total Service Liability) ನಿಧಿ ಮೌಲ್ಯ (Fund Asset) ಮತ್ತು ನಿಧಿಯಲ್ಲಿನ ಒಟ್ಟು ಕೊರತೆ (Deficit) ವಿವರಗಳನ್ನು ನಮೂದಿಸಿದೆ.

ii. ವರದಿ ಕಂಡಿಕೆ-6ರಲ್ಲಿ ಶಿಫಾರಸ್ಸು (Recommendations) ಮಾಡಿರುವುದು

ಆ. 2017-18ರ ಸಾಲಿನ ಅವಧಿಗೆ ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳು ಕಂಪನಿವಾರು ಟ್ರಸ್ಟ್‌ಗೆ ಸಂದಾಯ ಮಾಡಬೇಕಿರುವ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ವಂತಿಗೆ ಮೊತ್ತಗಳ ವಿವರಗಳನ್ನು ನಮೂದಿಸಿದೆ.

ಆ. ಹಿಂದಿನ ವರದಿಗಳಲ್ಲಿ ನಮೂದಿಸಿದಂತೆ, ಆರ್ಥಿಕ ವರ್ಷ 2017-18ರಿಂದ ಅನ್ವಯವಾಗುವಂತೆ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ವಂತಿಗೆಗಳಿಗೆ ಸಾಮಾನ್ಯ (Common) ಪಿಂಚಣಿ ವಂತಿಗೆ ದರ 42.53% ಮತ್ತು ಉಪದಾನ ದರ 4.62% ಶಿಫಾರಸ್ಸು ಮಾಡಲಾಗಿದೆ.

6. ಸದರಿ ವರದಿಯಲ್ಲಿ ಪಿಂಚಣಿ ವಂತಿಗೆ ದರವು ಪ್ರಸ್ತುತ 33.08% ರಿಂದ 42.53%ಕ್ಕೆ ಏರಿಕೆಗೆ ಹಾಗೂ ಉಪದಾನ ವಂತಿಗೆ ದರವು ಪ್ರಸ್ತುತ 6.08% ರಿಂದ 4.62%# ಇಳಿಕೆಯಾಗಿರುವುದು ಅಂದಾಜಿಸಲಾಗಿದೆ. ಈ ರೀತಿಯ ಹೆಚ್ಚಿನ ಬದಲಾವಣೆಗೆ ಕಾರಣಗಳನ್ನು ಕೇಳಿ ಮತ್ತು ಇತರ ಸಂಬಂಧಿತ ವಿಷಯಗಳ ಬಗ್ಗೆ ಟ್ರಸ್ಟ್ ವತಿಯಿಂದ ಪ್ರಾಥಮಿಕವಾಗಿ ವರದಿಯನ್ನು ಅಭ್ಯಸಿಸಿ ಮೌಲ್ಯಮಾಪಕರಿಂದ ಸ್ಪಷ್ಟನೆ ಮತ್ತು ವಿವರಗಳನ್ನು ಕೋರಲಾಗಿತ್ತು. ಅವರು ನೀಡಿರುವ ವಿವರಗಳು ಸಮಂಜಸವೆನಿಸುತ್ತವೆ. ಈ ಸಂಬಂಧ ಟ್ರಸ್ಟ್‌ನಿಂದ ಕೇಳಲಾದ ವಿವರ ಮತ್ತು ಅವರ ಸ್ಪಷ್ಟೀಕರಣದ ಪತ್ರವನ್ನು ಅನುಬಂಧ-2ರಲ್ಲಿ ಲಗತ್ತಿಸಲಾಗಿದೆ.


#ಟಿಪ್ಪಣಿ: ಉಪದಾನದ ಗರಿಷ್ಠ ಮಿತಿಯು ₹ 20 ಲಕ್ಷಕ್ಕೆ ಏರಿಕೆಯಾಗಿರುವುದನ್ನು ಗಮನದಲ್ಲಿಟ್ಟುಕೊಂಡು ವಂತಿಗೆ ದರವನ್ನು ಕಡಿಮೆ ಮಾಡುವ ಬದಲು ಜಾರಿಯಲ್ಲಿರುವ ಉಪದಾನ ವಂತಿಗೆ ದರ 6.08%ನ್ನು ಮುಂದುವರಿಸಬಹುದೆಂದು ಮೌಲ್ಯಮಾಪಕರು ಅಭಿಪ್ರಾಯಪಟ್ಟಿರುತ್ತಾರೆ.

7. ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳ ಸಿಬ್ಬಂದಿ/ಪಿಂಚಣಿದಾರರು ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಅಂತರ ಬದಲಾವಣೆ (Inter Changable) ಆಗುತ್ತಿರುವುದರಿಂದ ಹಾಗೂ ಪಿಂಚಣಿ/ಕುಟುಂಬ ಪಿಂಚಣಿದಾರರು ವಿಸಕಂಗಳಿಗೆ ಹೋಲಿಸಿದಲ್ಲಿ ಕವಿಪ್ರನಿಯಲ್ಲಿ ಕಡಿಮೆ ಸಂಖ್ಯೆಯಲ್ಲಿರುವುದರಿಂದ ಪಿಂಚಣಿ ಹೊಣೆಯನ್ನು ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳಲ್ಲಿ ಸಮಾನ ಅನುಪಾತದಲ್ಲಿ ವಿಂಗಡಣೆ ಮಾಡುವುದು ಸಮಂಜಸವಾಗಿರುವುದಿಲ್ಲ. ಆದ್ದರಿಂದ, ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳಿಂದ ಪ್ರಸ್ತುತ ಜಾರಿಯಲ್ಲಿರುವ ಪದ್ಧತಿಯಂತೆ, ಕಂಡಿಕೆ-5ರ ಉಪಕಂಡಿಕೆ-(ii)ಆ)ರಲ್ಲಿ ನಮೂದಿಸಿದ ವಂತಿಗೆ ದರದಂತೆ ಪಿಂಚಣಿ ವಂತಿಗೆಯನ್ನು ಮತ್ತು ಪ್ರಸ್ತುತ ಜಾರಿಯಲ್ಲಿರುವ ಉಪದಾನ ವಂತಿಗೆ ದರದಲ್ಲಿ ಆಕರಿಸುವುದು ಸೂಕ್ತವೆಂದು ಅಭಿಪ್ರಾಯಪಡಲಾಗಿದೆ.

8. ಸಿಬ್ಬಂದಿ/ಪಿಂಚಣಿದಾರರಿಗೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕ ವರದಿಯನ್ನು ಪ್ರತಿ ಆರ್ಥಿಕ ವರ್ಷದ ಅಂತ್ಯಕ್ಕೆ ಪಡೆಯುವ ಜವಾಬ್ದಾರಿಯು ಪ್ರಧಾನ ಉದ್ಯೋಗದಾತರಾದ ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳ ಮೇಲಿರುತ್ತದೆ. ಆದರೂ ಸಹ ನಿಗಮ ಮತ್ತು ಕಂಪನಿಗಳಲ್ಲಿನ ಅಧಿಕಾರಿ/ಸಿಬ್ಬಂದಿಯ ಅಂತರ ಬದಲಾವಣೆಗೆ ಅವಕಾಶವಿರುವುದರಿಂದ ಮತ್ತು ಹಿಂದಿನ ಬೋರ್ಡ್ ಆಫ್ ಟ್ರಸ್ಟೀಸ್ ಸಭೆಗಳಲ್ಲಿ ನಿರ್ಣಯಿಸಿದಂತೆ, 'ಕವಿಪ್ರನಿ ಮತ್ತು ವಿಸಕಂಗಳ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಟ್ರಸ್ಟ್' ಎಲ್ಲಾ ಕಂಪನಿಗಳ ಪರವಾಗಿ ಕ್ರೋಢೀಕೃತ ವರದಿಯನ್ನು ಪಡೆಯುತ್ತಲಿದ್ದು, ಟ್ರಸ್ಟ್ ಸಭೆಯಲ್ಲಿ ಚರ್ಚಿಸಿ ದರ ಪರಿಷ್ಕರಣೆ ನಿರ್ಣಯಿಸಲಾಗುತ್ತಿದೆ. ಆದ್ದರಿಂದ, ಸದರಿ ವರದಿಯನ್ನು ಕೂಲಂಕುಶವಾಗಿ ಅಭ್ಯಸಿಸಿ ಮುಂದಿನ ಟ್ರಸ್ಟ್ ಸಭೆಯಲ್ಲಿ ದರ ಪರಿಷ್ಕರಣೆ ನಿರ್ಣಯ ಕೈಗೊಳ್ಳಲು ಅನುವಾಗುವಂತೆ ತಮ್ಮ ಅಭಿಪ್ರಾಯ ಮತ್ತು ಅನಿಸಿಕೆಗಳನ್ನು ವ್ಯಕ್ತಪಡಿಸಲು ಮುಂಚಿತವಾಗಿಯೇ ಸಿದ್ಧರಾಗಿರುವಂತೆ ಕೋರಿದೆ.

9. ಮುಂದುವರಿದು, ವರದಿಯಲ್ಲಿನ ಯಾವುದೇ ಅಂಶಗಳ (Assumptions), ಆತಂಕಗಳು (Apprehension) ಮತ್ತು ಇತರ ವಿಷಯಗಳ ಬಗ್ಗೆ ನೀಡಿರುವ ಸ್ಪಷ್ಟೀಕರಣಗಳನ್ನು ಅಭ್ಯಸಿಸಿ ಹೆಚ್ಚಿನ ಮಾಹಿತಿ ಹಾಗೂ ಸ್ಪಷ್ಟೀಕರಣ ಬೇಕಿದ್ದಲ್ಲಿ ಈ ಪತ್ರದ ದಿನಾಂಕದಿಂದ ಒಂದು ವಾರದೊಳಗೆ ವಿಷಯವನ್ನು ನಿರ್ದಿಷ್ಟವಾಗಿ ವಿಶ್ಲೇಷಿಸಿ ಈ ಕಛೇರಿಗೆ ತಿಳಿಸಲು ಕೋರಲಾಗಿದೆ. ತಮಗೆ ಅಗತ್ಯವಿರುವ ಸ್ಪಷ್ಟೀಕರಣವನ್ನು ಪ್ರಾತ್ಯಕ್ಷಿಕೆ ಮೌಲ್ಯಮಾಪಕರಿಂದ ಪಡೆದು, ತಮಗೆ ಕಳುಹಿಸುವುದರ ಜೊತೆಗೆ ವರದಿಗಳಲ್ಲಿನ ಅಂಶಗಳನ್ನು ಅನುಷ್ಠಾನಕ್ಕೆ ತರಲು ಮುಂದಿನ ಬೋರ್ಡ್ ಆಫ್ ಟ್ರಸ್ಟೀಸ್ ಸಭೆಯ ನಿರ್ಣಯಕ್ಕಾಗಿ ಮಂಡಿಸಲು ಕ್ರಮ ಕೈಗೊಳ್ಳಲಾಗುವುದು.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

  
ಆರ್ಥಿಕ ಸಲಹೆಗಾರರು & ಮೌಲ್ಯಮಾಪಕ ಟ್ರಸ್ಟಿ  
ಕವಿಪ್ರನಿ/ವಿಸಕಂಗಳ ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಟ್ರಸ್ಟ್

ಪ್ರತಿ:

ನಿರ್ದೇಶಕರು(ಪಣಕಾಳು), ಕವಿಪ್ರನಿ ಮತ್ತು ಅಧ್ಯಕ್ಷರು, ಪಿಂಚಣಿ ಮತ್ತು ಉಪದಾನ ಟ್ರಸ್ಟ್‌ರವರ ಹಿರಿಯ ಆಪ್ತ ಕಾರ್ಯದರ್ಶಿ.

**SOURCE WISE INSTALLED CAPACITY**

Source	Units	2018-19 (Upto Sept-18)
<b>Installed Capacity</b>		
<b>1. Public Sector</b>		
a) Hydel	MW	3667
b) Wind energy	MW	5
c) Thermal	MW	5020
d) Diesel plants	MW	0
e) Solar PV plant	MW	34
<b>Total</b>		<b>8726</b>
<b>f) Jurala Hydro</b>	<b>MW</b>	<b>117</b>
<b>2. Private Sector</b>		
g) IPP Thermal	MW	1200
h) Mini Hydel	MW	852
i) Wind energy	MW	4731.26
j) Co-generation & Biomass	MW	2767
k) Solar	MW	5154.29
<b>Total</b>		<b>14704</b>
<b>3. Central Generating Station Allocation</b>	MW	3693
<b>TOTAL INSTALLED CAPACITY</b>		<b>27240</b>

**Proposed generations expected to be commissioned during 2019-22:**

Source	Installed capacity in MW
Yelahanka Gas generation	350
Solar	1591
Wind	4058



**Annexure-7(b)**

- a) **The ESCOM-wise details of demand considered and methodology adopted in arriving at Demand forecast:** Rolling plan studies have been conducted for the period 2019-20, 2020-21 and 2021-22 with system peak load to match the state demand based on peak demand projection of ESCOMs (as per the load forecast study report submitted by ESCOMs). ESCOM wise peak demand in MW considered for study is as appended below.

<b>Financial Year</b>	<b>In MW</b>					
	<b>BESCOM</b>	<b>CESC</b>	<b>MESCOM</b>	<b>HESCOM</b>	<b>GESCOM</b>	<b>State</b>
2019-20	4967	1719	1290	2619	1533	<b>12128</b>
2020-21	5051	1858	1321	2787	1607	<b>12624</b>
2021-22	5187	2007	1354	2965	1682	<b>13195</b>

**PICTORIAL REPRESENTATION OF EXISTING AND PLANNED ADDITION**  
**OF TRANSMISSION CAPACITY:**

**Annexure-8****TERMINAL BENEFITS**

	<b>2018-19</b>	<b>2019-20</b>	<b>2020-21</b>	<b>2021-22</b>
Pension & Gratuity Contt.	204.67	244.03	285.26	332.64
NDCPS Cont. Existing	37.55	40.82	44.34	48.04
NDCPS Recruitment		1.75	1.77	
NDCPS Regularisation of JSA		1.13	1.13	
<b>TOTAL</b>	<b>242.22</b>	<b>287.73</b>	<b>332.50</b>	<b>380.68</b>

## Annexure-9

### a) Rationale for capital investment programme for FY 20, FY 21 and FY 22:

- i) **RE capacity addition in the State:** KPTCL has undertaken the development and strengthening of its transmission infrastructure specially to facilitate evacuation of power to be generated from these sources and to take care of the existing renewable generation in two phases.

#### Projects approved under Green Energy Corridor Phase-1:

Sl. No	Name of the Project	RE capacity	Status of work
1	Establishing 2x500 MVA, 400/220 kV sub-station at <b>Jagalur</b> , in Davangere district along with associated 400 kV and 220 kV lines.	Wind: <b>1240 MW</b> Solar: <b>745 MW</b>	Work under progress
2	Establishing 2x500 MVA, 400/220 kV sub-station at <b>Doni</b> , in Gadag district along with associated 400 kV and 220 kV lines.	Wind: <b>893 MW</b> Solar: <b>220 MW</b>	Commissioned
3	Establishing 2x100 MVA, 220/66 kV sub-station at <b>Hoasadurga</b> , in Chitradurga district along with associated 220 kV and 66 kV lines.	Wind: <b>102 MW</b> Solar: <b>20 MW</b>	Work under progress
4	Establishing 2x100 MVA, 220/110 kV sub-station at <b>Mugalkhod</b> , in Belgaum district along with associated 220 kV and 110 kV lines.	Wind: <b>161 MW</b>	NIT issued. Target to be completed by March 2020.
5	Establishing 2x100 MVA, 220/66 kV sub-station at <b>Shivanasamudram</b> , in Mandya district along with associated 220 kV and 66 kV lines.	MHS: <b>54 MW</b> Solar: <b>15 MW</b>	Work under progress
6	Construction of 220 kV SC line on DC towers from 400/220 kV Receiving station at Hiriyyur (PGCIL) up to 220/66/11kV sub-station (KPTCL) at Hiriyyur and Construction of 220kV	Wind: <b>222 MW</b> Solar: <b>407 MW</b>	Work under progress

	DC line from 220/66/11kV substation at Chitradurga up to 220kV substation at Hiriyur in the existing corridor of 220 kV SC line.		
7	Construction of 220kV DC line from 220 kV substation at Bidnal to LILO one of the circuits of the existing 220kV Narendra-Haveri DC line.	Wind: <b>579 MW</b> Solar: <b>90 MW</b>	Commissioned
8	Construction of 400 kV D/C line with Quad Moose conductor between <b>Rampura limits and proposed 400/220 kV Jagalur</b> sub-station.	Wind: <b>1240 MW</b> Solar: <b>745 MW</b>	Work under progress
9	Strengthening of 220 kV D/C line between <b>Gadag to Lingapura</b> switching station by replacing existing Drake by equivalent HTLS conductor.	Wind: <b>434 MW</b> Solar: <b>20 MW</b>	Line survey under progress.

**Projects approved under Green Energy Corridor Phase-2:**

Sl. No	Name of the Project	RE capacity	Status of work
1	Establishing 2X500 MVA, 400/220/110kV substation at Yalwar in B.Bagewadi Taluk, Bijapur district along with associated 400kV and 220kV lines.	Wind: <b>1371 MW</b> Solar: <b>174 MW</b>	Estimate under preparation
2	Establishing 2X100MVA, 220/110 kV substation at Ron in Gadag district along with associated 220kV and 110kV lines.	Wind: <b>150 MW</b>	Land acquisition under progress
3	Establishing 2X100MVA, 220/110 kV substation at Savalgi in Bagalkot district along with associated 220kV and 110kV lines.	Wind: <b>119 MW</b> Solar: <b>45 MW</b>	Estimate under preparation
4	Establishing 2X100MVA, 220/66 kV substation at P.D.Kote in Chitradurga district along with associated 220kV and 66kV lines.	Solar: <b>121 MW</b>	Land to be identified
5	Establishing 2 x 100 MVA, 220/66kV, with 1X12.5MVA 66/11kV Sub-Station at Hanagal	Solar: <b>97 MW</b>	Land to be identified

	in Chitradurga district.		
6	LILO of 2nd circuit of the existing 220 kV DC line running between 220 kV stations at Mahalingpura and Kudachi to 220 kV sub-station at Athani.	Wind: <b>351 MW</b> Solar: <b>40 MW</b> Co-gen: <b>202 MW</b>	Detailed line survey under progress
7	Conversion of existing 220 kV SC line to 220 kV DC line with Drake conductor running between 220 kV stations at Bidnal, Saundatti and Mahalingpura	Wind: <b>169 MW</b> Solar: <b>34 MW</b> Co-gen: <b>294 MW</b>	Detailed line survey under progress
8	Strengthening of 220 kV Lingapura-Ittagi-Neelagunda-Guttur SC line by replacing SC line with Drake conductor by 220 kV DC line using Drake conductor.	Wind: <b>391 MW</b> Solar: <b>272 MW</b>	Detailed line survey under progress

- ii) **24x7 Power for All:** KPTCL has initiated action on implementing 24x7 power supply to all consumers. In view of this adequacy of transmission network has been evaluated and planned accordingly. Proposals for establishing new sub-stations, Augmentation and line strengthening under this program are under review. Zone wise details of works approved under "24x 7 Power for All" program is as follows:

Sl. No	Transmission Zone	Total no. of works	Sub-station	Augmentation
1	Bagalkot	16	6	10
2	Bengaluru	12	1	10
3	Hassan	5	1	4
4	Mysore	10	-	10
5	Tumakuru	12	4	8
6	Gulbarga	2	-	2

- iii) Existing and Approved Installed capacity of RE sources(Wind & Solar) is as follows:

TYPE OF RES	CAPACITY CONNECTED TO GRID	APPROVED CAPACITY TO BE CONNECTED
WIND	4731.26	4058
SOLAR	5154.29	1591

Detailed load flow study is being carried out regularly to check the feasibility for evacuation of RE power for normal and contingency conditions. Studies are conducted for each RE project and evacuation scheme is proposed with most economical and reliable to evacuate the RE generation meeting all CEA Planning Guidelines. To facilitate the evacuation of RE power, KPTCL has planned to build transmission infrastructure with transmission capacity of about 4920 MVA and transmission lines of about 2800 ckms.

**Financing Capital Expenditure**

	<b>2018-19</b>	<b>2019-20</b>	<b>2020-21</b>	<b>2021-22</b>
<b>Equity from GoK</b>	100.00	100.00	100.00	100.00
<b>Borrowings from Commercial Bar</b>	2342.17	2607.97	2669.65	2687.70
<b>Internal Resources</b>	400.00	500.00	500.00	500.00
<b>Central Grant</b>	100.00			
<b>Total</b>	<b>2942.17</b>	<b>3207.97</b>	<b>3269.65</b>	<b>3287.70</b>



## Capital Works planned for 5th MYT period

New projects viz. sub-station works, Augmentation of transmission lines, Augmentation of sub-stations

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
1	<b>Chikkanayakanahalli 400kV:</b> Establishing 400KV switching station at Chikkanayakanahalli	BESCOM	Tumakuru	Tumakuru			25000	YTPS Evacuation scheme	1	3000	5000	15000
2	400 kV Kalaburagi Switching Station : Establishment of 400/220 kV Sub Station at Kalaburagi	GESCOM	Kalaburagi	Kalaburagi			47401.63	YTPS Evacuation scheme	1	8000	10000	20000
3	Establishing 2x500 MVA ,400/220 kV GIS sub-station at existing SRS, Peenya premises	BESCOM	Bengaluru	Bangalore Urban			43345.86	System improvement	0	8500	10000	20000
4	400kV S/s Dommasandra: Establishing 2X500 MVA, 400/220kV GIS Sub-station at Dommasandra with associated 400kV source line and 220kV evacuation lines.	BESCOM	Bengaluru	Bengaluru Rural			45000	System improvement	0	1000	3000	30000
5	Yalwar: Establishing 2x500 MVA, 400/220 KV S/S at Yalwar in B.Bagewadi Tq., Vijayapur Dist.	HESCOM	Bagalkote	Vijayapur			20000	Green Energy Corridor Phase II	0	100	2000	15000
<b>Sub-station augmentation- 400 kV</b>												
1	Providing 3rd 500 MVA, 400/220kV Power Transformer and 220kV Terminal bays at KIADB Hardware Park, Devanahalli, Bengaluru Rural District.	BESCOM	Bengaluru	Bangalore Urban			2820	System improvement	0	564	1410	846
<b>Transmission line works-400 kV</b>												
1	400 KV BTPS from Rampura Limits to Chikkanayakanahalli: a) Construction of 400 KV Quad Moose DC Line from 400 KV Rampura Limits to Jagaluru Limits for 65Kms b) Construction of 400 KV Quad Moose DC Line from 400 KV Jagaluru Limits to Chikkanayakanahalli for 123.69Kms	BESCOM	Tumakuru	Tumakuru			55124.32	B) YTPS Evacuation scheme	5000	5000	17500	9800
<b>Sub-station Works- 220 kV</b>												
1	EXORA Business park: Establishing 2x150MVA, 220/66/11kV Station with associated line.	BESCOM	Bengaluru	Bengaluru Urban			10403.9	System improvement	10	1000.0	4000.0	5393.9
2	<b>Nelamangala:</b> Upgradation of existing 66/11kV Nelamanagala S/s to 2x100 MVA, 220/66/11kV sub station	BESCOM	Bengaluru	Bengaluru Urban			8740.0	System improvement	5	1000.0	2000.0	5735.0
3	<b>Sahakarinaragar:</b> Establishing 2x150 MVA, 220/66/11kV GIS sub station	BESCOM	Bengaluru	Bengaluru Urban			14960.7	System improvement	10	1000.0	4000.0	9000.0
4	<b>Sira(Kallukote) :</b> Establishing 2x100MVA, 220/66/11kV Sub-station with associated line	BESCOM	Tumakuru	Tumakuru			5844.6	System improvement	50	1000.0	2000.0	2794.6

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
5	<b>Heggunje :</b> Establishing 2x100 MVA, 220/110 kV , 1x10 MVA 110/11kV Sub Station at Heggunje in Udupi Tq & Dist with Construction of 220/110kV MCMV LILo line from 220kV Varahi-Kemar SC line and 110kV Haladi-Hiriyadka SC line to proposed 220/110/11kV Station at Heggunje and a) Construction of 110kV DC line from the proposed Heggunje Station to the existing 110/11kV Brahmavara S/S for a dist of 17.5Kms b) Construction of 110kV DC line on Conventional, 110kV MC and 220/110kV MC towers from the proposed Heggunje Station to the existing Kundapura S/S for a dist of 25Kms. c) Construction of 2Nos of TB's for 110kV Heggunje-Brahmavara DC line at 110/11kV S/S Brahmavara d) Construction of 2Nos of 110kV TN's for 110kV Heggunje-Kundapura DC line at Kundapura S/S	MESCOM	Hassana	Udupi			7996.8	System improvement	500	2000.0	3998.4	1498.4
6	220kV Nagamangala: Establishing 2X100MVA, 220/66kV Station with associated lines	CESC	Mysuru	Mandya			9000.0	System improvement	1	500.0	2000.0	6000.0
7	<b>220kV Begur:</b> Establishing 2X100MVA, 220/66kV Station with associated lines	CESC	Mysuru	Chamarajanagara			11814.8	System improvement	1	2000.0	4000.0	5000.0
9	Ghanagapura: Establishing 2x100MVA, 220/110/11kV Station with associated 220kV and 110kV lines.	GESCOM	Kalaburagi	Kalaburagi			6911.7	System improvement	1	1000.0	2000.0	3910.7
10	<b>Sindagi:</b> Establishing 220/110kV Receiving Station with associated 220kV and 110kV lines	HESCOM	Bagalkote	Bijapur			11180.0	System improvement	0	300.0	5590.0	5290.0
11	Establishing 2X150MVA, 220/66/11kV Sub-Station at Nagarbhavi, Bangalore North Taluk, Bangalore Urban District - 220 kV Incoming lines. Further it was instructed to CEE, TRZ, Bengaluru to explore the alternate 220 kV incoming line to proposed Nagarbhavi s/s in view of upstream loading restriction at proposed 400 kV Peenya s/s .	BESCOM	Bengaluru	Bangalore Urban			5410.0	System improvement	0	100.0	1500.0	3000.0
12	Establishing 2x150 MVA, 220/66 kV sub-staion at HBR Layout along with 220 kV Incoming line and additional 220 kV evacuation lines from 400/220 kV Devanahalli to link 220kV Nelamangala-Hoody DC line	BESCOM	Bengaluru	Bangalore Urban			16718.0	System improvement	0	2000.0	8000.0	6718.0
13	<b>Hunsur:</b> Establishing 220kV Station with 220kV line and 66kV evacuation lines .	CESC	Mysuru	Mysuru			6000.0	System improvement	0	100.0	2000.0	3000.0

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
14	Adakanahalli: Establishing 2X100MVA, 220/66kV R/s & 2X12.5MVA66/11kV S/s with associated lines	CESC	Mysuru	Mysuru			8000.0	System improvement	0	100.0	2000.0	4000.0
15	Establishing 2X150MVA, 220/66/kV Gas Insulated Switchgear sub-station at Shobha Dreams	BESCOM	Bengaluru	Bangalore Urban			10000.0	System improvement	0	1000.0	3000.0	5000.0
16	Huliyurdurga 220/66 kV: Establishing 2x100 MVA, 220/66 kV sub-station at Huliyurdurga.	BESCOM	Tumakuru	Tumakuru			9473.4	System improvement	0	100.0	1000.0	7000.0
17	Srinivasapura: Establishing 2x100MVA, 220/66kV Station with associated lines	BESCOM	Bengaluru	Kolar			8000.0	System improvement	0	10.0	100.0	6000.0
18	Establishing 2X100MVA, 220/66 kV Sub-Station at P D Kote in Hiriyur Taluk, Davanagere District.	BESCOM	Tumakuru	Davanagere			8500.0	Green Energy Corridor Ph-II	0	100.0	3000.0	5000.0
19	Establishing 2X100MVA, 220/66 kV Sub-Station near 66/11 kV Hangal sub-station, Davanagere District.	BESCOM	Tumakuru	Davanagere			8500.0	Green Energy Corridor Ph-II	0	100.0	3000.0	5000.0
20	Bhramasagara: Establishing 2x100MVA, 220/66/11kV Sub-station with associated line	BESCOM	Tumakuru	Chitradurga			6800.9	System improvement	0	100.0	2000.0	3000.0
21	Sirvara: Establishing 2x100MVA, 220/66/11kV Sub-station with associated line	BESCOM	Tumakuru	Tumakuru			6500.0	System improvement	0	100.0	2000.0	3000.0
22	Kaniyaru: Establishing 1X100MVA and 1X8MVA ,220/66/11kV substatopn near Kaniyaru village in Arakalagudu TQ,Hassan dist with associated 220kV and 66kV lines	CESC	Hassana	Hassan			6000.0	System improvement	0	100.0	2000.0	3000.0
23	Maddur : Establishing 220/66 kV Gas Insulated Substation .	CESC	Mysuru	Mandya			9000.0	System improvement	0	100.0	1000.0	6000.0
24	Bilagi: Establishing 2x100 MVA, 220/110 kV S/S with associated line.	HESCOM	Bagalkote	Bagalkot			6250.0	System improvement	0	100.0	1000.0	4000.0
25	Gangavathi: Establishing 220/110/11kV Receiving Station	GESCOM	Kalaburagi	Koppal			6000.0	System improvement	0	100.0	2000.0	3000.0
<b>Transmission line Works- 220 kV</b>												
1	Kadakola - Vajamangala: Construction of 220kV D/C line from Kadakola to Vajamangala with TB's for a distance of 19.64Kms	CESC	Mysuru	Mysuru			1052.7	System improvement	10	50.0	384.4	164.7
2	<b>220-220kV MC line to 220/66/11kV Yerranadanahalli S/s:</b> Construction of 220-220kV Narrow based Multi Circuit Lines for route length of 6.615kms from the proposed 220kV Sommanahally-Malur I & II Lines to the exisisting 220/66/11kV Yarandanahally S/s in exisisting 220kV Sommanahally-Singarpet SC line Corridor	BESCOM	Bengaluru	Bengaluru Urban			1550.6	System improvement	10	500.0	700.0	340.6

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
3	<b>Kanakapura- Kothipura 220 kV S/s:</b> Interlinking of existing 220/66 kV Kanakapura sub-station with proposed 220 kV Kothipura S/s by construction of 220 kV DC line for a distance of 27 Kms.	BESCOM	Bengaluru	Ramanagara			5798.0	System improvement	5	2319.2	1739.4	1159.6
4	<b>Shimoga-Bengaluru 1 &amp; 2 lines:</b> Re-stringing of existing Drake Conductor, replacing of Ground Conductor, Disc Insulators, Hardwares of 220kV Shimoga-Bengaluru 1 & 2 DC line from MRS Shimoga to Basavanahalli gate (Loc.No.1 to 269)	BESCOM	Hassana	Shimoga			289.5	Line strengthening	1	144.8	52.0	
5	<b>Hootgalli-Kanayanbetta upto Bavali limit:</b> Re-Construction of 220kV Hootgalli-Kanayanbetta line upto Bavali limit for a distance of 81kms as per Southern Grid instruction.	CESC	Mysuru	Mysuru			415.2	Line strengthening	10	100.0	200.0	105.2
6	<b>Somanahalli Station to T.K.Halli Station:</b> Construction of 220kV DC line on DC towers in the existing SC corridor	BESCOM	Bengaluru	Ramanagara			5000.0	Line strengthening	0	500.0	1000.0	2500.0
7	Construction of 220 kV multi-circuit, multi-voltage line between 400/220 kV Somanahalli and 220/66 kV Subramanyapura s/s in the existing 66 kV line corridor.	BESCOM	Bengaluru	Bangalore Urban			8030.0	System improvement	0	1000.0	3000.0	4030.0
<b>Sub-station augmentation- 220 kV</b>												
1	<b>220KV EKARAJAPURA:</b> Additional 220/66kV,100MVA Transformer.	BESCOM	Bengaluru	Bengaluru Rural			1351.0	Existing Transformer overload	5	500.0	846.0	
2	<b>Bagalkot:</b> 3rd 1x100MVA Transformer at 220/110KV Bagalkote S/s	HESCOM	Bagalkote	Bagalkote			728.9	Existing Transformer overload	1	300.0	218.7	209.2
3	<b>Hassan 220:</b> Providing additional 1x100 MVA, 220/66kV power transformer at 220/66 kV Hassan Receiving station in Hassan District.	CESC	Hassana	Hassana			922.9	Existing Transformer overload		100.0	461.4	361.4
4	Providing additional 1x100 MVA, 220/66 kV transformer at 220/66 kV Thallak sub-station.	BESCOM	Tumakuru	Tumakuru			920.0	Existing Transformer overload		100.0	460.0	360.0
5	Kanakapura: Providing 1X100MVA, 220/66kV Power transformer as SPARE with associated terminal bay.	BESCOM	Bengaluru	Ramanagara			900.0	System improvement		100.0	450.0	350.0
6	Doddaballapura : Providing additional 1X100MVA, 220/66kV Power transformer at Doddaballapura S/s.	BESCOM	Bengaluru	Bengaluru Rural			1030.4	Existing Transformer overload		100.0	515.2	415.2
7	Providing spare 1X100MVA, 220/66kV Power transformer at 220/66kV Malur sub-station.	BESCOM	Bengaluru	Kolar			700.0	System improvement		10.0	190.0	500.0
8	Providing 1 x 100MVA, 220/66KV Power Transformer with 66KV bus coupler and 4 Nos. of 66kV bays at 220KV MRS Shivamogga	MESCOM	Hassana	Shimoga			700.0	Existing Transformer overload		10.0	300.0	390.0
9	Kadakola R/S : Spare 1X100 MVA 220/66/11kV Power Transformer	CESC	Mysuru	Mysuru			700.0	System improvement		10.0	200.0	490.0

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
10	Belagavi: Providing 3 rd 100 MVA ,220/11 KV Transformer at 220 KV Belagavi Receiving Station , Belagavi Dist	HESCOM	Bagalkote	Belagavi			755.0	Existing Transformer overload	50	250.0	455.0	
11	Sirsi: Providing additional 1X50MVA,220/110kV Trf at 220kV Sirsi(Else) S/S.	HESCOM	Bagalkote	Uttara Kannada			650.0	Existing Transformer overload		10.0	300.0	340.0
12	220 KV Chikkodi Providing additional 3rd 1X100 MVA ,220/110 KV Power Transformer at 220/110/11 KV Chikkodi Sub Station in Belagavi District	HESCOM	Bagalkote	Belagavi			755.0	Existing Transformer overload		151.0	453.0	151.0
13	220 KV Ghataprabha Providing additional 1X100 MVA ,220/110 KV Power Transformer at 220/110/11 KV Ghataprabha Sub Station in Belagavi District	HESCOM	Bagalkote	Belagavi			755.0	Existing Transformer overload		151.0	453.0	151.0
14	Additional 100 MVA, 220/110 kV transformer at 220/110/11 KV Athani	HESCOM	Bagalkote	Belgaum			750.0	Existing Transformer overload		50.0	200.0	500.0
15	Allipur: Providing spare 100 MVA, 220/110 kV Power Transformer at 220 kV R/S Allipur	GESCOM	Kalaburagi	Bellary			700.0	System improvement		140.0	420.0	140.0
16	Augmentation of 2*100MVA by 2*150MVA Power Transformer 2 & 3 at 220kV R/S Hoody	BESCOM	Bengaluru	Bengaluru Urban			1500.0	Existing Transformer overload		300.0	900.0	300.0
<b>Other works-220 kV</b>												
1	<b>Kavoor:</b> R & M Works at Kavoor 220kV Station.	MESCOM	Hassana	Dakshina Kannada			1948.2	System improvement	1	100.0	1000.0	847.2
2	Formation of <b>220KV rigid bus</b> at 220KV RS, Kemar	MESCOM	Hassana	Udupi			236.9	System improvement	1	165.8	70.1	
3	<b>Munirabad Power House Station:</b> Shifting of existing Control Room at 220kV Munirabad Power House to existing work shop building at 220kV Munirabad Power House yard	GESCOM	Kalaburagi	Koppal			315.8	System improvement	1	100.0	213.8	
4	<b>Guddadahalli:</b> Providing Bus Bar protection to 220kV KPTCL Bays at 400/220kV, Guddadahalli, PGCIL Sub-station in Koppal Taluk and District	GESCOM	Kalaburagi	Koppal			160.4	System improvement	100	48.1	12.3	
<b>Sub-station Works- 110 kV</b>												
1	<b>Karadi:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	BESCOM	Tumakuru	Tumakuru			590.7	System improvement	50	378.5	162.2	

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
2	<b>Belapu :</b> Establishing 1x10MVA, 110/11kV Sub-Station at Belapu in Udupi Tq & Dist with construction of 110kV SC line on DC towers from the proposed 110kV Nandikur S/S for a dist of 10Kms with 110kV TB at Nandikur	MESCOM	Hassana	Dakshina Kannada			964.9	System improvement	1	10.0	289.5	386.0
3	<b>Sulia:</b> Establishing 2x10MVA, 110/11kV, 1x20MVA, 110/33-11kV Sub-Station with associated line.	MESCOM	Hassana	Dakshina Kannada			1492.0	System improvement	1	10.0	447.6	596.8
4	<b>Belman(Nandalike):</b> Establishing 1x10MVA, 110/11kV s/s at Belman(Nandalike) (in Karkala Taluk, Udupi district with associated line for a distance of 1.031 Kms.	MESCOM	Hassana	Udupi			878.8	System improvement	1	527.3	350.5	
5	<b>Singatalur :</b> Up-gradation of existing 33/11kV MUSS to 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Gadag			1033.4	System improvement	1	300.0	500.0	232.4
6	<b>Banavasi:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line & TB.	HESCOM	Bagalkote	Uttar Kannada			938.4	System improvement	1	300.0	500.0	137.4
7	<b>Shiraguppi:</b> Up-gradation of 33kV MUSS to 1x10MVA, 110/11kV Sub-Station with associated line for a distance of 16.7 kms & TB.	HESCOM	Bagalkote	Belgaum			1075.4	System improvement	1	300.0	500.0	274.4
8	<b>Bayappur:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Raichur			1229.0	System improvement	5	100.0	750.0	374.0
9	<b>Kukanoor(Dyamapura) :</b> Upgradation of 2x5MVA,33/11kV Sub-station to 2x10MVA, 110/11kV and 1x20MVA 110/33kV Sub-station Kukanoor(Dyamapura) in Yelburga Taluk.	GESCOM	Kalaburagi	Koppal			1600.1	System improvement	10	500.0	1000.0	90.1
10	<b>Ukkali :</b> Establishing 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Vijayapura			920.0	System improvement	1	100.0	500.0	319.0
11	<b>Ronihal:</b> Establishing 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Bijapur			1097.3	System improvement	1	500.0	596.3	
12	<b>Alnavar:</b> Up-gradation of 33/11kV sub-station to 2x10MVA, 110/11kV & 1x20 MVA, 110/33 kV Sub-station with 110 kV SC line from 110 kV Halyal S/S.	HESCOM	Bagalkote	Dharwad			1757.1	System improvement	0	500.0	1257.1	
13	<b>Yakatpur (Mannalli):</b> Establishment of 2x10MVA 110/11 kV S/S at Yakatpur (Mannalli)	GESCOM	Kalaburagi	Bidar			1251.8	System improvement	0	100.0	625.9	525.9
14	<b>Halyal:</b> Up-gradation of existing 33/11kV MUSS to 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Belgaum			961.0	System improvement	0	100.0	480.5	380.5

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
15	<b>Siddakatte:</b> Establishing 2x10MVA, 110/11kV Sub-Station at Siddakatte in Bantwala Tq, D.K.Dist with Construction of 110kV LILo line with Lynx ACSR conductor for a dist of 2.52Kms from one circuit of the proposed Moodabidri- Mulibettu 110kV DC line to the proposed 110/11kV S/S at Siddakatte.	MESCOM	Hassana	Dakshina Kannada			900.0	System improvement	0	180.0	450.0	90.0
16	<b>Hosmar:</b> Establishing 1x10MVA, 110/11kV Sub-Station at Hosmar in Karkala tq, Udupi Dist with construction of 110kV LILo line from 220/110kV Multi circuit Kemar-Guruvayankere line to the proposed 110/11kV S/S at Hosmar for a dist of 0.14Km	MESCOM	Hassana	Udupi			650.0	System improvement	0	130.0	325.0	65.0
17	<b>Diggewadi:</b> Establishing 2x10MVA, 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Belgaum			1024.0	System improvement	0	512.0	204.8	102.4
18	<b>Gosbal:</b> Establishing 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Belgaum			1177.1	System improvement	0	588.5	235.4	117.7
19	Establishing 2 x 10 MVA, 110/11 kV sub-station at Jumnal in Vijayapura Taluk, Vijayapura District	HESCOM	Bagalkote	Vijayapur			1000.0	System improvement	0	200.0	200.0	500.0
20	<b>Ashapur Road:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Raichur			750.0	System improvement	0	150.0	375.0	150.0
21	<b>Gandhi Nagar:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Raichur			775.0	System improvement	0	155.0	387.5	155.0
22	<b>Ballatgi :</b> Establishing 1 x10 MVA, 110/11 Kv S/S at Ballatgi along with associated 110kV Line in Manvi Taluka	GESCOM	Kalaburagi	Raichur			750.0	System improvement	0	150.0	375.0	75.0
23	<b>Tavergera:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Kalaburgi			750.0	System improvement	0	150.0	375.0	75.0
24	<b>M-Kollur:</b> Establishing of 1X10MVA, 110/11kV Sub-Station at M-Kollur Village in Shahapur Tq, Yadgir Dist.	GESCOM	Kalaburagi	Yadgir			750.0	System improvement	0	150.0	375.0	75.0
<b>Transmission line Works- 110 kV</b>												
1	<b>Shimoga Station to 220kV Kadur Station:</b> Construction of 110kV SBT-2DC line on DC tower for a distance of 60.281 kms in the existing Corridor of 110 KV SBT-2 SC line from 220/110/66/11 KV M.R.S Shivamogga to 220/110/11KV Kadur Station along with Construction of 110KV TB at 220KV M.R.S Shivamogga and 220KV Kadur Sation	MESCOM	Hassana	Chikkamagaluru			2134.06	Line strengthening	10	1493.84	500	130.218

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
2	<b>110KV Kawalwad-Hubli Line:</b> Replacing of Existing Dog/Wolf conductor by Lynx Conductor of 110KV NK1 & NK2 Line from 110KV Kavalavad S/s 220KV SRS Hubali S/s for a distance of 32kms along with strengthening of line by replacing weakened Towers for a distance of 32Kms	HESCOM	Bagalkote	Dharwad			869.92	Line strengthening	1	200	400	268.92
3	<b>220KV SRS Hubli -220kv Haveri Station:</b> Conversion of existing S/C line on /SC Towers to SC line from 220/110KV SRS Hubli R/S to 220/110KV Haveri Station for a length of 68Kms	HESCOM	Bagalkote	Dharwad/Haveri/Uttara Kannada			2218.56	Line strengthening	1	200	700	1317.56
4	<b>Gadag-Naregal-Ron:</b> Conversion of 110KV SC line to DC line from 220KV Gadag S/s to 110KV Naregal S/s and Stringing of 110KV 2nd Circuit from 110KV Naregal S/s to 110KV Ron S/s for a distance of 28.57 & 16.795Kms	HESCOM	Bagalkote	Gadag			1246.4	To relieve line overload	1	200	700	345.4
5	<b>Jog-Sirsi:</b> Replacement of Existing Towers Dog/Coyote Conductor by new towers and Lynx Conductor of 110KV NK1 & NK-2 DC line form MGHE PH Jog to 110KV Sirsi S/s for A distance of 49.71 Kms	HESCOM	Bagalkote	Uttar Kannada/Shimogga			1534.87	Line strengthening	1	200	700	633.87
6	<b>Sirsi and Kavalawada line</b> Replacement of 110KV Dog/coyote ACSR conductor by Lynx conductor of NK-1 and NK-2 lines between Sirsi and Kavalawada for a distance of 67.376Kms	HESCOM	Bagalkote	North Canara			1560.53	Line strengthening	1	200	700	659.53
7	<b>Ambewadi - Kawalwad Line:</b> Replacement of deteriorated and rusted 19 Nos. of MS towers and Dog and coyote conductor by lynx conductor of 110KV NK-1 & 2 D/C Line between Ambewadi and Kawalwad.	HESCOM	Bagalkote	Uttar Kannada			850.28	Line strengthening	1	200	500	149.28
8	<b>Alipur to Bellary(South):</b> Stringing of 110KV 2nd Circuit on existing DC towers from Alipur Station to Bellary (South) Sub-Station for a distance of 8.00 Km.	GESCOM	Kalaburagi	Bellary			51.95	Line strengthening	1	31.17	19.78	
9	<b>Betagera to proposed 220kv Station at Koppal:</b> Construction of 110KV SC line on DC towers from proposed 220/110/11KV Halavarthy(Koppal) S/s to the existing 110/33/11KV Betagera S/s for a distance of 23.836Kms	GESCOM	Kalaburagi	Koppal			1029.46	Line strengthening	10	300	308.838	410.622



**Capital works planned for 5th MYT period**

**Sub-station works- 400 kV**

**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
10	a) Construction of 110KV LILO line to 110/11KV <b>Kamalapura</b> sub-station on the existing DC towers from the tapping point for a distance of 5.8Kms in Bellary Taluk and District. b) Construction of 110KV Terminal bay for the proposed 110KV LILO line at existing 110/11KV <b>Kamalapura</b> sub-station on the existing DC towers from the tapping point for a distance of 5.8Kms in Bellary Taluk and District.	GESCOM	<b>Kalaburagi</b>	Bellary			86.33	Line strengthening	1	10	75.33	
11	a) Construction of 110KV LILO line to 110/11KV <b>Bisilahalli</b> sub-station on the existing DC towers from the tapping point for a distance of 1.906Kms in Bellary Taluk & District. b) Construction of 110KV Terminal Bay for the proposed line to 110KV/11KV <b>Bisilahalli</b> Substation on the existing DC towers from the tapping point for a distance of 1.906Kms in Bellary Taluk & District.	GESCOM	<b>Kalaburagi</b>	Bellary			57.37	Line strengthening	1	10	46.37	
12	<b>Vitla Sub-Station :</b> Construction of 1 No. of 110KV Terminal Bay at existing 110KV Vitla substation for making LILO of the proposed 110KV Line from existing 110KV Netlamandur-Salethur SC Line for a Distance of 0.55 with 110KV MC towers.	MESCOM	<b>Hassana</b>	Dakshina Kannada			262.38	Line strengthening	1	100	161.38	
13	Re-conductoring of the existing Lynx conductor by drake conductor of 110kv <b>Kemar-Hiriyadka-Mudabidare</b> DC line between <b>Khemar</b> 220kv substation and Kuntalpady village limits (from Loc 01 to Loc 16) for a distance of 1.727Kms in Karakala Taluk.	MESCOM	<b>Hassana</b>	Udupi			84.59	Line strengthening	1	50	33.59	
14	<b>Linganamakki to Iduvani:</b> Re-construction of two numbers of 110kv Dc lines from iduvani limits to Linganamakki power House in the existing corridor of 110kv JLT-3&4 DC line(4.6 Kms) and 110kv LST-3 &4 DC line (4.7Kms) using Lynx conductor for a distance of 9.28kms in Shimoga District.	MESCOM	<b>Hassana</b>	Shimoga			566.76	Line strengthening	1	50	515.76	
15	Construction of 2nd circuit line from 220kv <b>Shahapur</b> to <b>Khanapur</b> on existing DC tower for a distance of 19.25 Kms & TB at both ends.	GESCOM	<b>Kalaburagi</b>	Yadgir			433.64	Line strengthening		86.728	216.82	130.092

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
16	B.Bagewadi - Shahabad-Moratagi line : Replacement of MS towers by GI towers along with conductor and ground wire from 220kV S/S B.Bagewadi to 220kV S/S Shahabad-up to Moratagi S/S (Loc.No194 to 415)	HESCOM	Bagalkote	Bijapur			3276	Line strengthening		300	1638	1338
17	Construction of 110 KV SC Line Line on DC Towers with Lynx Conductor from 110 KV Ainapur to 110 KV Kagwad Sub Station for a distance of 25 Kms in Belagavi Dist (Approved 110 KV Link Line between proposed 110 KV Shiraguppi and existing 110 Kagwad Sub Station for a distance of 9 Kms)	HESCOM	Bagalkote	Belgaum			450	Line strengthening		90	225	135
18	Conversion of 110 KV SC Line on SC Towers (Partially MS and Partially GI) by DC Line with GI Towers from 220 KV Mahalingpur S/S to 220 KV Athani S/s from Loc No-1 to 117 in Bagalkot and Belagavi Dist	HESCOM	Bagalkote	Belagavi-Bagalkot			1272	Line strengthening		100	636	536
19	Conversion of 110 KV SC Line on SC towers to DC towers from 220 KV Mahalingpur S/S to 110 KV Yalaparhatti S/S in Bagalkot / Belagavi Dist	HESCOM	Bagalkote	Belagavi-Bagalkot			1215	Line strengthening		100	607.5	507.5
20	New proposal for alternate power supply to 110kV Akshay Colony S/s to 110kV Tarihal S/s by installing 110kV U.G. Cables for about 5 kms.	HESCOM	Bagalkote	Dharwad			5564	Line strengthening		500	2782	2282
21	Providing LILO arrangement 110KV SS2 line 110/11KV MUSS at Kumsi sub-station.	MESCOM	Hassana	Shimoga			177	Line strengthening		35.4	88.5	53.1
<b>Sub-station augmentation- 110 kV</b>												
1	<b>Doddaguni:</b> Providing Spare 1x10MVA, 110/11kV Transformer	BESCOM	Tumakuru	Tumakuru			186.2	System improvement	1	130.3	54.9	
2	<b>K.B Cross:</b> Providing Spare 1x20 MVA, 110/11 kV Power Transformer at 110/11kV Station in K.B.Cross	BESCOM	Tumakuru	Tumakuru			307.0	System improvement	1	214.9	91.1	
3	<b>Huliyar:</b> Providing Additional 1x10MVA, 110/11kV Power Transformer at 110/11kV Station.	BESCOM	Tumakuru	Tumakuru			253.9	Existing Transformer overload	100	126.9	26.9	
4	<b>Kadaba:</b> Replacing 1x10 MVA,110/11kV by 1x 20 MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			204.2	Existing Transformer overload	50	142.9	11.3	
5	<b>Sampige:</b> Replacing 1x10MVA,110/11kV by 1x 20MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			204.2	Existing Transformer overload	100	102.1	2.1	
6	<b>K.G Temple:</b> Replacing 1x10MVA,110/11kV by 1x 20MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			204.5	Existing Transformer overload	100	102.3	2.3	
7	<b>Kallur:</b> Replacing 1x10 MVA,110/11kV by 1x 20 MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			204.5	Existing Transformer overload	100	102.3	2.3	
8	<b>MSEZ:</b> Providing 1 x20 MVA, 110/33/11kV Transformer as spare at 110KV Station MSEZ, Bage in Mangalore Taluk, KDK Dist	MESCOM	Hassana	Dakshina Kannada			285.4	System improvement	10	142.7	132.7	

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
9	<b>Konnur:</b> Providing additional 1x10MVA, 110/11kV Power Transformer at 110kV Konnur S/s.	HESCOM	<b>Bagalkote</b>	Gadag			281.4	Existing Transformer overload	10	100.0	171.4	
10	<b>110KV S/S Nagaramunnoli/Kabbur</b> Replacement of 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer	HESCOM	<b>Bagalkote</b>	Belgaum			247.7	Existing Transformer overload	50	148.6	49.1	
11	<b>110 kV S/S Sulthanpur :</b> Replacement of 1x10 MVA, 110/11 kV transformer by 1x20 MVA, 110/11 kV transformer at 110 kV Sulthanpur sub-station, in Raibag Taluk, Belagavi District	HESCOM	<b>Bagalkote</b>	Belgaum			93.1	Existing Transformer overload	10	55.9	27.2	
12	<b>Shiragaon :</b> Replacing 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer	HESCOM	<b>Bagalkote</b>	Belgaum			286.8	Existing Transformer overload	10	100.0	176.8	
13	<b>Hirebagewadi:</b> Augmentation of 10 MVA ,110/11 KV by 20 MVA, 110/11 KV Power Transformer at 110 KV S/S Hirebagewadi	HESCOM	<b>Bagalkote</b>	Belgaum			295.1	Existing Transformer overload	10	100.0	185.1	
14	<b>110 kV S/S Satti :</b> Providing additional 1x10 MVA, 110/11 kV transformer at 110 kV Satti sub-station, in Athani Taluk, Belagavi District	HESCOM	<b>Bagalkote</b>	Belgaum			289.8	Existing Transformer overload	10	100.0	179.8	
15	<b>110 kV S/S Itnal :</b> Replacement of 1x10 MVA, 110/11 kV transformer by 1x20 MVA, 110/11 kV transformer at 110 kV Itnal sub-station, in Raibag Taluk, Belagavi District	HESCOM	<b>Bagalkote</b>	Belgaum			282.0	Existing Transformer overload	10	100.0	172.0	
16	<b>110 kV S/S Bisnal :</b> Creating 33 kV reference by installing 1x20 MVA, 110/33 kV transformer at 110 kV Bisnal sub-station, in Bilagi Taluk, Bagalkot District	HESCOM	<b>Bagalkote</b>	Bagalkote			320.3	Existing Transformer overload	10	100.0	210.3	
17	<b>Muddebihal:</b> Providing additional 1x10MVA, 110/33kV Transformer	HESCOM	<b>Bagalkote</b>	Bijapur			179.3	Existing Transformer overload	10	100.0	63.6	
18	<b>Valkamdinni:</b> Replacement of 1x10MVA by 1x20MVA 110/33KV Power Transformer at 110KV S/S Walkamdinni.	GESCOM	<b>Kalaburagi</b>	Raichur			202.3	Existing Transformer overload	1	50.0	151.3	
19	<b>Sindhanoor:</b> Replacement of 1x10MVA by 1x20MVA 110/11KV Power Transformer at 110KV S/S Sindhanoor	GESCOM	<b>Kalaburagi</b>	Raichur			217.6	Existing Transformer overload	5	50.0	162.6	
20	<b>Raichur:</b> Providing spare 10 MVA, 110/11 kV Power Transformer at 220 kV R/S Raichur	GESCOM	<b>Kalaburagi</b>	Raichur			227.8	System improvement	1	50.0	176.8	
21	<b>Somasamudra:</b> Providing additional 1x10MVA, 110/11kV Transformer	GESCOM	<b>Kalaburagi</b>	Bellary			209.7	Existing Transformer overload	1	50.0	158.7	
22	<b>Kamalapur (Hospet Tq.):</b> Providing additional 1 X10MVA, 110/11kV Power Transformer at kamalapur in Hospet Tq.	GESCOM	<b>Kalaburagi</b>	Bellary			268.9	Existing Transformer overload	10	50.0	208.9	
23	<b>Tekkalakote:</b> Providing 1x20 MVA, 110/33 kV Power transformer	GESCOM	<b>Kalaburagi</b>	Bellary			304.2	Existing Transformer overload	1	50.0	253.2	

Capital works planned for 5th MYT period								Budget required				
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
24	<b>Sankalapura:</b> Repl of 1X10MVA by 1X20MVA, 110/11KV Trf at 110/11KV S/S Sankalapura	GESCOM	Kalaburagi	Bellary			258.6	Existing Transformer overload	10	100.0	148.6	
25	<b>Kalaburagi University:</b> Replacement of 1X10MVA by 1X20MVA power Transformer at 110/11KV S/s Kalaburagi University	GESCOM	Kalaburagi	Kalaburagi			172.8	Existing Transformer overload	1	100.0	71.8	
26	Creating 33 KV reference by providing additional 1 x 20 MVA 110/33 kv Power Transformer along with construction of 33kv Terminal Bay at Existing 110/11kv Gurmitkal Sub-Station in Yadgir Tq. yadgir Dist.	GESCOM	Kalaburagi	Yadgir			326.1	Existing Transformer overload	1	100.0	225.1	
27	Enhancement of 1x10MVA, 110/11kv Power Transformer No. 1 by 1x20 MVA 110/11kv Power Transformer at 110/11kv Shorapur.	GESCOM	Kalaburagi	Yadgir			294.3	Existing Transformer overload	5	100.0	189.3	
28	Enhancement of 1x10MVA,110/33kv power transformer No.III by 1X20MVA 110/33kv Power Transformer at <b>110/11kv Shahapur S/S</b>	GESCOM	Kalaburagi	Yadgir			207.6	Existing Transformer overload	5	10.0	70.0	100.0
29	<b>Manvi:</b> Replacement of 1x10MVA by 1x20MVA 110/11KV Power Transformer at 110KV S/S Manvi and providing 3 Nos of 1x100Sqmm XLPE cable to 11kv bank II at 110/11kv manvi station	GESCOM	Kalaburagi	Raichur			213.5	Existing Transformer overload	1	100.0	112.5	
30	<b>Raichur:</b> Enhancement of 1x10MVA, 110/11KV Power Transformer by 20MVA ,110/11kv power transformer & providing 3 no's of 1x1000sq.mm XLPE CABLES TO 11Kv Bank III at 220KV S/S Raichur.	GESCOM	Kalaburagi	Raichur			227.8	Existing Transformer overload	1	100.0	126.8	
31	Providing additional 1x10MVA, 110/33kv Power Transformer at <b>110/11kv Mandewal Sub Station.</b>	GESCOM	Kalaburagi	Kalaburagi			287.7	Existing Transformer overload	1	100.0	186.7	
32	Providing additional 1 X 10MVA, 110kv Power Transformer at 110/33/11kv <b>MUSS, Chowdapur.</b>	GESCOM	Kalaburagi	Kalaburagi			298.1	Existing Transformer overload	1	100.0	197.1	
33	<b>Javagal:</b> Replacement of 1 X 10 MVA, 110/11 KV power Transformer by 1 X 20 MVA 110/11KV power transformer at 110/11KV Javagal S/S in Arasikere Taluk	CESC	Hassana	Hassana			204.2	Existing Transformer overload	1	50.0	153.2	

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
34	<b>Nittur:</b> Replacement of 1x10MVA, 110/11KV Power Transformer by 1x20MVA, 110/11KV Power Transformer at 110/11kV Nittur S/s .	MESCOM	Hassana	Udupi			355.2	Existing Transformer overload	1	50.0	304.2	
35	<b>Kundapura:</b> Providing additional 1X20MVA, 110/11KV Power Transformer at existing 110/33/11kV Kundapura substation in Kundapura Taluk.	MESCOM	Hassana	Udupi			329.5	Existing Transformer overload	1	50.0	278.5	
36	<b>Manipal:</b> Providing additional 1X20 MVA, 110/11KV Power Transformer at 110/33/11KV Manipal Sub-station in Udupi Taluk and District.	MESCOM	Hassana	Udupi			440.7	Existing Transformer overload	1	50.0	389.7	
37	<b>Karaya:</b> Creating 33KV reference by installing 1x20MVA, 110/33KV Power Transformer at 110/11kV Karaya S/s in Belthangudi Taluk	MESCOM	Hassana	Dakshina Kannada			323.4	Existing Transformer overload	1	50.0	272.4	
38	<b>Singtagere:</b> Providing additional 1x10MVA, 110/11KV Power Transformer at 110/11kV Singtagere S/s Kadur Taluk	MESCOM	Hassana	Chikkamagaluru			289.4	Existing Transformer overload	1	50.0	238.4	
39	<b>Tangli:</b> Enhancement of 1 x 10MVA 110/11KV Power transformer 2 by 1 x 20 MVA, 110/11KV power transpower at 110/11kV Tangli S/s in Kadur Taluk.	MESCOM	Hassana	Chikkamagaluru			319.4	Existing Transformer overload	1	50.0	268.4	
40	110 KV S/S Alamel: Replacement of 1X10 MVA, 110/11 KV by 1X20 MVA, 110/11 KV transformer	HESCOM	Bagalkote	Vijayapura			202.0	Existing Transformer overload		40.4	101.0	60.6
41	110 kV S/S Aremallapura : Providing additional 1x10 MVA, 110/11 kV transformer at 110 kV Aremallapura sub-station, in Ranebennur Taluk, Haveri District	HESCOM	Bagalkote	Haveri			350.0	Existing Transformer overload		70.0	175.0	105.0
42	Providing spare 1X20MVA, 110/33-11KV Trfr at 110KV Sambapur Road Sub station in Gadag Taluk, Gadag District instead of providing at 110KV Mundaragi Sub station.	HESCOM	Bagalkote	Gadag			291.0	Existing Transformer overload		58.2	145.5	87.3
43	Replacement of 1x10 MVA, 110/11 kV transformer by 1x20 MVA, 110/11 kV transformer at 110 kV Tikota sub-station, in Vijayapura Taluk, Vijayapura District.	HESCOM	Bagalkote	Vijayapura			315.0	Existing Transformer overload		63.0	157.5	94.5
44	Creating 33kV reference by providing 1x20 MVA, 110/33 kV transformer along with 33kV bank & feeders bay at 110 kV Uchagaon sub-station in Belgavi Taluk & District.	HESCOM	Bagalkote	Belgaum			446.0	Existing Transformer overload		89.2	223.0	133.8
45	Creating 33kV reference by providing 1x20MVA, 110/33 kV Power Transformer at 110kV Taushi (Balligeri) sub station in Athani Taluk.	HESCOM	Bagalkote	Belgaum			340.0	Existing Transformer overload		68.0	170.0	102.0
46	Providing additional 1 x 20 MVA, 110/11kV Transformer at 110/33/11kV Kulashekar station in Mangaluru Taluk, D.K. District.	MESCOM	Hassana	Dakshina Kannada			251.9	Existing Transformer overload		50.4	125.9	75.6

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kv												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
47	Replacement of 1 x 10MVA, 110/11kV Power Transformer by 1 x 20MVA, 110/11kV Power Transformer at 110/11kV Muthinakoppa sub-station, Narasimharajapura (N.R. Pura) Taluk and Shivamogga District	MESCOM	Hassana	Shimoga			266.3	Existing Transformer overload		159.8	106.5	
48	Kammaradi: Providing additional 1X10MVA Power Transformer at 110/11kV sub-station.	MESCOM	Hassana	Shimoga			269.2	Existing Transformer overload		161.5	107.7	
49	Thirthahalli: Enhancement of 1X10MVA Power Transformer -2 by 20MVA capacity power transformer at 110/33/11kV substation	MESCOM	Hassana	Shimoga			289.6	Existing Transformer overload		173.8	115.9	
50	Yagati: Enhancement of 1 x 10MVA, 110/11kV power transformer No.1 by 1 x 20MVA, 110/11kV sub-station Yagati, Kadur Taluk, Chikkamagaluru Dist.	MESCOM	Hassana	Chikkamagaluru			301.2	Existing Transformer overload		60.2	150.6	90.3
51	Honnnavalli: Replacing 1x10 MVA,110/11kV by 1x 20 MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			200.0	Existing Transformer overload		40.0	120.0	40.0
52	Chikkanayakanahalli: Replacing 1x10 MVA, 110/11kV by 1x 20 MVA, 110/11kV Transformer	BESCOM	Tumakuru	Tumakuru			200.0	Existing Transformer overload		40.0	120.0	40.0
53	Enhancement of existing 1x10 MVA 110/33kV Power Transformer-1 by 1 x20 MVA,110/33kV power transformer at 110/33/11kV Sagar Sub-station in Sagar Taluk, Shivamogga District.	MESCOM	Hassana	Shivamogga			200.0	Existing Transformer overload		10.0	90.0	100.0
54	Katkol: Augmentation of 10 MVA ,110/11 KV by 20 MVA, 110/11 KV Power Transformer at 110 KV S/S Katkol	HESCOM	Bagalkote	Belagavi			235.0	Existing Transformer overload		47.0	141.0	47.0
55	110 kV S/S Tumminakatti : Creating 33 kV reference by installing 1x20 MVA, 110/33 kV transformer at 110 kV Tumminakatti sub-station, in Ranebennur Taluk, Heveri District	HESCOM	Bagalkote	Haveri			285.0	Existing Transformer overload		57.0	171.0	57.0
56	Yalparahatti: Providing additional 1x10MVA, 110/11KV Power Transformer	HESCOM	Bagalkote	Belgaum			185.0	Existing Transformer overload		37.0	111.0	37.0
57	Hirehal:Replacement of 1X10MVA,110/33kV Trf by 1X20MVA,110/33kV Trf at Hirehal S/S and RON:Replacement of 1X20MVA,110/33kV Trf by 1X10MVA,110/33kV Trf at Ron S/S.	HESCOM	Bagalkote	Gadag			450.0	Existing Transformer overload		90.0	270.0	90.0
58	Mundargi:Replacement of 1X10MVA,110/11kV Trf by 1X20MVA,110/11kV Trf at Mundargi S/S.	HESCOM	Bagalkote	Gadag			235.0	Existing Transformer overload		47.0	141.0	47.0
59	Providing Addl 1X10MVA, 110/11KV Trfr at 110KV Hosa Honnatti Sub station in Ranebennur Taluk, Haveri District.	HESCOM	Bagalkote	Haveri			185.0	Existing Transformer overload		37.0	111.0	37.0
60	Replacement of 1X10MVA, 110/33KV Trfr by 1X20MVA, 110/33KV Trfr at 110KV Dambal Sub station in Mundaragi Taluk, Gadag District.	HESCOM	Bagalkote	Gadag			235.0	Existing Transformer overload		47.0	141.0	47.0

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
61	Replacement of 1X10MVA, 110/11KV Trfr by 1X20MVA, 110/11KV Trfr at 110KV Tiluvalli Sub station in Hanagal Taluk, Haveri District.	HESCOM	Bagalkote	Haveri			185.0	Existing Transformer overload		37.0	111.0	37.0
62	110 KV S/S Yalapharatti Creating 33 KV reference by installing 1X20 MVA ,110/33 KV Transformer at 110 KV Yalapharatti Sub station in Raibag Taluka, Belagavi Dist	HESCOM	Bagalkote	Belagavi			235.0	Existing Transformer overload		47.0	141.0	47.0
63	110 KV S/S Sadalaga Providing spare 1X10 MVA,110/33-11 KV Transformer at 110 KV Sadalaga Sub -Station in Chikkodi Taluka, Belagavi Dist	HESCOM	Bagalkote	Belagavi			185.0	System improvement		37.0	111.0	37.0
64	110 KV Udyambagh Creating 33 KV Reference by providing additional 1X20 MVA 110/33 KV Transformer at 110 KV Udyambagh Sub Station in Belagavi Taluka, Belagavi Dist	HESCOM	Bagalkote	Belagavi			235.0	Existing Transformer overload		47.0	141.0	47.0
65	Jambagi K.D.: Providing additional 1x10 MVA, 110/11 KV Transformer at 110 KV Jambagi K.D. S/S in Mudhol Tq. Bagalkot Dist.	HESCOM	Bagalkote	Bagalkote			182.0	Existing Transformer overload		36.4	109.2	36.4
66	Raichur: Providing spare 10 MVA, 110/11 kV Power Transformer at 220 kV R/S Raichur	GESCOM	Kalaburagi	Raichur			150.0	System improvement		30.0	90.0	30.0
67	Mukkunda: Replacement of 1x10MVA by 1x20MVA 110/11KV Power Transformer at 110KV S/S Mukkunda	GESCOM	Kalaburagi	Raichur			200.0	Existing Transformer overload		40.0	120.0	40.0
68	Turvihal: Replacement of 1x10MVA by 1x20MVA 110/11KV Power Transformer at 110KV S/S Turvihal.	GESCOM	Kalaburagi	Raichur			200.0	Existing Transformer overload		40.0	120.0	40.0
69	Enhancement of 1x10MVA, 110/11kV Power Transformer No-1 by 1x20 MVA, 110/11kV Power Transformer at 110/11kV S/S Chidri	GESCOM	Kalaburgi	Bidar			200.0	Existing Transformer overload		40.0	120.0	40.0

**Other works-110 kV**

1	Kulashekar: 1) Re-arranging of existing 110kV lines at 110/33/11kV Kulashekara S/S in view of R&M works of S/S. 2) R&M of 110/33/11kV Kulashekara S/S and providing additional 1X20MVA, 110/33kV Tr at 110/33/11kV Kulashekara S/S	MESCOM	Hassana	Dakshina Kannada			716.0	System improvement	1.0	501.2	213.7	
2	Baikampady: Providing 110KV, 20MVAR Capacitor Bank along with associated TB at existing 110/33/11KV Baikampady S/s.	MESCOM	Hassana	Dakshina Kannada			85.3	System improvement	1.0	59.7	24.6	

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
3	Formation of 110KV rigid bus at 220KV RS, Kemar	MESCOM	Hassana	Udupi			50.0	System improvement	1.0	35.0	14.0	
4	Gangavathi: LILoing of 110KV Munirabad-Sindhur line - II and construction of 2 Nos. TBs at 110KV Gangavathi Sub-Station	GESCOM	Kalaburagi	Bellary			162.7	System improvement	1.0	50.0	111.7	
Sub-station Works- 66 kV												
1	Huskuru : Establishing 2x12.5MVA, 66/11kV Sub-Station with Cable from existing 66/11 KV Malgudi(Electronic City sector -II, Phase -II) Substation for a Route length of 6.885Kms.	BESCOM	Bengaluru	Bengaluru Urban			5038.2	System improvement	5	3526.7	1506.5	
2	S.Medehalli: Establishing 2x12.5 MVA, 66/11kV sub-station at S.Medehalli, in Anekal Taluk, Bengaluru Urban District.	BESCOM	Bengaluru	Bengaluru Urban			1978	System improvement	1	989	691.6	296.4
3	Muthanalur: Establishing 2x8 MVA, 66/11kV Sub-Station with associated line at anekal taluk.	BESCOM	Bengaluru	Bengaluru Urban			1080	System improvement	1	540	377.3	161.7
4	Bagganadoddi: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	Bengaluru Urban			2913	System improvement	150	1000	1000	763
5	Madappanahalli: Establishing 2x20MVA, 66/11kV Sub-Station with associated line for a distance of 3.604Kms	BESCOM	Bengaluru	Bengaluru Urban			1119.73	System improvement	2	559.9	390.5	167.4
6	Tadigol Cross : Establishing 2x8MVA, 66/11kV Sub-Station with associated line.	BESCOM	Bengaluru	C.B.Pura			1060.45	System improvement	5	424.2	500.0	131.3
7	Nandi (Muddenahalli): Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 3.466 Km.	BESCOM	Bengaluru	C.B.Pura			425.71	System improvement	10	100.0	151.6	65.0
8	Bommepalli cross: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	C.B.Pura			661.64	System improvement	5	330.8	228.1	97.7
9	Changawara: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Tumakuru	Tumakuru			612.5	System improvement	50	245.0	317.5	
10	Kundur Mata: Establishing 1 X 8 MVA ,66/11 KV S/S at Kunduru Mata in CR Patna Taluk Hassana Dist with construction of 66kv Tap line on DC towers from Bagur- Ramapura line to proposed 66/11kV S/S at Kundurmata for a dist of 6.2Kms	CESC	Hassana	Hassana			491.91	System improvement	1	344.3	146.6	



**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
11	<b>Nagarthi:</b> Establishing 1x6.3 MVA, 66/11KV S/S at Nagarthi in H.N.Pura Tq, Hassan Dist with construction of 66kV SC line of DC towers for a route length of 10.03Kms to tap the existing 66kV C.R.Patna-H.N.Pura-Singapura SC line to the proposed 66/11kV Nagarthi S/S.	CESC	Hassana	Hassana			680.67	System improvement	1	476.5	203.2	
12	<b>Kampalapura:</b> Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 1.837Kms	CESC	Mysuru	Mysuru			562.89	System improvement	1	450.3	111.6	
13	<b>Kaggere (Hampapura)</b> Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 1.0Kms	CESC	Mysuru	Mysuru			528.36	System improvement	1	422.7	104.7	
14	<b>Chamalapura (B.Seehalli):</b> Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 3.835Kms	CESC	Mysuru	Mysuru			618.08	System improvement	10	494.5	113.6	
15	<b>Mandakalli (Koppalur):</b> Establishing 1x12.5MVA, 66/11kV Sub-Station with associated line	CESC	Mysuru	Mysuru			834.16	System improvement	100	667.3	66.8	
16	<b>Arkalavadi:</b> Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 10.368Kms	CESC	Mysuru	Chamarajanagara			736.13	System improvement	1	100.0	500.0	135.1
17	<b>Lokkanahalli :</b> Establishing 1 x 8 MVA,66/11 KV sub-station.	CESC	Mysuru	Chamarajanagara			900	System improvement	1	10.0	50.0	700.0
18	<b>Mallapanahalli:</b> Establishing 2x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Tumakuru	Chitradurga			900.93	System improvement	1	500.0	399.9	
19	<b>Godabanalu :</b> Establishing 2x12.5MVA, 66/11kV Sub-Station with associated line in Chitradurga Taluk & Dist.	BESCOM	Tumakuru	Chitradurga			1053.64	System improvement	1	500.0	552.6	
20	<b>Neralagunte:</b> Establishing 1x12.5MVA, 66/11kV substation with associated line in Challakere Taluk ,Chitradurga dist	BESCOM	Tumakuru	Chitradurga			745.54	System improvement	1	500.0	244.5	
21	<b>Ajjipura:</b> Establishing 1x8MVA, 66/11kV Sub-Station with associated line.	CESC	Mysuru	Chamarajanagara			645.2	System improvement		300.0	345.2	
22	Establishing 1x12.5 MVA, 66/11 kV sub-station at Vijapura in Chitradurga Taluk & District.	BESCOM	Tumakuru	Chitradurga			550.46	System improvement		100.0	450.5	
23	<b>Yerahally Hand post :</b> Upgradation of 33/11KV SS to 66/11KV SS.	CESC	Mysuru	Mysuru			935.09	System improvement		100.0	467.5	367.5

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
24	Talagawadi / Dugganahalli limits : Establishing 1x12.5MVA, 66/11kV Sub-Station with associated line.	CESC	Mysuru	Mandya			862.99	System improvement		100.0	431.5	331.5
25	Gownpalli : Establishing 2x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	Kolar			1141.89	System improvement		100.0	570.9	470.9
26	Manihambal: Establishing 1X8 MVA, 66/11 kV s/s with with construction of 66kV SC line on DC towers from existing 66kV Maralawadi S/s for a distance of 7kms.	BESCOM	Bengaluru	Ramanagara			450	System improvement		180.0	225.0	45.0
27	Anathanagara: Establishing 2x31.5MVA, 66/11kV Sub-Station with associated line at anekal taluk.	BESCOM	Bengaluru	Bengaluru			1500	System improvement		10.0	500.0	990.0
28	Thorlakki: Establishing 2x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	Kolar			500	System improvement		100.0	250.0	150.0
29	JN Kote : Establishing 2x8MVA, 66/11kV Sub-Station with associated line in Chitradurga Tq & Chitradurga Dist.	BESCOM	Tumakuru	Chitradurga			750	System improvement		150.0	375.0	75.0
30	Arasikere: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Tumakuru	Davanagere			550	System improvement		110.0	275.0	55.0
31	Establishing 1x8 MVA, 66/11 kV Sub-station at Harakanalu (Hulikatte Cross) in Harapanahalli Taluk, Davanagere District by constructing 66kV LILo line on DC towers from 66kV Neelagunda-Harapanahalli line for a distance of 7kms using coyote conductor	BESCOM	Tumakuru	Davanagere			550	System improvement		110.0	275.0	55.0
32	Pandithanahalli: Establishing 1 x 8 MVA, 66/11 KV Sub-Station with associated line	CESC	Mysuru	Mandya			550	System improvement		110.0	275.0	55.0
33	Thalabetta: Establishing 1x8MVA 66/11kV Sub-Station with associated line	CESC	Mysuru	Chamarajana- nagar			550	System improvement		110.0	275.0	55.0
34	Sunkathonnur: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	CESC	Mysuru	Mandya			550	System improvement		110.0	275.0	55.0
35	Padukote/Chikkereyur : Establishing 1 x 8 MVA,66/11 KV sub-station.	CESC	Mysuru	Mysuru			550	System improvement		110.0	275.0	55.0
36	Shindenahally : Establishing 1 x 8 MVA,66/11 KV sub-station.	CESC	Mysuru	Mysuru			550	System improvement		110.0	275.0	55.0
37	Kudige: Establishing 2x 8 MVA,66/11 KV sub-station.	CESC	Mysuru	Kodagu			700	System improvement		140.0	350.0	70.0

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
38	Hanagallu Shettalli(Hanagallu bani) : Establishing 1 x 8 MVA,66/11 KV sub-station.	CESC	Mysuru	Kodagu			550	System improvement		110.0	275.0	55.0
39	Chifakana Hatti: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Bellary			550	System improvement		110.0	275.0	110.0
40	G.Kodihalli: Establishing 1X8 MVA 66/11 KV S/S at G.Kodihalli.	GESCOM	Kalaburagi	Bellary			534	System improvement		106.8	267.0	106.8

**Transmission line Works- 66 kV**

1	Antharsanahally - Chelur tap point - Sira: Construction of (a) 66kV MC line from Antharsana hally to Chelur tap point b) 66kV MC line from Chelur tap point to Sira (partly on DC) c) Providing 66kV TBs at 66kV Sira & Antharsana hally for above lines for a distance of 52.00 Kms.	BESCOM	Tumakuru	Tumakuru			3504.08	To relieve line overload	1	53.634	22.986	
2	Nagalamadike : Construction of new 66kV SC tap line on DC towers from Pavagada tapping point to Nagalamadike S/ S (Replacement of Rabbit conductor on RCC poles) for a distance of 13.46Kms.	BESCOM	Tumakuru	Tumakuru			197.11	To relieve line overload	1	108.367	46.443	
3	Shylapura - Y. N. Hosakote: Construction of new 66kV SC line on DC towers (Replacement of Rabbit conductor on RCC poles by Coyote conductor on 17.24 Kms.	BESCOM	Tumakuru	Tumakuru			265	To relieve line overload	1	134.666	57.714	
4	Pandarahalli - Holalkere: Construction of 66kV DC line in the existing corridor of 66kV S/C line with TBs for a distance of 25.34 Kms.	BESCOM	Tumakuru	Chitradurga			646	To relieve line overload	10	133.763	57.327	
5	MRS to Lingadahalli: Construction of new 66kV SC line on DC towers for a distance of 46.039Kms in the existing corridor of 66kV DVG-2 SC line From MRS Shivamogga to Lingadahalli (Channagiri Taluk) in Shivamogga & Davanagere Districts.	MESCOM	Hassana	Shimoga			864.2	To relieve line overload	500	300	64.2	
6	Virajpet - Madakeri: Construction of 66kV SC Link line on DC towers between 66kV Virajpet & Madakeri Sub-Stations for a distance of 36.16kms.	CESC	Mysuru	Kodagu			842.37	To relieve line overload	50	100	300.923	128.967
7	Munirabad - Ujjini: Dismantling of existing 66kV Munirabad-Sokke-Davangere line emanating from Munirabad Generating Station & Erecting a new 66kV line with Coyote conductor upto 66kV Ujjani Sub-Station in Kudligi Taluk for a distance of 204.31 Kms	GESCOM	Kalaburagi	Bellary			773.98	System improvement	10	226.884	97.236	
8	HAL-Amarjyothi: Strengthening of existing 66kV line by replacing Coyote by HTLS Conductor for a distance of 3.21 kms	BESCOM	Bengaluru	Bengaluru Urban			481.6	To relieve line overload	1	337.1	100.0	43.5

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
9	<b>Amarjyothi-Audugodi:</b> Replacement of Existing Coyote ACSR Conductor by HTLS Conductor for a route length of 4.20Kms in the existing 66kV DC Audugodi-Amarjyothi line.	BESCOM	Bengaluru	Bengaluru Urban			665.2	To relieve line overload	1	465.7	100.0	98.6
10	<b>Nelagadarenhalli to WIDIA:</b> Running of 66kV 1000sqmm SC UG cable from existing 66/11kV Nelagadarenhalli S/s to existing Widia S/s for a route length of 3.540Kms	BESCOM	Bengaluru	Bengaluru Urban			2359.0	To relieve line overload	1	1651.3	500.0	206.7
11	<b>Kanteerava GIS Station:</b> Establishing link line between 220/66/11kV Sir.M.V.GIS station(East Division Compound) and 66kV Kanteerava GIS station by laying kV SC 1000Sqmm UG cable for a route length of 2.488Kms	BESCOM	Bengaluru	Bengaluru Urban			1782.0	To relieve line overload	10	1247.4	524.6	
12	<b>66KV D.B.Pura -Devanahalli line:</b> Strengthening the 66KV D.B.Pura -Devanahalli line by Drake conductor 20KMS	BESCOM	Bengaluru	Bengaluru rural			950.0	To relieve line overload	10	665.0	275.0	
13	<b>D cross to Thodebhavi:</b> Strengthening of 66kV line from D cross to Thodebhavi limites (Existing fabricated small tower and rabbit conductor)	BESCOM	Bengaluru	Bengaluru Rural & CBPura			1177.0	To relieve line overload	10	823.9	343.1	
14	<b>66kV Mattikere- Jalamangala Line:</b> Construction of 66kV Line from 66/11kV Mattikere to Jalamangala for a distance of 10.78Kms	BESCOM	Bengaluru	Ramanagara			564.1	To relieve line overload	5	225.6	169.2	112.8
15	<b>66kV DC line to 66/11kV Maralavadi S/s:</b> Replacing of existing 66KV SC Tower of 66 KV Maralwadi line by constructing DC tower, drake DC line from tapping point of existing 66KV Kanakapura-Chatra(Tapping -Maralwadi tapping )- Hanumanthanagara-Yedamadu-Somanahalli line-1	BESCOM	Bengaluru	Ramanagara			656.0	To relieve line overload	5	262.4	196.8	131.2
16	Conversion of existing 66kV SC line to <b>DC line from Harobele station to Kodihalli station</b>	BESCOM	Bengaluru	Ramanagara			142.0	To relieve line overload	5	56.8	42.6	28.4
17	<b>66kV SC line from 220kV Kanakapura to Kunur station:</b> Construction of 66kV SC line partially cable and partially overhead line from Kanakapura to proposed Kunur station for a distance of 7.481Km	BESCOM	Bengaluru	Ramanagara			3149.0	To relieve line overload	5	1259.6	944.7	629.8
18	Construction of 66kV MC/DC line in the existing corridor of 66kV <b>Somanahalli - Kanakapura - T.K.Halli</b> DC line B1 & B2 having old H frame towers and cat conductor	BESCOM	Bengaluru	Ramanagara			4157.0	To relieve line overload	5	1662.8	1247.1	831.4
19	<b>Siddlaghatta - Y.Hunaseshalli:</b> Running of 2nd Circuit on existing DC Tower of Siddlaghatta 66kV line upto Tower No.51 and linking the same to Y.Hunaseshalli line with TB at 220kV R/S Chintamani for a distance of 12.3 kms.	BESCOM	Bengaluru	C.B.Pura			529.9	To relieve line overload	1	371.0	158.0	

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
20	<b>Jangankote Sub-Station:</b> Providing 66kV LILO arrangement to 66/11kV Sub-Station for a distance of 7.00 kms.	BESCOM	Bengaluru	C.B.Pura			55.0	System improvement	1	38.5	15.5	
21	<b>Chilur Station to Chilur Tap point:</b> Conversion of SC line on SC towers to DC line on DC towers from Tap point to Chilur 66kV Sub-Station for a distance of 1 Km with TB at Chilur station for LILO arrangement.	BESCOM	Tumakuru	Davanagere			54.1	To relieve line overload	10	27.1	17.1	
22	<b>Jagalur-Sokke 66KV line:</b> Reconstruction of existing 66kV, age old coyote conductor SC line from 66kV Sub-Station Jagalur to 66kV Sub-Station Sokke as SC line on DC towers with coyote conductor for a distance of 20.961 Kms.	BESCOM	Tumakuru	Davanagere			401.1	System improvement	10	200.6	190.6	
23	<b>Sasvehalli Station to Sasvehalli Tap point:</b> Providing LILO arrangement at 66kv station Sasvehalli from tap point of Lingadahalli-Channagiri line for a distance of 0.5 kms with TB.	BESCOM	Tumakuru	Davanagere			53.3	To relieve line overload	10	26.7	16.7	
24	<b>Gendehally - Arehally:</b> Construction of 66kV DC line from 66kV Arehally Sub-station to LILO the existing 66kV SC line between Belur-Gendehally Sub-station along with two Nos of 66kV TB's at 66kV Arehally Sub-station	CESC	Hassana	Hassana			612.1	System improvement	1	428.5	100.0	82.6
25	<b>S K Pura to Arehall:</b> Stringing of 2nd Circuit with Coyote ACSR Conductor on existing 66KV SC line onDC towers between 66/11KV S/s at Sakaleshpura and 66/11 KV S/s at Arehally with TB at both Sakaleshpura and Arehally S/s.	CESC	Hassana	Hassana			245.8	To relieve line overload	5	172.1	68.8	
26	Reconstruction of 66kV SC line in existing corridor of 66kV SC MBT(FTS Mysuru-Bhadra) line on DC towers from Hassan to H.N.Pura and reconstruction of 66kV SC line in the existing 110kV SC SMT(Shimoga-Mysuru) line corridor on DC towers from HN Pura to Hootagalli	CESC	Hassana	Hassana			2108.4	System improvement	1	500.0	1000.0	607.4
27	<b>Hootagalli - Bherya Limits:</b> Replacing of H - Frames by Re-construction of 66kV SC line between Hootagalli - Bherya Limits to a distance of 54 km	CESC	Mysuru	Mysuru			1025.0	System improvement	1	300.0	500.0	224.0
28	<b>Hootagalli R/S, Vijayanagar and FTS Sub-Station:</b> Stringing of 66kV 2nd circuit between Hootagalli R/S, Vijayanagar and FTS Sub-Station on existing D/C towers with Terminal Bays at both ends	CESC	Mysuru	Mysuru			128.0	To relieve line overload	1	76.8	50.2	

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
29	<b>Bettadapura Sub-station:</b> Reconstruction of 66 kV SC line on SC towers by LILO line from existing 66 kV Chunchanahatti-Kushalnagar line to 66/11 kV Bettadapura S/S for a distance of 2.457 km in Periyapatna Taluk,Mysuru District for a distance of 2.46 kms	CESC	Mysuru	Mysuru			94.3	System improvement	1	56.6	36.7	
30	<b>Jayapura :</b> Providing additional 1 No. of 66 kV TB and LILO of Kadakola - Sargur 66kV line by constructing additional Circuit on existing towers for a distance of 6.0 kms along with Terminal Bay at Jaipura for a distance of 6 kms	CESC	Mysuru	Mysuru			58.0	System improvement	1	34.8	22.2	
31	<b>K R Nagar to Chunchanakatte:</b> Re-Construction of existing 66kV line between K R Nagar Sub-Station to Chunchanakatte Sub-Station for a distance of 5.8kms	CESC	Mysuru	Mysuru			156.0	System improvement	1	93.6	61.4	
32	<b>Kadakola-Devanur (Nanjangud) Drake Line:</b> Strenthening of 66kv s/c line on s/c towers from Kadakola 220kv R/S TO 66KV Devanur s/s ( Nanjanagud ) by Drake Conductor on 110/66KV DC Tower to a distance of 23Kms	CESC	Mysuru	Mysuru			2574.0	To relieve line overload	1	10	800	1000
33	<b>Shimsha - Mandya:</b> Construction of 66kV SC link line in the existing corridor for a distance of 44.57KMs.	CESC	Mysuru	Mandya			346.9	To relieve line overload	10	100.0	100.0	94.6
34	<b>Hampapura :</b> LILO of Kadakola -Santhesaguru 66kV line by constructing additional Circuit on existing towers for a distance of 6.5km along with Terminal Bay at Hampapura (HD Kote) for a distance of 6.5 kms	CESC	Mysuru	Mandya			60.6	System improvement	1	36.3	23.2	
35	<b>Kiragavalu LILO:</b> Converston of 66kV S/C Line on SC Tower to 66kV LILO line on DC Towers from the existing 66kV SFC-Vajamangala DC line.	CESC	Mysuru	Mandya			132.4	System improvement	75	39.7	17.7	
36	<b>Anegola LILO:</b> Construction of 2nd circuit on existing 66kV DC towers for a distance of 2.965 Kms for Making LILO arrangement to Anegola Sub-Station	CESC	Mysuru	Mandya			74.1	System improvement	1	44.5	28.6	
37	<b>Santhemaranahalli Sub-station:</b> Providing 66kV LILO arrangment to existing 66/11kV Santhemaranahally S/s along with 1 No TB	CESC	Mysuru	Chamarajanagara			154.8	System improvement	50	92.9	11.9	
38	<b>Ramapura LILO:</b> Construction of 66kV 2nd circuit line for a distance 1.5Kms. on existing D/C towers for making LILO arrangement to Ramapura Sub-Station along with Terminal Bay.	CESC	Mysuru	Chamarajanagara			56.3	System improvement	10	33.8	12.5	

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
39	66KV link line from proposed 66KV Hire Mallana Hole to 66KV Hosahalli	GESCOM	Kalaburagi	Bellary			278.0	To relieve line overload	1	166.8	110.2	
40	<b>Magadi-Byadarahalli:</b> Conversion of existing 66kv Byadarahalli-Magadi S/C line to DC line with Drake ACSR conductor using proposed 110kv Narrow based DC towers for a distance of 28.990Kms and 66kv 1000sqmm, UG cable from existing 66/11Kv Byadarahalli station to U.G. cable terminating tower for a route length of 0.098 Kms.	BESCOM	Bengaluru	Bengaluru Urban Ramanagara			2232.0	To relieve line overload	1	500	1731	
41	66KV D.B.Pura - Vijayapura line : Strengthening the 66KV D.B.Pura - Vijayapura line of coyote conductor by drake	BESCOM	Bengaluru	Bengaluru rural			1586.0	To relieve line overload		500	1086	
42	Providing LILO arrangement to 66/11kv Attichowdanahally Sub-station from 66kv Channarayapatna-Malali SC line in C.R. Patna Taluk in Hassan District	CESC	Hassana	C.R.PATNA			154.7	System improvement		92.8	61.9	
43	Providing LILO arrangement to 66 kv Harihara sub-station from 66 kv Harihara-Hospet line at Loc. 78-79 by stringing SC on DC tower.	BESCOM	Tumakuru	Tumakuru			43.5	System improvement		8.7	21.8	13.1
44	B) Providing alternate 66 kv source to 66 kv Vidyanagar sub-station by running 1000sqmm UG Cable from 220 kv Devanahalli Hardware Park sub-station for a distance of 9.1 km. c) 4 runs of 220 kv UG cable from 400 kv DWHP to link 220 kv Nelamangala-Hoody DC line.	BESCOM	Bengaluru	Bengaluru Rural			28210.0	To relieve line overload		3000	14105	11105
45	Work of providing 66kv alternate source to 66/11kv Brigade Metropolis by tapping existing 66kv HAL-1 or 2 line (Bagmane 1 or 2 feeding from 220/66kv Hoody) by laying 66kv, 1000sq mm single circuit XLPE insulated copper UG cable	BESCOM	Bengaluru	Bengaluru Urban			130.7	To relieve line overload		26.1	65.3	39.2
46	Releasing the overload on 66kv Gowribidanur- Peresandra S/C line by making LILO arrangement from 66/11kv S/s Somenahalli to Somenahalli tap point.	BESCOM	Bengaluru	CB Pura			156.5	To relieve line overload		31.3	78.2	46.9
47	220/66/11kv NRS Doddaballapura to CBPura 1 & 2 DC lines: Replacement of coyote ACSR by Drake ACSR conductor	BESCOM	Bengaluru	Bengaluru Rural			1156.7	To relieve line overload		100	578.4	478.4
48	Jigani-RBI - Strengthening 66kv Jigani-2A & 2B circuit lines from Coyote to Drake in the existing corridor from RBI tapping point(Kotthur dinne) to Jigani.	BESCOM	Bengaluru	Bengaluru Rural			1010.2	To relieve line overload		100	505.1	405.1
49	Sarjapura station to 66 kv Lakkur : Construction of 66 kv DC line from 220 kv Sarjapura station to 66 kv Lakkur sub-station	BESCOM	Bengaluru	Bengaluru Urban			698.0	To relieve line overload		139.6	349	209.4
50	Providing 66KV, 1000sqmm cable from existing Jigani1/2 line to 66/11kv Anjanapura S/s for a distance of 3.5 Kms.	BESCOM	Bengaluru	Bengaluru Urban			1516.0	To relieve line overload		200	758	558
<b>Sub-station augmentation-66 kV</b>												

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
1	Hoody: Providing 3rd additional 1x31.5 MVA, 66/11 kV transformer.	BESCOM	Bengaluru	Bengaluru Urban			555.0	Existing Transformer overload	10	388.5	156.5	
2	Kolala: Replacing 1x8 MVA,66/11kV by 1x 12.5 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			136.5	Existing Transformer overload	5	95.6	36.0	
3	Thovinakere: Replacement of 1x12.5MVA, 66/11kV by 1x 20MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			177.1	Existing Transformer overload	1	123.9	52.1	
4	Ankasandra: Providing Additional 1x8MVA, 66/11kV Power Transformer at 66/11kV Station.	BESCOM	Tumakuru	Tumakuru			112.4	Existing Transformer overload	100	6.4	6.0	
5	Kolala: Replacing 2nd 1x8 MVA, 66/11kV by 1x 12.5 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			139.1	Existing Transformer overload	50	69.5	19.5	
6	Bellavi: Replacing 1x12.5MVA Power Trnsformer-1 by 1x20MVA Power Transformer at 66/11kV Bellavi Substation	BESCOM	Tumakuru	Tumakuru			203.5	Existing Transformer overload	50	142.4	11.0	
7	Heggere: Providing additional 1x8MVA Power Transformer at 66/11kV Substation	BESCOM	Tumakuru	Tumakuru			273.1	Existing Transformer overload	100	136.6	36.6	
8	Tavarekere: Replacing 1x8MVA, 66/11kV Power transformer-1 by 1x12.5MVA 66/11kV Power transformer	BESCOM	Tumakuru	Tumakuru			142.3	Existing Transformer overload	50	71.1	21.1	
9	Koratagere: Replacement of 1x 12.5MVA 66/11kV Power Transformer by 1x 20 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			206.3	Existing Transformer overload	100	103.2	3.2	
10	Thimmasandra: Replacing1x8MVA, 66/11kV by 1x 12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			136.4	Existing Transformer overload	50	68.2	18.2	
11	Hebbur: Replacing 1x12.5 MVA, 66/11kV by 1x 20 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			212.0	Existing Transformer overload	120	63.6	28.4	
12	Sira: Replacing 12.5MVA,66/11kV by 1x 20 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			214.0	Existing Transformer overload	100	107.0	7.0	
13	Hirehalli: For replacement of 1 x 12.5 MVA Tr.-1 by 1 X20 MVA Tr. at 66/11 KV Sub-station with 1IC+4F+1BC	BESCOM	Tumakuru	Tumakuru			204.2	Existing Transformer overload	50	142.9	11.2	
14	Yadiyur: For replacement of 1 x 6.3 MVA by 1 X 20 MVA Tr. at 66/11 KV Sub-station	BESCOM	Tumakuru	Tumakuru			205.7	Existing Transformer overload	100	102.8	2.8	
15	Kunigal: For replacement of 1 x 12.5 MVA Tr-2 by 1 X 20 MVA Tr. 1Bank + 4Feeders at 66/11 KV Sub-station	BESCOM	Tumakuru	Tumakuru			204.5	Existing Transformer overload	100	102.3	2.3	
16	Honnudike: Replacing 1x8 MVA-1 66/11kV by 1x 12.5 MVA, 66/11kV Transformer (2nd Tr.)	BESCOM	Tumakuru	Tumakuru			145.0	Existing Transformer overload	50	72.5	22.5	



**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
17	Kattige: Providing additional 1x8MVA, 66/11kV Transformer	BESCOM	Tumakuru	Davanagere			173.5	Existing Transformer overload	30	86.7	33.9	
18	Kundur: Providing additional 1x8MVA, 66/11kV Transformer	BESCOM	Tumakuru	Davanagere			174.7	Existing Transformer overload	30	87.3	34.5	
19	Davanagere: Providing Spare 1x20MVA, 66/11kV Transformer at 220/66kV Davanagere SRS.	BESCOM	Tumakuru	Davanagere			253.2	System Improvement	1	177.3	75.0	
20	Bidarekere: Providing Additional 1x8MVA, 66/11kV Power Transformer.	BESCOM	Tumakuru	Davanagere			179.0	Existing Transformer overload	20	125.3	33.7	
21	Obbajjhalli: Providing Additional 1x8MVA, 66/11kV Power Transformer	BESCOM	Tumakuru	Davanagere			179.0	Existing Transformer overload	50	125.3	3.7	
22	Avaregare: Replacing 1x8MVA, 66/11kV by 1x 12.5MVA, 66/11kV Tranformer.	BESCOM	Tumakuru	Davanagere			136.5	Existing Transformer overload	100	27.3	9.2	
23	Mayakonda: Replacing 1x8MVA, 66/11kV by 1x 12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Davanagere			137.8	Existing Transformer overload	100	27.6	10.3	
24	Uchchagidurga: Replacing 2x8MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformer	BESCOM	Tumakuru	Tumakuru			271.9	Existing Transformer overload	135	27.2	19.2	
25	Harapanahalli: Replacing 1x12.5 MVA, 66/11kV by 1x 20 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Davanagere			201.5	Existing Transformer overload	100	80.6	20.9	
26	Bennihalli: Replacing 1x6.3 MVA, 66/11kV by 1x 12.5 MVA, 66/11kV Tranformer.	BESCOM	Tumakuru	Davanagere			140.1	Existing Transformer overload	100	28.0	12.1	
27	Halavagalu: Replacing 2x6.3M VA, 66/11kV by 2x 12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Davanagere			274.7	Existing Transformer overload	100	137.4	37.4	
28	Telagi: Replacing 2x6.3 MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Davanagere			272.8	Existing Transformer overload	120	136.4	16.4	
29	Sasuvehalli : Replacing of 1x6.3 MVA 1x8MVA by 2x12.5MVA 66/11kv Power Transformer	BESCOM	Tumakuru	Davanagere			273.9	Existing Transformer overload	200	54.8	19.1	
30	Bharamasagara: Providing Spare 1x12.5MVA, 66/11kV Transformer	BESCOM	Tumakuru	Chitradurga			198.5	System Improvement	5	139.0	54.6	
31	Kanchipura: Providing Additional 1x8 MVA, 66/11kV Power Transformer.	BESCOM	Tumakuru	Chitradurga			183.7	Existing Transformer overload	5	128.6	50.1	
32	Mylanahalli : Replacing 1x8 MVA, 66/11kV by 1x 12.5 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Chitradurga			142.4	Existing Transformer overload	50	71.2	21.2	
33	Thallak : Replacing 1x6.3 MVA, 66/11kV by 1x 12.5 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Chitradurga			139.8	Existing Transformer overload	50	69.9	19.9	
34	Hanagal: Replacing 1x8 MVA, 66/11kV by 1x12.5 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Chitradurga			156.7	Existing Transformer overload	50	78.4	28.4	

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
35	Bannur : Replacing 2nd 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV Transformer with additional SWG.	CESC	Mysuru	Mysuru			248.3	Existing Transformer overload	1	149.0	98.3	
36	Bhogadhi: Providing Spare 1x20 MVA 66/11kV Transformer	CESC	Mysuru	Mysuru			225.7	System Improvement	1	135.4	89.3	
37	Jayapura: Replacing 2nd 8MVA, 66/11kV by 12.5MVA, 66/11kV Transformer	CESC	Mysuru	Mysuru			134.2	Existing Transformer overload	1	80.5	52.7	
38	Hebbal : Replacement of 2 X 12.5 MVA, 66/11 KV Power Transformer by 2 X 20 MVA .	CESC	Mysuru	Mysuru			230.7	Existing Transformer overload	50	138.4	42.3	
39	Dattagalli: Replacing 1x5 MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	CESC	Mysuru	Mysuru			168.5	Existing Transformer overload	10	101.1	57.4	
40	Hadli : Providing additional 1x12.5MVA, 66/11kV Transformer	CESC	Mysuru	Mandya			248.7	Existing Transformer overload	1	149.2	98.5	
41	Addihalli: Replacing 1X6.3MVA & 1X8MVA, 66/11kV Trs. by 2x12.5MVA, 66/11kV Trs. at Addihalli along with stringing of 2nd ckt 66kV line b/w 220kV K.R.Pet-Santhebachally and linking by 66kV SC line to Addihally Sub-station with construction of 2Nos of 66kV TBs at Santhebachahalli, One TB at Addihalli Sub-station and One TB at 220kV K.R.Pet station.	CESC	Mysuru	Mandya			1216.7	Existing Transformer overload	300	500.0	416.7	
42	Guddenahalli : Replacement of 1 X 6.3 MVA by 1 X 12.5 MVA 66/11kV Transformer.	CESC	Mysuru	Mandya			158.9	Existing Transformer overload	1	95.3	62.5	
43	Akkihebbal : Replacement of 2 nd 8MVA by 12.5 MVA, 66/11kV Transformer.	CESC	Mysuru	Mandya			178.6	Existing Transformer overload	1	107.2	70.4	
44	Gamanahalli : Replacement of 1 X 8 MVA by 12.5 MVA, 66/11kV Transformer.	CESC	Mysuru	Mandya			167.0	Existing Transformer overload	1	100.2	65.8	
45	Mandagere : Providing additional 1 X 12.5 MVA, 66/11 KV Power Transformer.	CESC	Mysuru	Mandya			257.2	Existing Transformer overload	1	154.3	101.9	
46	Mandya KIADB: Replacing 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV Transformers with SWGs	CESC	Mysuru	Mandya			272.3	Existing Transformer overload	1	163.4	107.9	
47	Chinakurali : Replacement of 1 X 8 MVA, 66/11 KV Power Transformer by 1 X 12.5 MVA, 66/11 KV.	CESC	Mysuru	Mandya			156.2	Existing Transformer overload	1	93.7	61.5	
48	Kadaballi : Providing additional 1 X 12.5 MVA, 66/11 KV Power Transformer	CESC	Mysuru	Mandya			254.9	Existing Transformer overload	1	153.0	101.0	

## Capital works planned for 5th MYT period

## Sub-station works- 400 kV

## Budget required

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
49	Adichunchangiri: Additional 1X12.5MVA 66/11kV Power Transformer	CESC	Mysuru	Mandya			257.1	Existing Transformer overload	1	154.2	101.8	
50	Chandakavadi : Replacing 2X8 MVA,66/11 KV transformers by 2X12.5 MVA transformers .	CESC	Mysuru	Chamarajanagara			290.2	Existing Transformer overload	175	58.0	57.1	
51	Hanur : Replacement of 1 X 8 MVA by 1 X 12.5 MVA, 66/11kV Transformer.	CESC	Mysuru	Chamarajanagara			158.6	Existing Transformer overload	1	95.2	62.5	
52	Begur : Replacing the existing 2nd 8MVA Tr. By 12.5MVA Transformer.	CESC	Mysuru	Chamarajanagara			178.5	Existing Transformer overload	1	107.1	70.4	
53	Kunthur: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Chamarajanagara			235.3	Existing Transformer overload	10	141.2	84.1	
54	Bandalli: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Chamarajanagara			265.2	Existing Transformer overload	10	159.1	96.1	
55	Kogali: Providing additional 1x8MVA, 66/11kV Transformer	GESCOM	Kalaburagi	Bellary			178.2	Existing Transformer overload	1	50.0	127.2	
56	Sovenahalli: Providing additional 1x8MVA, 66/11kV Transformer	GESCOM	Kalaburagi	Bellary			178.5	Existing Transformer overload	1	50.0	127.5	
57	Banavikallu: Providing additional 1x8MVA, 66/11kV Transformer	GESCOM	Kalaburagi	Bellary			180.8	Existing Transformer overload	1	50.0	129.8	
58	HB Halli: Replacement of 1X 8MVA,66/11kV Transformer by 1X12.5MVA,66/11KV	GESCOM	Kalaburagi	Bellary			136.5	Existing Transformer overload	1	50.0	85.5	
59	Venkatapura: Repl of 1X8MVA by 1X12.5MVA, 66/11KV Trf at 66/11KV S/S Venkatapura	GESCOM	Kalaburagi	Bellary			155.5	Existing Transformer overload	10	93.3	52.2	
60	Hampasagara: Enhancement of 1X6.3MVA, 66/11KV Power Transformer by 1X12.5MVA, 66/11KV Power Transformer at 66/11KV Hampasagara Sub-station in H.B.Halli Taluk, Bellary District.	GESCOM	Kalaburagi	Bellary			151.8	Existing Transformer overload	1	50.0	100.8	
61	Ramnathapura: Augmentation of 1x6.3MVA 66/11kV power transformer by 1x12.5 MVA 66/11 KV Power Transformer at 66/11 KV Ramanathapura S/s in Arakalagud Taluk, Hassan District.	CESC	Hassana	Hassana			207.4	Existing Transformer overload	1	50.0	156.4	
62	Bagur: Replacement of 1 X 8 MVA, 66/11 KV Power Transformer by 1 X 12.5 MVA, 66/11 KV Power Transformer at 66/11 KV Bagur S/S in C. R. Patna Taluk	CESC	Hassana	Hassana			166.9	Existing Transformer overload	1	50.0	115.9	
63	Belur: Replacement of 1x6.3MVA, 66/11kV Power Transformer-2 by 1x12.5MVA, 66/11 KV Power Transformer at 66/11KV Belur S/s in Belur Taluk, Hassan District	CESC	Hassana	Hassana			152.7	Existing Transformer overload	1	50.0	101.7	

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
64	Rameshwaranagara: Replacement of 2x8MVA, 66/11kV Power Transformer by 2x12.5MVA, 66/11kV Power Transformer at 66/11 KV Rameshwaranagara S/s in Hassan Taluk, Hassan District	CESC	Hassana	Hassana			292.4	Existing Transformer overload	1	50.0	241.4	
65	Basavaghatta Replacement of 2x8MVA, 66/11kV Power Transformers by 2x12.5MVA 66/11kV Power Transformers at 66/11KV Basavaghatta S/s in Hassan Taluk, Hassan District	CESC	Hassana	Hassana			282.1	Existing Transformer overload	1	50.0	231.1	
66	Halebeedu: Replacement of 1x12.5MVA, 66/11kV Power Transformer by 1x20 MVA 66/11kV Power Transformer at 66/11KV Halebeedu S/s in Belur Taluk, Hassan District	CESC	Hassana	Hassana			229.1	Existing Transformer overload	1	50.0	178.1	
67	Singapura: Enhancement of 1x8MVA, 66/11kV Power Transformer-2 by 1x12.5MVA 66/11 kV power transformer at 66/11kV Singapura S/s in Holenarasipura Taluk, Hassan District	CESC	Hassana	Hassana			186.8	Existing Transformer overload	1	50.0	135.8	
68	Shanivarsanthe: Providing additional 1X8MVA, 66/11kV Power Transformer at 66/11kV at Shanivarsanthe Substatio Somavarpet Taluk.	CESC	Hassana	Hassana			234.9	Existing Transformer overload	1	50.0	183.9	
69	Panchanahalli : Replacement of 1x6.3 MVA, 66/11 kV Power Transformer-2 by 12.5MVA, 66/11 kV power transformer at 66/11kV Panchanahalli sub-station, in Kadur Taluk, Chikkamagalur District	MESCOM	Hassana	Chikkamagaluru			277.3	Existing Transformer overload	1	50.0	226.3	
70	Holaluru: Replacement of 1x 8 MVA, 66/11KV Power transformer by 1x 12.5,66/11kV power transformer at 66/11kV Holalur S/s in Shivamogga taluk .	MESCOM	Hassana	Shimoga			148.8	Existing Transformer overload	1	50.0	97.8	
71	Hosur Gate : Providing additional 1x8MVA, 66/11 KV Power Transformer at Hosur Gate S/s at Hunsur Taluk & Mysuru Dist.	CESC	Mysuru	Mysuru			230.8	Existing Transformer overload	1	50.0	179.8	
72	Gavadagere: Providing additional 1x8MVA, 66/11kV Power Transformer at Gavdagere substation Hunsur Taluk Mysuru District.	CESC	Mysuru	Mysuru			230.3	Existing Transformer overload	1	50.0	179.3	
73	Replacement of 1 x 6.3 MVA, 66/11kV Power Transformer by 1 x 12.5 MVA, 66/11kV Power transformer at 66/11kV Magge Sub-station in Alur Taluk, Hassan District.	CESC	Hassana	Hassana			145.8	Existing Transformer overload		87.5	58.3	
74	Providing additional 1x8MVA, 66/11kV Power Transformer with additional 11 kV switchgears 11/C+3F+1C @ 66/11kV Bandishettyhally Sub-station, Holenarasipura Taluk, Hassan District	CESC	Hassana	Hassana			217.0	Existing Transformer overload		130.2	86.8	

**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
75	Mattanavile: Augmentation of 1x8MVA, 66/11kV Power Transformer by 1x12.5MVA@Mattanavile S/s in Channarayapattana Taluk, Hassan District	CESC	Hassana	Hassana			162.5	Existing Transformer overload		97.5	65.0	
76	Providing additional 1x8 MVA, 66/11 kV transformer at 66 kV Sokke sub-station.	BESCOM	Tumakuru	Davanagere			329.0	Existing Transformer overload		197.4	131.6	
77	Augmentation of existing 1x5 MVA by 1x12.5 MVA at 66/11 kV Venkatapura sub-station.	BESCOM	Tumakuru	Tumakuru			144.0	Existing Transformer overload		28.8	72.0	43.2
78	Replacement of 1x12.5 MVA, 66/11 kV power transformer by 1x20 MVA, at 66/11 kV Pavagada sub-station.	BESCOM	Tumakuru	Tumakuru			210.0	Existing Transformer overload		42.0	105.0	63.0
79	Hosakere_Madhugiri: Replacing 1x8MVA, 66/11kV by 1x 12.5MVA,66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			143.0	Existing Transformer overload		28.6	71.5	42.9
80	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Nagalamadike sub-station.	BESCOM	Tumakuru	Tumakuru			143.0	Existing Transformer overload		28.6	71.5	42.9
81	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Holavanahalli sub-station.	BESCOM	Tumakuru	Tumakuru			143.0	Existing Transformer overload		28.6	71.5	42.9
82	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Pulamaghatta sub-station.	BESCOM	Tumakuru	Tumakuru			143.0	Existing Transformer overload		28.6	71.5	42.9
83	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Badavanahalli sub-station.	BESCOM	Tumakuru	Tumakuru			143.0	Existing Transformer overload		28.6	71.5	42.9
84	Augementation of existing 1x6.3 MVA by 1x12.5 MVA at 66/11 kV Rampura sub-station.	BESCOM	Tumakuru	Tumakuru			155.0	Existing Transformer overload		31.0	77.5	46.5
85	Augementation of existing 1x6.3 MVA by 1x12.5 MVA at 66/11 kV Turuvanur sub-station.	BESCOM	Tumakuru	Chitradurga			150.0	Existing Transformer overload		30.0	75.0	45.0
86	Augementation of existing 1x12.5 MVA by 1x20 MVA at 66/11 kV Chitradurga sub-station.	BESCOM	Tumakuru	Chitradurga			210.0	Existing Transformer overload		42.0	105.0	63.0
87	Augementation of existing 1x12.5 MVA by 1x20 MVA at 66/11 kV Aimangala sub-station.	BESCOM	Tumakuru	Chitradurga			210.0	Existing Transformer overload		42.0	105.0	63.0
88	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Chitrahalli sub-station.	BESCOM	Tumakuru	Chitradurga			140.0	Existing Transformer overload		28.0	70.0	42.0
89	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Sirigere sub-station.	BESCOM	Tumakuru	Chitradurga			140.0	Existing Transformer overload		28.0	70.0	42.0
90	Replacement of 1x8 MVA, 66/11 kV power transformer by 1x12.5 MVA at 66/11 kV Balenahalli sub-station.	BESCOM	Tumakuru	Chitradurga			140.0	Existing Transformer overload		28.0	70.0	42.0
91	Augementation of existing 1x12.5 MVA by 1x20 MVA at 66/11 kV Nayakanahatti sub-station.	BESCOM	Tumakuru	Chitradurga			210.0	Existing Transformer overload		42.0	105.0	63.0
92	Augementation of existing 2x12.5 MVA by 2x20 MVA at 66/11 kV Bharamasagar sub-station.	BESCOM	Tumakuru	Chitradurga			400.0	Existing Transformer overload		80.0	200.0	120.0
93	Replacement of 2x8 MVA, 66/11 kV power transformer by 2x12.5 MVA at 66/11 kV Hireguntur sub-station.	BESCOM	Tumakuru	Chitradurga			288.0	Existing Transformer overload		57.6	144.0	86.4

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
94	Replacement of 1x8 MVA, 66/11 kV power transformer-II by 1x12.5 MVA at 66/11 kV Kurubarahalli sub-station.	BESCOM	Tumakuru	Chitradurga			144.0	Existing Transformer overload		28.8	72.0	43.2
95	Kanakapura : Providing 1X20MVA, 66/11kV Power transformer as a SPARE at Kanakapura 66/11kV S/s with associated bay equipments	BESCOM	Bengaluru	Ramanagara			307.0	System Improvement		61.4	153.5	92.1
96	Erection of 1X20MVA spare power transformer by extending existing 66KV bay at 66/11 KV sub station, Gudemaranahalli in TL&SS Division, Nelamangala	BESCOM	Bengaluru	Ramanagara			256.0	System Improvement		51.2	128.0	76.8
97	Bommasandra I/A: Providing 1X20MVA, 66/11kV Power transformer as a SPARE at Bommasandra I/A 66/11kV S/s with associated bay equipments	BESCOM	Bengaluru	Bengaluru Rural			256.0	Existing Transformer overload		51.2	128.0	76.8
98	Augmentation of 2 No.s of existing 8 MVA, 66 /11 kV transformers by 2 X 12.5MVA 66/11 kV transformers at 220/66/11 kV T K Halli sub-station.	BESCOM	Bengaluru	Bengaluru Rural			281.9	Existing Transformer overload		56.4	141.0	84.6
99	Providing additional 12.5 MVA Transformer-2 at 66/11 kV Sankalgere sub-station in Channapatna Taluk, Ramanagara District	BESCOM	Bengaluru	Ramanagara			257.7	Existing Transformer overload		51.5	128.8	77.3
100	KGF : Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			202.5	Existing Transformer overload		40.5	101.3	60.8
101	Bangarpet: Replacing second 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			212.2	Existing Transformer overload		42.4	106.1	63.7
102	Augmentation of 1x12.5MVA Power Transformer-I by 1x20MVA Power Transformer at 66/11KV Vemagal Sub-station in Kolar Taluk of TL & SS Division Kolar.	BESCOM	Bengaluru	Kolar			189.2	Existing Transformer overload		37.8	94.6	56.8
103	Augmentation of 1x8MVA by 1x20MVA Power Transformer (Instead of DPR approved for replacement of 1X8MVA by 1x12.5MVA Power Transformer) at 66/11KV Addagal Sub-station in Srinivasapura Taluk, Kolar district.	BESCOM	Bengaluru	Kolar			203.3	Existing Transformer overload		40.7	101.6	61.0
104	Augmentation of 2x20MVA Power Transformers by 2x31.5MVA Power Transformer at 66/11KV Koramangala Sub-station in Bengaluru.	BESCOM	Bengaluru	Bengaluru Urban			537.6	Existing Transformer overload		107.5	268.8	161.3
105	Attur Yelahanka: Providing additional 1x31.5 MVA, 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Urban			250.0	Existing Transformer overload		10.0	90.0	150.0
106	220kV R/S Gowribidanur: Additional 1x20 MVA, 66/11kV Transformer with 66kV Bay	BESCOM	Bengaluru	CB Pura			200.0	Existing Transformer overload		10.0	70.0	120.0
107	Tamaka : Replacing 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			180.0	Existing Transformer overload		10.0	50.0	120.0

**Capital works planned for 5th MYF period**
**Sub-station works- 400 kv**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
108	Pottery Road: Replacing 1x20MVA, 66/11kV by 1x31.5MVA, 66/11kV Transformer along with one incommer pannel	BESCOM	Bengaluru	Bengaluru Urban			250.0	Existing Transformer overload		5.0	95.0	150.0
109	LR bande: Replacing 1x20MVA, 66/11kV by 1x31.5MVA, 66/11kV Transformer along with one incommer panel	BESCOM	Bengaluru	Bengaluru Urban			250.0	Existing Transformer overload		5.0	50.0	195.0
110	Providing additional 1x20MVA Power Transformer in 66/11kV Elita station	BESCOM	Bengaluru	Bengaluru Urban			200.0	Existing Transformer overload		40.0	120.0	40.0
111	Viduraswatha: Replacing 1x8MVA, 66/11kV by 1x20MVA, Power Transformer-II 66/11kV transformer at 66/11kV Muss Viduraswatha	BESCOM	Bengaluru	CB Pura			200.0	Existing Transformer overload		10.0	70.0	120.0
112	Providing additional 31.5MVA transformer at BTM 4th phase	BESCOM	Bengaluru	Bengaluru Urban			250.0	Existing Transformer overload		50.0	150.0	50.0
113	Providing 1X12.5MVA, 66/11kV Power transformer as a SPARE at Ganjigunte 66/11kV S/s with associated bay equipments	BESCOM	Banagaluru	Chikkaballapura			180.0	System Improvement		5.0	75.0	100.0
114	D Cross: Providing 1X12.5MVA, 66/11kV Power transformer as spare power transformer with associated bay at D-cross s/s	BESCOM	Banagaluru	Bengaluru Rural			180.0	System Improvement		5.0	75.0	100.0
115	Erection of 1X20MVA spare power transformer by extending existing 66KV bay at 66/11 KV sub station, Gudemaranahalli in TL&SS Division, Nelamangala	BESCOM	Bengaluru	Ramnagar			200.0	System Improvement		40.0	120.0	40.0
116	Erection of 1X20MVA spare power transformer by extending existing 66KV bay at 66/11 KV sub station, Kodigehalli in TL&SS Division, Nelamangala	BESCOM	Bengaluru	Bengaluru Urban			200.0	System Improvement		40.0	120.0	40.0
117	Goppenhalli: Replacing 1x8MVA, 66/11kV by 1x 12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		36.0	108.0	36.0
118	Challakere: Providing Additional 1x12.5 MVA, 66/11kV Power Transformer.	BESCOM	Tumakuru	Chitradurga			180.0	Existing Transformer overload		5.0	75.0	100.0
119	Hosadurga: Replacing 1x12.5 MVA, 66/11kV by 1x 20 MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Chitradurga			200.0	Existing Transformer overload		5.0	75.0	120.0
120	Bevinahalli: Replacing 1x8MVA, 66/11kV by 1x 12.5MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			180.0	Existing Transformer overload		36.0	108.0	36.0
121	Replacement of existing 1x8 MVA power transformer-1 by 1x20 MVA power transformer and 1x8 MVA power transformer-2 by 1x12.5 MVA power transformer at 66/11 kv Anagodu sub-station in Davanagere Taluk, Davanagere District-	BESCOM	Tumakuru	Davanagere			200.0	Existing Transformer overload		5.0	95.0	100.0
122	Replacement of existing 1x8 MVA power transformer-1 by 1x20 MVA power transformer at 66/11 kv Kora sub-station in Tumakuru Taluk, Tumakuru District	BESCOM	Tumakuru	Tumakuru			200.0	Existing Transformer overload		5.0	95.0	100.0

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
123	Providing additional 1x12.5 MVA, 66/11 kV Power Transformer at 220/66/11 kV Station Neelagunda in Harapanahalli Taluk, Davanagere District	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		5.0	75.0	100.0
124	Replacement of 1x8 MVA, 66/11 kV Power Transformer-II by 1x12.5 MVA, 66/11 kV Power Transformer at 66/11kV Station at Kurubarahalli in Harihara Taluk, Davanagere District	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		36.0	108.0	36.0
125	Replacement of existing 1x8 MVA power transformer 2 by 1x12.5 MVA power transformer with 2 No.s of additional 11 kV Switchgears at 66/11 kV Garaga sub-station in Hosadurga Taluk, Chitradurga District.	BESCOM	Tumakuru	Chitradurga			180.0	Existing Transformer overload		5.0	75.0	100.0
126	Replacement of existing 1x8 MVA power transformer by 1x12.5 MVA power transformer at 66/11 kV Nyamathi Sub-station in Honnali Taluk, Davanagere District.	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		5.0	75.0	100.0
127	Replacement of existing 1x8 MVA power transformer-1 by 1x12.5 MVA power transformer at 66/11 kV sub-station Mavinakatte in Davanagere Taluk, Davanagere District.	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		5.0	75.0	100.0
128	For replacement of existing 1x6.3 MVA power transformer-1 by 1x12.5 MVA power transformer at 66/11 kV Benkikere sub-station in Channagiri Taluk, Davanagere District	BESCOM	Tumakuru	Davanagere			180.0	Existing Transformer overload		5.0	75.0	100.0



**Capital works planned for 5th MYT period**
**Sub-station works- 400 kV**
**Budget required**

Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
129	Providing additional 1x8 MVA, 66/11 kV transformer at 220/66/11kV Sub-station, Mugalavalli in Chikkamagalure Taluk, Chikkamagalure District.	MESCOM	Hassana	Chikkamagalur			150.0	Existing Transformer overload		30.0	90.0	30.0
130	Providing spare 1x12.5 MVA, 66/11 kV transformer at 220/66/11kV Sub-station, Mugalavalli in Chikkamagalure Taluk, Chikkamagalure District.	MESCOM	Hassana	Chikkamagalur			150.0	System Improvement		30.0	90.0	30.0
131	Providing spare 1x12.5 MVA, 66/11 kV transformer at 66/11kV Sub-Station, Juttanahalli in Channarayapatna Taluk, Hassan District.	CESC	Hassana	Hassan			150.0	System Improvement		30.0	90.0	30.0
132	Enhancement of 1x5MVA, 66/11kV Power Transformer-1 by 1x8MVA, 66/11kV Power Transformer along with additional two numbers SWGs (one number in each 11kV Bank) with strengthening of 11kV ODS and Providing Metering & Protection to 66kV Incoming line and strengthening of 66kV ODS (replacement of existing coyote conductor by drake) with necessary civil works (viz replacement of un even and un-sized jelly as per standards and formation of Cable duct) at 66/11kV Hallymysore sub-station in Holenarasipura Taluk, Hassan District.	CESC	Hassana	Hassan			200.0	Existing Transformer overload		10.0	90.0	100.0
133	Doddainduvadi : Replacing 1X8 MVA,66/11 KV transformers by 1X12.5 MVA transformers.	CESC	Mysuru	Chamarajanagara			180.0	Existing Transformer overload		10.0	70.0	100.0
134	Madhuvanahalli : Replacing 1X6.3 MVA,66/11 KV transformers by 1X12.5 MVA transformers .	CESC	Mysuru	Chamarajanagara			113.0	Existing Transformer overload		22.6	67.8	22.6
135	Sathegala : Replacing 1X6.3 MVA,66/11 KV transformers by 1X12.5 MVA transformers .	CESC	Mysuru	Chamarajanagara			150.0	Existing Transformer overload		30.0	90.0	30.0
136	Yelandur : Replacing 2 nd 8 MVA,66/11 KV transformers by 1X12.5 MVA transformers .	CESC	Mysuru	Chamarajanagara			120.0	Existing Transformer overload		24.0	72.0	24.0
137	Chunchanakatte: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			150.0	Existing Transformer overload		30.0	90.0	30.0
138	Berya: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			150.0	Existing Transformer overload		30.0	90.0	30.0
139	Hura: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			180.0	Existing Transformer overload		10.0	70.0	100.0
140	Antharasanth: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			150.0	Existing Transformer overload		30.0	90.0	30.0
141	B.Matkere: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			150.0	Existing Transformer overload		30.0	90.0	30.0
142	Ramapura : Replacement of 2X8MVA, 66/11kV Power Tr. By 2X12.5MVA Tr.	CESC	Mysuru	Chamarajanagara			226.0	Existing Transformer overload		10.0	116.0	100.0

Capital works planned for 5th MYT period									Budget required			
Sub-station works- 400 kV												
Sl. No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR			Reason for taking up the work	FY-19	FY-20	FY-21	FY-22
					Scheduled year of commencement	Scheduled year of completion	Cost to be incurred					
143	Martalli : Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Chamarajanagara			150.0	Existing Transformer overload		10.0	50.0	90.0
144	DMG Halli : Replacement of 1 X 8 MVA, 66/11 KV Power Transformer by 1 X 12.5 MVA	CESC	Mysuru	Mysuru			120.0	Existing Transformer overload		24.0	72.0	24.0
145	Nanjangud : Replacement of 1 X 8MVA, 66/33 KV Power Transformer by 1 X 12.5 MVA, 66/33/11 KV.	CESC	Mysuru	Mysuru			120.0	Existing Transformer overload		24.0	72.0	24.0
146	Doora: Providing additional 1x8MVA, 66/11kV Power Tr.	CESC	Mysuru	Mysuru			150.0	Existing Transformer overload		10.0	50.0	90.0
147	Megalapura : Replacement of 2nd 8MVA, 66/11kV Power Tr. By 12.5MVA Tr.	CESC	Mysuru	Mysuru			120.0	Existing Transformer overload		24.0	72.0	24.0
148	K.Honnalagere: Replacement of 2 X 8 MVA, 66/11 KV Power Transformer by 2 X 12.5 MVA, 66/11 KV.	CESC	Mysuru	Mandya			226.0	Existing Transformer overload		10.0	50.0	166.0
149	66KV S/S Hoovinahadagali: Augumentation 6.3MVA by 12.5 MVA Trf	GESCOM	Kalaburagi	Ballari			180.0	Existing Transformer overload		36.0	108.0	36.0
<b>Other works-66 kV</b>												
1	Chikkamagalur: Providing of 2Nos. of 66kV SF6 CB to Incoming lines from 220kV R/S Muglivali (Chikkamagalur) & 2Nos of 66kV SF6 CB to Incoming lines from Bhadra including 2Nos. bay at Chikkamagalur Sub-Station	MESCOM	Hassana	Chikkamagaluru			211.33	System Improvement	50	147.931	13.399	
2	Audugodi GIS: Conversion of existing 66/11 kV Audugodi substation(AIS) to GIS substation	BESCOM	Bengaluru	Bangalore Urban			4483	System Improvement		500	2241.5	1741.5
<b>TOTAL Rs. in Crores</b>							<b>6941.5</b>		<b>106.3</b>	<b>1061.1</b>	<b>2174.3</b>	<b>2808.3</b>

# Capital Works planned for 5th MYT period

## Proposed capital investment plan for FY 20-22

Completed works													Budget required for FY-20
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
<b>Sub-station works-400 kV</b>													
1	Jagalur (Hiremallanahole): a) Establishing 2x500MVA,400/220 KV partly GIS S/S i.e., 400kV GIS and 220kV AIS with associated 400kV lines. b) 220kV DC Line to Thallak, Chitradurga & Kudligi along with 220kv TB's	BESCOM	Tumakuru	Davanagere			28440.49	2016	2018-19	17149.62	9706	Forest clearance to be obtained for 400k transmission line. online Proposal Submitted : 07.03.2018. Proposal is pending in Government of Karnataka.	1584.87
2	Doni 400kV (Gadag): Establishing 2x500MVA, 400/220kV Station with associated 440kV & 220kV link lines for a distance of 26.798Kms	HESCOM	Bagalkote	Gadag			17738.35	2016	2018-19	12459.49	2253	500MVA Transformer-I, Commissioned on 17-Oct-2018 500MVA Transformer-II, Commissioned on 20-Oct-2018 400kV line commissioned on 16-Oct-2018. 220kV line commissioned on 23-Oct-2018. Delay due to local ROW issues	3025.86
<b>Transmission line works-400 kV</b>													
1	YTPS to 400kV Bellary pooling station (BPS): Construction of 400kV DC Line with Quad Moose Conductor from YTPS to Proposed 400kV Bellary pooling station (BPS) for a distance of 142.49Kms	GESCOM	Kalaburagi	Raichur			51500.42	2015	2018-19	37365.35	10156	Commissioned on 04-May-2018. Delay due to ROW issues	3979.07
<b>Augmentation works-400 kV</b>													
1	Nelamangala 400kV: Providing additional 3rd 500MVA, 400/220kV three phase Power ICT with associated equipments for a distance of 3.06 kms	BESCOM	Bengaluru	Bengaluru Rural			4177.12	2011	Commissioned	3953.86	100	Slow progress by the agency	123.26
<b>Other sub-station works-400 kV</b>													
1	400kV R/S Hoody: Providing 63MVAR Bus Reactor at 400/220kV Station.	BESCOM	Bengaluru	Bengaluru Urban			726.2	2011	2018-19	267.8	200.0	Slow progress by the agency	258.4
2	Nelamangala: Providing 63MVAR Bus Reactor at 400/220kV Station.	BESCOM	Bengaluru	Bengaluru Rural			641.7	2011	2018-19	232.9	170.0	Slow progress by the agency	238.8
<b>Sub-station works-220 kV</b>													

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
1	Koramangala: Establishing 220/66/11kV GIS substation at Kormangala with 220 kV 1000 sqmm LILO UG cable from existing HSR-NIMHANS UG cable with associated 66kV lines.	BESCOM	Bengaluru	Bengaluru Urban			18047.93	2017	2018-19	3881.96	10500	Target date is 05-Nov-2018. will be commission shortly	3666.0
2	ITI : Establishing 2x150 MVA, 220/66/11kV GIS substation at ITI with 220kV DC 1200 sq mm Copper single core XLPE UG cable from existing Hoody-Hebbal for a route length of 2.607Kms along with associated 66kV line.	BESCOM	Bengaluru	Bengaluru Urban			19711.21	2017	2018-19	5177.66	11000	Target date is 05-Nov-2018. will be commission shortly	3533.6
3	Hoskote: a) Establishing 2x100MVA, 220/66kV Station with 220/66kV MC line from BIAL with 220kV TB at BIAL b) Hoskote 220KV LILO line from Hoody-Kolar line c) 66KV SC line from Hoskote to Mandur, Pillaguppa-sulibele line to Nandagudi, 66 kV TB at Nandagudi & BIAL d) Hoskote to Tower no5 of existing Pillagumpa-Sulibele 66kV line and Tower no5 of existing Pillagumpa-Sulibele 66kV line to Hoskote s/s 1) 21.03 Kms 2) 13.12 Kms 3) 10.25 Kms 4) 10.28 Kms.	BESCOM	Bengaluru	Bengaluru Rural			7475.45	2007	Commissioned	6686.78	250	Station commissioned on 19-Feb-2009. 220kV LILO line and 66kV lines work short closed. Balance woks to be tendered. Delay due to ROW issues for constructing transmission line.	538.7
4	Dobbaspet (Nelamangala): a) Establishing 2x100MVA, 220/66kV Station with 220kV LILO of Kadur - Nelamangala b) 66kV lines to Nelamangala & Kolala Sub-Station upto loc 65 c) Construction of 66kV SC line on DC towers from Dabaspeta to Kolala from location 66 to 99 for a distance of 5.856 kms	BESCOM	Bengaluru	Bengaluru Rural			5416.94	a) 2007 b) 2007 c) 2013	Commissioned	4618.51	40	Substation commissioned on 31-Mar-2009 66kV lines to Nelamangala & Kolala Sub-Station upto loc 65 commissioned on 26-May-2011 Dabus pet Kolalline : delay due to ROW issues	758.4

**Completed works**

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
5	Pavagada: Establishing 2x100MVA, 220/66kV Station with associated lines for a distance of 120.00 Kms.	BESCOM	Tumakuru	Tumakuru			9473.37	2013	2018-19	5700.17	3000	Commissioned on 30-Nov-2018. Delay due to ROW issue for constructing transmission line.	773.2
6	Mangalore SEZ: Establishing 2x100MVA, 220/110kV and 2x20MVA, 110/11kV Station at MSEZ near Bajpe in Mangalore taluk along with associated lines for a distance of 6.854Kms	MESCOM	Hassana	Dakshina Kannada			3855.62	2011	Commissioned	3720.98	100	Commissioned on 30-Dec-2014. Delay due to ROW issues for constructing transmission line. Construction of 110kV lines pending due to ROW issues.	34.6
7	Chikkamagalur: Part A Establishing 2 x 100MVA, 220/66KV Substation & 1 x 12.5 MVA 66/11 KV Sub Station at Chikkamagalur and Construction of 220KV DC line for a length of 28.55 Kms from 220KV Shimoga Mysuru DC line to the proposed 220/66KV S/S at Chikkamagalur on PTK Basis Part B Construction of 66KV Evacuation lines from the proposed 220KV Station at Chikkamagalur 1) Chikkamagalur to Hassana DC line: 0.6 Kms 2) Chikkamagalur MC line : 0.74Kms 3) 66KV DC line from proposed 66KV MC line to Balehonnur (Mattavara Limits): 7.8 Kms	MESCOM	Hassana	Chikkamagaluru			5286.74	220KV S&L 2008 Eva-line 2007	Commissioned	4437.65	10	Station commissioned on 28-Oct-2011. Delay due to ROW issues for constructing transmission line. Construction of 66kV lines pending due to ROW issues.	839.1
<b>Transmission line works-220 kV</b>													
1	Vasanthanarasapura to Madhugiri: Construction of 220kV DC line with Moose ACSR from PGCIL Station at Vasanthanarasapura to existing 220kV station at Madhugiri along with terminal	BESCOM	Tumakuru	Tumakuru			7945.94	2015	2018-19	6488.82	1149	Delay due to KIADB issue. (land to be acquired by KIADB)	308.12

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
2	HAL Project: a) Construction of 220/220KV MC line for Shifting of Existing 220KV B1,B2 & B3,B4 Lines at proposed HALpremises b) Construction of 110KV D/C line with NBT for the shifting of existing 110KV S/C Nittur-Doddaguni line at Proposed HAL premises near Bidarehalli Kaval village limits in Gubbi taluk in Tumakuru District.	BESCOM	Tumakuru	Tumakuru			6925.32	2016	2018-19	4370.78	1500	220kv line commissioned on 11-Sep-2018. 110kv line work under progress. Delay due to Forest clearence.	1054.54
3	Hassana: a) Re-orientation of 220kv & 66kv lines from Hassana 220kv Station. b) Shifting of 220kv B-4 LILO line passing through Airport Land near Bhoovanahalli Cross. c) Providing 2Nos of 66kv TB's for C R Patna 66kv DC line at 220kv/66KV R/S Hassana for a distance of 66kv 7.8/220kv 17.68Kms	CESC	Hassana	Hassana			1850.18	2007	2018-19	1176.34	100	ROW issues for constructing transmission line	573.84
<b>Sub-station augmentation- 220 kV</b>													
1	Naganathapura: Augumentation of 2x100 MVA, 220/66/11kv Power Transformer by 2x150MVA, 220/66/11kv Power Transformers at 220/66/11kv Naganathapura Receiving Station, Bangalore South Taluk, Bangalore Urban District.	BESCOM	Bengaluru	Bengaluru Urban			1777.57	2018	2018-19	0	492	Target date is 19-Mar-2019	1285.57
<b>Other works-220 kV</b>													
1	Singanayakanahalli: Construction of 4Nos of 220kV Bays for KPTCL lines.	BESCOM	Bengaluru	Bengaluru Urban			761.93	2010	commissione	742.31	5	Commissioned (DCW work)	14.62
2	Somanahalli: R&M works at Somanahalli 220/66kv Station	BESCOM	Bengaluru	Bengaluru Urban			2016.71	2012	2018-19	1312.02	500	Delay due line clear issues	204.69
3	KIADB DB Pura: R & M works at 220/66kv KIADB DB Pura Station for a distance of 0.56	BESCOM	Bengaluru	Bengaluru Rural			3072.66	2014	2018-19	2120.36	600	Delay due line clear issues	352.3

**Completed works**

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
4	Renovation and Upgradation of Protection systems of 220kV Substations (12 Nos) in Kalaburagi Transmission Zone	GESCOM	Kalaburagi	Kalaburagi			1436.37	2015	2018-19	602.28	160	Works under progress. Delay due to slow progress by the agency and line clear issues.	674.09
5	Chikkodi 220kV R/S: Construction of 2 Nos of 220kV TBs at 220kV Chikkodi S/s for Terminating 220kV Ghataprabh-Chikkodi DC line.	HESCOM	Bagalkote	Belgaum			362.32		2018-19	0	1	Twice tendered no particpepts. Hence decided to be tendered with additional 3rd 100MVA	361.32
<b>Sub-station works-110 kv</b>													
1	<b>Karaya:</b> Establishing 2x10MVA, 110/11kV Sub-Station with SC line from VIT College for a distance of 15.00 Kms.	MESCOM	Hassana	Dakshina Kannada			1574.05	2008	Commissioned	1401.82	25	Commissioned on 16-Apr-2014. Delay due to ROW issues for constructing transmission line.	147.231
2	<b>McGann Hospital;</b> Establishing 1x10MVA,110/11KV S/S at McGann Hospital premises in Shivamogga Dist with running of 110kV , 240Sqmm XLPE Copper U.G.Cable single circuit with one spare cable (4Runs) for a dist of 2.123Kms from 110/11kV Alkola S/S to the proposed 110/11kV S/S MC Gann Hospital with construction of 1No of TB at Alkola S/S .	MESCOM	Hassana	Shimoga			1540.2	Stn:2018 Line:2018	2018-19	0	1000	Target date is 14-Mar-2019	540.2

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
3	<b>Garag (Shedabal):</b> Establishing 2x10MVA, 110/11kV Sub-Station with associated line for a distance of 4.598Kms	HESCOM	Bagalkote	Dharwad			1080.62	2017	2018-19	337.06	600	Commissioned on 25-Aug-2018 (Targety date 15-Sep-2018)	143.56
4	<b>Belavanaki:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line for a distance of 22.27Kms	HESCOM	Bagalkote	Gadag			1244.66	2017	2018-19	339.52	700	Commissioned on 30-Oct-2018 (Jtyager date 06-Jun-2018). Delay due to ROW issues for constructing transmission line	205.14
5	<b>Islampur:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line for a distance of 7.875Kms	HESCOM	Bagalkote	Belgaum			998.81	2018	2018-19	22.27	600	Commissioned on 31-Oct-2018 (target date 03-Oct-2018())	376.54
6	<b>Kakamari:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line & TB.	HESCOM	Bagalkote	Belgaum			922.03	2018	2018-19	25.38	600	ROW issues for constructing transmission line	296.65
7	<b>Aratagal(Kitadal):</b> Establishing 2x10MVA, 110/11kV Sub-Station with associated line & TB for a distance of 8.574Kms	HESCOM	Bagalkote	Belgaum			1002.44	2017	2018-19	0	600	Target date is 19-Dec-2018	402.44
8	<b>Morab:</b> Establishing 2x10MVA 110/11kV Sub-Station with associated line for a distance of 7.526Kms	HESCOM	Bagalkote	Belgaum			1037.64	2016	2018-19	646.72	310	Commissioned on 12-Dec-2018. Delay due to loacal ROW issues and Court case for constructing transmission line	80.92
9	<b>Talikote:</b> Up-gradation of existing 33/11kV S/s to 2x10MVA, 110/11kV Sub-Station with associated line for a distance of 17.557Kms	HESCOM	Bagalkote	Bijapur			1403.29	2017	2018-19	214.28	800	Local ROW issues (Standing crop) for constructing transmission line	389.01
10	<b>Rodagi (Khedagi cross) :</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line for a distance of 10.969	HESCOM	Bagalkote	Bijapur			903.25	2017	2018-19	148.73	600	Local ROW issues (Standing crop) for constructing transmission line	154.52
11	<b>Adavi Amareshwara:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated line	GESCOM	Kalaburagi	Raichur			541.76	2017	2018-19	0	500	Target date is 19-Dec-2018	41.76
<b>Transmission line works-110 kV</b>													
1	Kibbanhalli - CN Hally - Hulyiar : Construction of 110kV DC line in the new corridor from 220kV K.B.Cross to Thimmanahally tapping point for a distance of 20.5 Kms	BESCOM	Tumakuru	Tumakuru			975.5	2010	2018-19	654.4	200	ROW issues at 2 Locations	121.1



**Completed works**

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
2	110/11kV MUSS Thirthahalli LILO: 1) Construction of 110kV, 0.523KM LILO Line tapping from 110kV SK line to the existing 110/11kV Thirthahalli Sub-station in Thirthahalli Taluk, Shivamogga District. 2) Construction of 110kV line Terminal bay at 110/11kV Thirthahalli S/s.	MESCOM	Hassana	Shimoga			200.29	2018	2018-19	0	150	Line clear issue and delay by agency	50.29

**Augmentation works-110 kV**

1	Netlamadnur 220kV R/S: Additional existing 1x10MVA, 110/11kV Power Transformer by 1x20MVA, 110/11kV Power Transformer at existing 220/110/33/11kV Netlamudnur S/S	MESCOM	Hassana	Dakshina Kannada			164.56	2017	2018-19	131.22	30	Instead of replacement, additional transformer approved in 56th TCCM. Additional transformer work under progress.	3.34
2	Vittla: Replacing 1x10MVA, 110/11kV & 1x10MVA, 110/12.1kV Power Transformer by 2x20MVA, 110/11kV Power Transformer at Vittla S/s.	MESCOM	Hassana	Dakshina Kannada			481.99	2017	2018-19	34.48	144	1 no of transformer allotted on 24-Sep-2018 and commissioned on 08-Dec-2018.	303.51
3	Haveri: Providing spare 1x20MVA, 110/33-11kV Transformer	HESCOM	Bagalkote	Haveri			279	2017	2018-19	38.81	196	Transformer allotted on 04-Aug-2018.	44.19
4	Karwar(Shejwad): Providing additional 1x20MVA, 110/33-11kV Transformer	HESCOM	Bagalkote	Uttar Kannada			425.35	2017	2018-19	146.3	260	Transformer allotted on 21-Jun-2018 and commissioned on 06-Sep-2018	19.05
5	Rampur: Replacement of 1x10MVA, 110/33kV by 1x20MVA, 110/33kV Transformer	HESCOM	Bagalkote	Bagalkote			216.37	2017	2018-19	142.39	44	Transformer allotted on 21-Jun-2018 and commissioned on 06-Sep-2018	29.98
6	Hirebevanur: Providing additional 1x10MVA, 110/11kV Transformer.	HESCOM	Bagalkote	Bijapur			129.3	2017	2018-19	58.31	54	Transformer received at site 02-May-2018 and commissioned on 22-Aug-2018	16.99
7	Lachyan: Replacing 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer.	HESCOM	Bagalkote	Bijapur			304.96	2017	2018-19	206.82	22	Commissioned on 29-May-2018	76.14

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
8	110 KV S/S Malaghan: Replacement of 1X10 MVA, 110/11 KV by 1X20 MVA, 110/11 KV transformer instead of Providing additional 1x10MVA, 110/11kV Transformer	HESCOM	Bagalkote	Bijapur			305.53	2017	2018-19	165.06	100	Transformer allotted on 24-Apr-2018 and commissioned on 07-Jun-2018	40.47
9	Alkod: Providing additional 1 x 10 MVA, 110/11 kV Power Transformer at Alkod S/s	GESCOM	Kalaburagi	Raichur			226.73	2018	2018-19	0	150	Transformer to be allotted	76.73
10	Maliyabad : Providing additional 1 x 10 MVA, 110/11 kV Power Transformer at Maliyabad S/s	GESCOM	Kalaburagi	Raichur			226.78	2018	2018-19	0	150	Transformer to be allotted	76.78
11	Gurugunta: Providing additional 1 x 10 MVA, 110/11 kV Power Transformer at Gurugunta S/s	GESCOM	Kalaburagi	Raichur			226.28	2018	2018-19	0	150	Transformer to be allotted	76.28
12	BislaHalli : Creating 33kV reference by Providing 1x20MVA, 110/33kV Transformer.	GESCOM	Kalaburagi	Bellary			335.92	2017	2018-19	21.34	164	Transformer allotted on 24-Sep-2018.	150.58
13	Kampli: Repl of 1X10MVA by 1X20MVA, 110/11KV Trf at 110/11KV S/S Kampli	GESCOM	Kalaburagi	Bellary			182.78	2018	2018-19	131.68	50	Transformer allotted on 03-Nov-2017 and commissioned on 01-Aug-2018	1.1
14	Munirabad : Installing of 1x10MVA, 110/11kV Power transformer at 220/110/66/33/11kV Munirabad Power House Station	GESCOM	Kalaburagi	Koppal			155.08	2017	2018-19	0	45	Transformer allotted on 21-Feb-2018 work under progress	110.08
15	Dambal: Providing additional 1x10MVA, 110/11kV Transformer	HESCOM	Bagalkote	Gadag			95.71	2018	2018-19	17.29	50	Transformer to be allotted	28.42
<b>Other works-110 kV</b>													
1	Providing 12.1kV 2.9MVAR Capacitor Bank and other allied equipment's in KPTCL Sub-stations of Bagalkote Zone.	HESCOM	Bagalkote	Bagalkote			1783.83	2015	2018-19	823.42	484	Works under progress. Delay due to slow progress by the agency and line clear issues. Delay in supply of 11kV Switchgears by MEI	476.41

**Completed works**

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
2	Providing 12.1KV, 2.9MVAR Capacitor Bank and other allied equipment's in KPTCL Sub-stations of Kalaburagi Zone.	GESCOM	Kalaburagi	Kalaburagi			619.45	2015	2018-19	194.4	100	Works under progress. Delay due to slow progress by the agency and line clear issues. Delay in supply of 11kV Switchgears by MEI	325.05
<b>Sub-station works-66 kV</b>													
1	Hulimangala : Establishing 2x12.5MVA, 66/11kV Keonics (Electronic City) Sub-Station for a route length of 3.789Kms	BESCOM	Bengaluru	Bengaluru Urban			3474.13	Stn: 2018 cable: 2018	2018-19	0	3000	Target date is 13-Mar-2019	474.13
2	Thippur: Establishing 1 x 8 MVA 66/11 KV S/S with associated line	BESCOM	Tumakuru	Tumakuru			541.1	2017	2018-19	141.49	350	Local ROW issues for constructing transmission line	49.61
3	Nallur : Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Tumakuru	Davanagere			557.33	2018	2018-19	0	250	Target date is 19-Dec-2018	307.33
4	Visveswarapura: Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Tumakuru	Chitradurga			549.1	2018	2018-19	0	300	Target date is 19-Dec-2018	249.1
5	Rudrapatna: Establishing 1 X 8 MVA ,66/11 KV S/S at Rudrapatna in Arkalgud Tq, Hassana Dist with construction of 66kV SC line on DC towers for a route length of 4.8Kms to tap the existing 66kV Ramanathapura-Kushalanagar SC line to the proposed 66/11kV Rudrapatna S/S.	CESC	Hassana	Hassana			558.98	2018	2018-19	0	300	Target date is 11-Dec-2018. ROW issues for constructing transmission line (standing crops)	258.98
6	Santhekadur: Establishing 1x8MVA, 66/11kV Sub-Station at Santhekadur in Shivamogga Tq & Dist with construction of 66kV SC line on DC towers from the existing 66kV Bhadra-MRS Shivamogga line to the proposed S/S at Santhekadur for a dist of 0.095Kms.	MESCOM	Hassana	Shimoga			422.08	2018	2018-19	0	300	Target date is 11-Nov-2018. Delay by agency (Transformer to be supplied). ROW issues for constructing transmission line.	122.08
7	Bannikuppe Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 3.575Kms	CESC	Mysuru	Mysuru			663	2018	2018-19	0	300	Target date is 19-Dec-2018	363

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
8	Chandravadi (Nallitalapura):Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 1.290Kms	CESC	Mysuru	Mysuru			604	2018	2018-19	0	300	Target date is 23-Mar-2019	304
9	Maliyur: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 2.809Kms	CESC	Mysuru	Mysuru			670.21	2017	2018-19	173.03	400	Delay in supply of 11kV Switchgears by MEI (KPTCL scope)	97.18
10	Hemmargala: Establishing 1x8MVA, 66/11kV Substation with associated line for a distance of 3.905Kms	CESC	Mysuru	Mysuru			653.7	2017	2018-19	231.15	400	Delay in supply of 11kV Switchgears by MEI (KPTCL scope)	22.55
11	Tumbekere: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 6.596 Kms.	CESC	Mysuru	Mandya			778.96	2018	2018-19	0	400	Target date is 11-Dec-2018	378.96
12	Vadakepura Limits: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 0.356Kms	CESC	Mysuru	Mandya			585.91	2018	2018-19	0	300	Target date is 19-Dec-2018	285.91
13	Devalapura Handpost (Kasalagere) Establishing 1 x 8MVA, 66/11 KV Sub-Station with associated line for a distance of 7.65Kms	CESC	Mysuru	Mandya			881.84	2018	2018-19	0	400	Target date is 13-Dec-2018	481.84
14	66kv Badanakuppe Industrial area : Establishing 2 X 31.5 MVA, 66/11kV Station with MCMV with 220kv at top x arm provision & 66kv at bottom associated d/c lines	CESC	Mysuru	Chamarajana gara			3371.48	2018	2018-19	0	2500	Target date is 10-Jan-2019	871.48
15	Bargi: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a Distance of 10.864Kms.	CESC	Mysuru	Chamarajana gara			779.68	2017	2018-19	192.16	500	Commissioned on 24-Sep-2018 (Target date: 15-Sep-2018)	87.524
16	Kothanoor: Establishing 1x8MVA, 66/11kV Sub-Station with associated line.	CESC	Mysuru	Chamarajana gara			972.49	2017	2018-19	0	500	Transformer to be supplied (agency scope). 11kV Switchgears to be supplied by MEI (KPTCL scope)	472.49
17	Agara mamballi : Establishing 1 x 8 MVA,66/11 KV sub-station with associated line for a distance of 3.047Kms	CESC	Mysuru	Chamarajana gara			728.98	2018	2018-19	0	400	Target date is 19-Dec-2018	328.98

**Completed works**

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
18	Bachigondanahalli: Establishing 1x8MVA, 66/11kV Sub-Station with associated line or a distance of 6.85Kms	GESCOM	Kalaburagi	Bellary			585	2016	2018-19	215.3	205	Commissioned on 25-Aug-2018 (Targety date 22-Dec-2017) Delay due to ROW issues for constructing transmission line	164.7
19	Harivi : Establishing of 66/11kV Sub-station with installed capacity of 1x8MVA 66/11kV Transformer or a distance of 6.638Kms	GESCOM	Kalaburagi	Bellary			585.39	2016	2018-19	367.15	110	Delay due to ROW issues for constructing transmission line	108.24

**Transmission line works-66 kV**

1	T.K Halli to Iggalur: Construction of 66kV DC line for a distance of 9.924Kms from 220/66/11kV T.K.Halli Station to 66kV Iggalur Tap point in the existing corridor of 66kV T.K Halli-Akkurmole SC line and Providing 66kV TB's at T.K Halli	BESCOM	Bengaluru	Ramanagara			326.3	2017	2018-19	106.5	165.0	Delay due to ROW issues	54.8
2	Davanagere - Chitradurga No. 1 : Re-construction of 66kV S/C line on D/C towers in the existing corridor for a distance of 55.70 Kms.	BESCOM	Tumakuru	Davanagere			570.2	2010	2018-19	495.1	75.0	ROW issues for constructing transmission line	0.1
3	Davanagere - Chitradurga No. 2: Re-construction of 66kV S/C line on D/C towers in the existing corridor for a distance of 53.84 Kms.	BESCOM	Tumakuru	Davanagere			455.1	2010	2018-19	436.1	18.0	ROW issues for constructing transmission line	1.0

**Augmentation works-66 kV**

1	Thyamagondlu: Replacing 2x8MVA, 66/11kV by 2x20MVA, 66/11kV Transformers	BESCOM	Bengaluru	Bengaluru Rural			415.12	2016	2018-19	126.07	62	2nd Transformer to be allotted	227.1
2	Suttur : Replacing 2x8MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformers	CESC	Mysuru	Mysuru			244.72	2016	2018-19	89.69	130	1st transformer commissioned on 07-Sep-17. 2nd Transformer to be allotted	25.0
3	Santhesargur: Replacing 2x6.3MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformers	CESC	Mysuru	Mysuru			320.96	2018	2018-19	0	160	1st transformer commissioned on 10-Jul-2018. 2nd Transformer to be allotted	161.0
4	H.D.Kote: Replacing 2x12.5MVA, 66/11kV by 2x20MVA, 66/11kV Transformers	CESC	Mysuru	Mysuru			351.44	2017	2018-19	140.02	211	1st transformer commissioned on 15-Sep-17. 2nd Transformer to be allotted	0.4

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
5	<b>Hunsur:</b> Replacing 2x12.5MVA, 66/11kV by 2x20MVA, 66/11kV Transformers	CESC	Mysuru	Mysuru			369.32	2017	2018-19	301.92	60	1st transformer commissioned on 31-Jul-17. 2nd transformer commissioned on 02-Aug-17.	7.4
6	<b>R.K Nagar :</b> Replacement of 2 nd 12.5 MVA NGEF Power Transformer by 20 MVA, 66/11kV Power Transformer	CESC	Mysuru	Mysuru			196.51	2017	2018-19	142.09	40	Commissioned on 06-Sep-17	14.4
7	<b>Ravandur :</b> Providing Additional 1X8 MVA, and replacing 1x8MVA by 12.5MVA 66/11kV Transformer.	CESC	Mysuru	Mysuru			230.66	2016	2018-19	127.89	76	Replacement of 8 MVA by 12.5 MVA Transformer commissioned on 11-Oct-17. Additional Transformer commissioned on 20-Jun-2018.	26.8
8	<b>Bylukuppe:</b> Providing Additional 1X8 MVA, and replacing 1x8MVA by 1x12.5MVA 66/11kV Transformer.	CESC	Mysuru	Mysuru			232.27	2016	2018-19	127.83	77	Replacement of 8 MVA by 12.5 MVA Transformer commissioned on 16-Oct-17. Additional Transformer commissioned on 20-Jun-2018.	27.4
9	<b>Hampapura :</b> Providing Additional 1x12.5MVA 66/11kV Transformer and Replacement of 1 X 8 MVA by 1 X 12.5 MVA, 66/11kV with additional SWG	CESC	Mysuru	Mysuru			334.3	2017	2018-19	89.52	150	Replacement of 1x8 by 12.5 MVA. Commissioned on 05-Feb-18. Additional 12.5MVA transformer to be allotted.	94.8
10	<b>Hanagodu :</b> Replacement of 1 X 8 MVA by 1 X 12.5 MVA 66/11kV Transformer.	CESC	Mysuru	Mysuru			141.92	2017	2018-19	3.24	130	Commissioned on 19-Jun-2018	8.7
11	<b>Terakanambi:</b> Replacing 2X8MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformers	CESC	Mysuru	Chamarajana gara			252	2016	2018-19	184.05	25	2nos 12.5 MVA Transformers allotted on 22-Apr-2017 1st Transformer commissioned on 24-May-17. 2nd Transformer commissioned on 27-May-17.	43.0
12	<b>P.G.Palya :</b> Providing Additional 1X8 MVA, 66/11kV Transformer	CESC	Mysuru	Chamarajana gara			120.45	2014	2018-19	28.5	67	Commissioned on 23-Mar-18.	25.0
13	<b>Telecom Layout:</b> Replacing 1x20MVA, 66/11kV by 1x31.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Urban			235	2018	2018-19	0	200	Transformer allotted on 17-Oct-2018 and commissioned on 04-Dec-2018.	35.0
14	<b>Abbigere:</b> Replacement of 2x12.5MVA, 66/11kV by 2x20MVA, 66/11kV transformer	BESCOM	Bengaluru	Bengaluru Urban			546.12	2018	2018-19	0	5	Transformer allotted on 20-Aug-2018 and commissioned on 15-Sep-2018.	541.1

Completed works													
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required for FY-20
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred till date 31-03-2018	Budget for 2018-19		
15	<b>Raj Mahal Vilas (RMV):</b> Augmentation of 2x20MVA, 66/11kV by 2x31.5MVA, 66/11kV transformer	BESCOM	Bengaluru	Bengaluru Urban			530	2018	2018-19	0	85	Transformer allotted on 08-Aug-2018 and commissioned on 09-Sep-2018.	445.0
16	<b>Nelagadaranahalli:</b> Replacing 2x20MVA, 66/11kV by 2x31.5MVA, 66/11kV transformer	BESCOM	Bengaluru	Bengaluru Urban			668.45	2018	2018-19	0	200	Transformer allotted on 25-Jul-2018 and commissioned on 12-Aug-2018.	468.5
17	<b>Anekal.</b> Replacing 1X20MVA by 1X31.5MVA, 66/11KV Power transformer at 66/11KV S/S,	BESCOM	Bengaluru	Bengaluru Rural			282.61	2018	2018-19	0	200	Transformer to be allotted	82.6
18	Providing additional 20 MVA TR at 220 kV KIADB Doddaballapura	BESCOM	Bengaluru	Bengaluru Rural			387	2018	2018-19	0	5	To be tendered	382.0
19	<b>Channapatna:</b> Augmentation of 1X12.5 MVA 66/11 kV Tr. By 1 X 20 MVA at 66/11 kV Channapatna	BESCOM	Bengaluru	Ramanagara			181.74	2018	2018-19	0	170	Transformer failed when commissioning, new transformer allotted.	11.7
<b>Other works-66 kV</b>													
1	<b>Renovation and upgradation of protection system</b> of 220kV Sub-stations (10Nos) & 400kV Sub- Station (1No) in Hassana Transmission Zone	CESC	Hassana	Hassana			1449.82	2015	2018-19	528.65	900	Works under progress. Delay due to slow progress by the agency and line clear issues.	21.2
<b>TOTAL Rs. in Crores</b>							<b>2450.3009</b>			<b>1326.1</b>	<b>753.0</b>		<b>371.2</b>

Ongoing works														Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19					
<b>Sub-station works-400 kv</b>																
1	<b>Mylasandra (Near Electronic City):</b> Establishing 3 X 500 MVA, 400/220kV GIS Sub-Station at Mylasandra (Near Electronic City) in Bengaluru South Taluk, Bengaluru Urban District along with associated transmission lines and providing additional terminal bays (3 Nos) at 220/66/11kV S/s at Yerandahalli (Short closed work code AA1043)	BESCOM	Bengaluru	Bengaluru Urban			44017.6	2018	2019-20	1.13	10000	Target date is 23-Sep-2019	23811.55	10205		
2	<b>Devanahalli Hardware Park:</b> Establishing 2 X 500 MVA, 400/220kV Sub-Station (400KV GIS & 220KV AIS) at KIADB Hardware Park, Devanahalli, Bengaluru Rural District and also for creation of required 220kV Terminal Bays at the receiving 220/66kV sub-stations for evacuation of power.	BESCOM	Bengaluru	Bangalore Rural			43939.5	2018	2019-20	5.29	8000	Target date is 15-Sep-2019	20000	15934.3		
<b>Other sub-station works-400 kv</b>																
1	<b>Renovation and Up gradation of Protection systems</b> of 220kV substations(11 Nos) & 400kV Sub-stations(1 No) in Tumakuru Transmission Zone	BESCOM	Tumakuru	Tumakuru			1505.5	2015	2019-20	700.6	406.0	Works under progress. Delay due to slow progress by the agency and line clear issues.	398.9			
<b>Sub-station works-220 kv</b>																
1	<b>Brindavan alloys:</b> Establishing 220/66/11kV GIS Sub-station along with construction of 220kV DC line for a distance of 0.52 kms	BESCOM	Bengaluru	Bengaluru Urban			10570.2	2017	2019-20	0.0	1500	Target date is 29-May-2019	7999.2	1071.1		
2	<b>Kumbalgodu:</b> Establishing 2x150MVA, 220/66/11 kV sub-sation at Kumbalgodu with 220kv 1200sqmm UG Cable between 400/220kv Bidadi and Vrishabhavathi Valley	BESCOM	Bengaluru	Bengaluru Urban			48981.5	2018	2019-20	0.0	10000	Target date is 14-Sep-2019	20087	18894		
3	<b>Channapatna:</b> Establishing 1x100 MVA, 220/66/11kV Sub-station (220kV- Partial Hybrid/ Partial AIS, 66kV AIS) in the premises of existing 66/11kV Sub station Channapatna , Ramanagara District.	BESCOM	Bengaluru	Ramanagara			8910.9	2018	2019-20	0.0	4000	Target date is 15-Sep-2019	3437.6	1473.3		
4	<b>T.Gollahalli (Thimmasandra)</b> Establishing 2x100MVA, 220/66/11kV and 1x12.5MVA 66/11kV Station with associated lines for a distance of 220kV 27.269 Kms & 66kV (5.828+10.93+12.28)Kms	BESCOM	Bengaluru	Kolar			9579.2	2016	2019-20	1917.8	4500	ROW issues for constructing transmission line	3000.0	161.5		



Ongoing works														Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19					
5	<b>Benikere (Channagiri):</b> Establishing 2x100MVA, 220/66kV Station with associated 220kV line for a distance of 47.43Kms	BESCOM	Tumakuru	Davanagere			9764.0	2017	2019-20	4278.6	5000	ROW issues for constructing transmission line	485.4			
6	<b>Hosadurga:</b> Establishing 2x100MVA, 220/66 KV S/s with associated 220kV & 66kV lines	BESCOM	Tumakuru	Chitradurga			10034.8	2018	2019-20	0.0	4000	Target date is 14-Sep-2019	5024.3	1010.4		
7	<b>220kV Shivanasamudra:</b> Establishing 2x100 MVA, 220/66kV Station with associated lines	CESC	Mysuru	Mandya			9653.7	2018	2019-20	0.0	5000	Target date is 14-Jun-2019	4000.0	653.7		
8	<b>Kudligi:</b> Establishing 2x100MVA, 220/66/11kV & 1x12.5MVA, 66/11kV Station at Kudligi (Badeladaku) along with associated lines & TB's for a distance of (220kV 32.63Kms & 66kV M/C 5.36Kms)	GESCOM	Kalaburagi	Bellary			4603.7	2012	2019-20	2475.7	1000	Slow progress by agency	1000.0	128.0		
9	<b>Koppal :</b> Establishing 2x100MVA, 220/110kV and 1x10MVA, 110/11kV Station at Koppal (Halavarthi) along with associated lines & TB's. 11.06 (11KM-110KV&0.06KM-220KV)	GESCOM	Kalaburagi	Koppal			2997.9	2012	2019-20	778.2	1000	Work short closed on 12-Sep-2014. Rewarded on 23-Jan-2018. Delay due to ROW issues for constructing transmission line.	1219.7			
10	<b>Ramasamudra:</b> Establishing 220/110kV Sub Station with associated 220kV and 110kV lines	GESCOM	Kalaburagi	Yadgir			6284.1	2018	2019-20	0.0	1000	Target date is 14-Jun-2019	2500.0	2000.0	784.1	
11	<b>Mughalkod:</b> Establishing 2x100MVA, 220/110kV & 1x10MVA, 110/11kV Station with associated 220kV & 110kV lines	HESCOM	Bagalkote	Belgaum			7249.0	2018	2019-20	0.0	1	Tendered on 07-Dec-2018	3500.0	3748.0		
<b>Transmission line works-220 kV</b>																
1	<b>Somanahally to Kolar via Malur:</b> Construction of 220kV DC line (balanceworks).	BESCOM	Bengaluru	Bengaluru Rural			2739.1	2006	2019-20	3381.4	500	Work terminated on 22.03.17 by CEE TZ. Rewarded. Work commenced on 6.3.2018. ROW issues for constructing transmission line	500.0			
2	<b>Tallak:</b> Construction of Balance 220kV DC line from LILO Point of 220kV Hiriyur-Chitradurga to 400/220kV PGCIL Hiriyur station for a distance of 20.90 kms	BESCOM	Tumakuru	Chitradurga			6394.5	2009	2019-20	5718.6	10	ROW issues for constructing transmission line	500.0	166.0		
3	<b>Shanthigrama:</b> Construction of 1) 2 Nos of 220kV DC lines from 400KV PGCIL Station to LILO the existing Shimoga-Mysore 220KV DC M1& M2 lines near Melgodu limits-7.14 Kms 2) 220KV DC line from Shanthigrama Station to existing B4 line near Hedanahalli limits-7.76 Kms.	CESC	Hassana	Hassana			1122.1	2009	2019-20	767.2	10	1) Commissioned on 24-Jun-2010. 2) Work is short closed, Tender Invited for balance portion of work on 22-Nov-2018. Delay due to ROW issues	300.0	44.9		

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
4	Kudagi to Vajaramatti: Construction of 220KV DC Line from proposed Kudagi 400KV STPP to 220KV Sub-station Vajramatti for a distance of 79.42Kms	HESCOM	Bagalkote	Bijapur/ Bagakot			5888.7	2015	2019-20	2857.8	2500	Local ROW issues for constructing transmission line	530.9		
5	<b>Construction of 220KV link lines:</b> Hiriyur PGCIL to Hiriyur: Construction of 220kv SC line on DC towers for a length of 15.168 Kms from existing 400/220KV PGCIL station at Beerenahalli( Hiriyur) to existing 220/66/11KV Hiriyur S/s in existing Corridor of 220KV S/C line from Hoysala Katte to 220/66/11 KV Station Hiriyur(Partly in new Corridor i.e. from PGCIL point to link 220KV S/C line from Hoysala Katte to 220/66/11 KV SRS at Hiriyur) including re-arrangement of existing 220KV lines near Beerenahalli 400KV Station & dismantling of existing 220KV line Tower.	BESCOM	Tumakuru	Chitradurga			5572.7	2018	2019-20	0.0	5000	ROW issues for constructing transmission line	557.3	15.4	
<b>Augmentation works-220 kV</b>															
1	Davanagere: Replacing 2x60MVA, 220/66kV by 2x100MVA, 220/66kV transformers	BESCOM	Tumakuru	Davanagere			1298.4	2018	2019-20	65.5	100	1st 100MVA commissioned on 03-Feb-2011. work short closed. Tendered for balance works. 2nd 100MVA transformer allotted on 25-Jun-2018.	700.0	432.9	
2	Ambevadi: Replacing 2x55MVA, 220/110kV by 2x100MVA, 220/110kV Transformer with R&M works.	HESCOM	Bagalkote	North Canara			1466.4	2011	2019-20	847.6	1	Transformer-2 commissioned on 18-Aug-2014 and transformer -1 commissioned on 17-Jul-2015. Slow progress by the agency. Work short closed on 10-Jun-2016.	100.0	517.7	
3	B Bagewadi: 1x100MVA Transformer 220/110KV for arranging the power supply to the Chimmalaji LIS.	HESCOM	Bagalkote	Bijapur			847.0	2017	2019-20	0.0	580	Work under progress. Delay due to slow progress agency.	267.0		

Ongoing works														Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19					
4	<b>Somanahalli:</b> Replacing 2x100MVA, 220/66/11kV Power Transformer by 2x150MVA at 220/66/11kV R/s Somanahalli, Bengaluru.	BESCOM	Bengaluru	Bengaluru Urban			1872.1	2018	2019-20	0.0	200	Target date is 04-Nov-2019	1500.0	172.1		
5	<b>Gadag:</b> Providing additional 4th 1x100MVA, 220/110kV Transformer	HESCOM	Bagalkote	Gadag			1728.8	2018	2019-20	0.0	500	Tendered on 05-Sep-2018	1000.0	228.8		
<b>Other works-220 kV</b>																
1	<b>Peenya :</b> R & M works at Peenya 220/66kV Station.	BESCOM	Bengaluru	Bengaluru Urban			4093.4	2013	2019-20	2450.2	1000	Delay due line clear issues	500.0	143.2		
2	<b>SRS Hoody :</b> R & M Works at SRS Hoody 220/66kV Station	BESCOM	Bengaluru	Bengaluru Urban			2452.9	2013	2019-20	1443.5	500	Delay due line clear issues	250.0	259.4		
<b>Sub-station works-110 kV</b>																
1	<b>Jeppu:</b> Establishing 1x20MVA, 110/33kV & 2x10MVA, 110/11kV Sub-Station with LLO of Kulashekara - Konaje line for a distance of 10.00 Kms.	MESCOM	Hassana	Dakshina Kannada			1337.8	2008	2019-20	1007.2	10	ROW issues for constructing transmission line	224.5	96.2		
2	<b>Mulky:</b> Up-grading 2x5MVA, 33/11kV MUSS to 1x10MVA, 110/11kV Sub-Station with SC line from Nandikur for a distance of 11.00 Kms.	MESCOM	Hassana	Dakshina Kannada			741.8	2008	2019-20	408.1	50	ROW issues for constructing transmission line	198.5	85.1		
3	<b>Madavu:</b> Establishing 2x20MVA, 110/33-11kV & 1x10MVA, 110/11kV Sub-Station with 110kV line from Puttur 220kV Station for a distance of 27.00 Kms.	MESCOM	Hassana	Dakshina Kannada			2550.8	Stn:2018 Line:2010	2019-20	1229.0	1000	Forest clearance for station land. ROW issues for constructing transmission line	321.8			
4	<b>Konandur:</b> Establishing 1x10MVA, 110/11kV Sub-Station with associated 110kV V3 line for a distance of 11.83 Kms.	MESCOM	Hassana	Shimoga			1027.5	Stn:2006 Line:2018	2019-20	864.6	350	Forest clearance for constructing transmission line. Line work reawarded. Station almost completed.				
5	<b>Kortigere:</b> Establishing 1x10MVA, 110/11kV Sub-Station at Koratigere in Shikaripura Tq, Shivamogga Dist with construction of 110kV SC line on DC Towers from 110kV Balligavi (Shiralkoppa)- Bharangi line near Bilki Village limits to the proposed S/S at Koratigere for a dist of 7.139Kms	MESCOM	Hassana	Shimoga			683.8	2018	2019-20	0.0	300	ROW issues for constructing transmission line	383.8			
6	<b>Yemmedoddi:</b> Establishing 2x10MVA, 110/11kV Sub-Station at Yemmedoddi in Kadur Tq, Chikkamagalur Dist with construction of 110kV SC tap line on DC towers from existing 110kV Kadur-Nagenahalli SC line to the proposed 110/11kV Yemmedoddi S/S for a dist of 7.731Kms	MESCOM	Hassana	Chikkamagaluru			1104.3	2018	2019-20	0.0	600	ROW issues for constructing transmission line	353.0	151.3		

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
7	Koganolli Up-gradation 33/11kV S/s to 2x10MVA, 110/11kV Sub-Station with associated line for a distance of 17.192Kms	HESCOM	Bagalkote	Belgaum			1460.5	2018	2019-20	52.3	800	Local ROW issues for constructing transmission line	500.0	108.2	
8	G.Hosakoti: Establishing 1x10MVA, 110/11kV Sub-Station with associated line.	HESCOM	Bagalkote	Belgaum			943.1	2018	2019-20	0.0	551	Target date is 14-Feb-2019	391.7		
9	Inchageri: Establishing 1x10MVA, 110/11kV Sub-Station with associated line & TB for a distance of 19.759 Kms	HESCOM	Bagalkote	Bijapur			1192.6	2018	2019-20	0.0	600	Target date is 15-Feb-2019	500.0	92.6	
10	Thavaragera: Establishing 1x10MVA, 110/11kV and 1x20MVA, 110/33kV Sub-Station with associated 110kV line for a distance of 26.495 Kms.	GESCOM	Kalaburagi	Koppal			2018.4	2017	2019-20	1345.8	766	Delay due to ROW issues for constructing transmission line			
11	Mangalore: Up-gradation of 33/11kV MUSS to 2X10 MVA, 110/11kV Sub-Station with associated lines for a distance of 7.426 Kms.	GESCOM	Kalaburagi	Koppal			1048.2	2018	2019-20	0.0	100	Target date is 29-Mar-2019	845.6	102.6	
<b>Transmission line works-110 kV</b>															
1	Kavoor - Kulashekar : Construction of 110kV DC line from Kavoor to Kulashekar in the existing 33kV line corridor for a distance of 8.50 Kms and along with TBs	MESCOM	Hassana	Dakshina Kannada			917.4	2007	2019-20	475.5	10	ROW issues for constructing transmission line	100.0	331.9	
2	Puttur: Construction of 110-110kV MC and 110kV DC lines from loc no.28 (Kabaka Railway Crossing limits) to the 110/33/11kV Puttur S/S for a dist of 4.5Kms & Construction of 2nos of 110kV TBs at 110/33/11kV Puttur S/S for a distance of 4.5 Kms	MESCOM	Hassana	Dakshina Kannada			439.5	2010	2019-20	199.5	80	ROW issues for constructing transmission line	100.0	60.0	
3	Kavoor-Baikampady: Strengthening of 110kV-Kavoor-Baikampady line converting SC line by DC line with TB at Kavoor for a distance of 3.885 Kms	MESCOM	Hassana	Dakshina Kannada			358.1	2010	2019-20	171.8	10	ROW issues for constructing transmission line	100.0	76.3	
4	Brahmavara-Nittur: Stringing 2nd circuit in the existing 110kV Brahmavara-Nittur line and creating 110kV TB at Brahmavara & Nittur Sub-Stations.	MESCOM	Hassana	Udupi			169.6	2017	2019-20	15.8	90	ROW issues for constructing transmission line	63.8		
5	Guledgud - Ilkal: Construction of 110kV S.C. link line on D/C towers from 110kV Sub-Station Guledgudda to 110kV Sub-Station Ilkal for a distance of 34.575 Kms.	HESCOM	Bagalkote	Bagalkote			619.7	2011	2019-20	159.3	1	Work short closed on 02-Aug-2017. Balance works to be tendered.	50.0	409.4	

Ongoing works														Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19					
6	<b>Chincholi-Mannekalii-Sedam:</b> i) Construction of 110kV DC link line between 110kV Chincholi and 110kV Manna-E-Khelly Sub-Stations 49.87Kms. ii) Stringing Second circuit on existing DC towers from <b>220kV Sedam Station to 110kV Chincholi Sub-Station</b> for a distance of 32kMs.	GESCOM	Kalaburagi	Kalaburagi			925.0	2011	2019-20	146.4	729	Work short closed on 16-Sep-2016. Rewarded on 26-Mar-18, work under progress. Delay due to ROW issues	50.0			
7	<b>Nehru nagar-6 Pole Structure:</b> conversion of 110 kV Nehrunagar-6 pole structure SC line constructed on 110 kV SC towers(MS towers)to 110 kV SC line on DC towers for a distance of 2.3 kms	HESCOM	Bagalkote	Belgaum			82.19		2019-20	0.0	83	To be tendered				
8	<b>Nidagundi:</b> Shifting and Re-routing of 110 kV line from Loc 125-145 of Bagalkot-B.Bagewadi DC line in TLM section B.Bagewadi jurisdiction in Vijayapura District	HESCOM	Bagalkote	Vijayapura			583.23		2019-20	0.0	10	To be tendered	50	523.23		
9	<b>Jewargi Sub-station:</b> Construction of 110kV LILO line from existing Shahabad-Shahapur line to 110/33-11kV Jewargi sub-station in the existing corridor for a distance of 0.86Kms	GESCOM	Kalaburagi	Kalaburagi			128.83		2019-20	0.0	1	To be tendered	50	77.83		
<b>Augmentation works-110 kV</b>																
1	<b>Halukurke:</b> Providing Additional 1x10 MVA, 110/11 kV Power Transformer at 110/11kV Station.	BESCOM	Tumakuru	Tumakuru			308.5	2017	2019-20	63.3	75	Released transformer allotted and commissioned on 16-May-2018	170.3			
2	<b>110KV S/S Banahatti:</b> Replacement of 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer	HESCOM	Bagalkote	Bagalkote			58.6	2018	2019-20	0.0	258	Transformer allotted on 27-Aug-2018 and commissioned on 01-Nov-2018				
3	<b>Gubbi :</b> Replacing 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer.	BESCOM	Tumakuru	Tumakuru			201.6	2018	2019-20	0.0	200	Transformer allotted on 21-Jun-2018 and commissioned on 08-Aug-2018	1.6			
4	<b>Kallusadarahally :</b> Providing additional 1x10 MVA, 110/11 kV power transformer at 110/11 kV Kallusadarahally Sub station in Arasikere Taluk, Hassan District.	CESC	Hassana	Hassana			271.3	2018	2019-20	0.0	150	Transformer to be allotted	121.3			
5	<b>Saethur:</b> Providing additional 1X10 MVA 110/11kV Transformer.	MESCOM	Hassana	Dakshina Kannada			285.8	2018	2019-20	0.0	290	Transformer allotted on 05-Dec-2018, work under progress.				
6	<b>Netlamudnur:</b> Providing additional 1x20 MVA, 110/33 kV transformer at 220 kV Netlamudnur station, in Bantwal Taluk, DK District	MESCOM	Hassana	Dakshina Kannada			335.9		2019-20	0.0	250	To be tendered	85.9			
7	<b>Bantwala:</b> Providing additional 1x20 MVA, 110/33 kV transformer at 110 kV Bantwal station, in Bantwal Taluk, DK District.	MESCOM	Hassana	Dakshina Kannada			338.1	2018	2019-20	0.0	340	Tendered. Transformer to be allotted				

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
8	<b>Gurupura:</b> Replacement of 1x10MVA, 110/11kV by 1x20MVA, 110/11kV Transformer's at 110/11kV Gurupura S/s	MESCOM	Hassana	Dakshina Kannada			249.5	2018	2019-20	0.0	250	Transformer to be allotted			
9	<b>Madhuvana:</b> Providing additional 1x20 MVA, 110/11kV Power Transformer at 110/11kV Madhuvana Sub-station in Udupi Taluk and District.	MESCOM	Hassana	Udupi			256.4	2018	2019-20	0.0	260	Transformer to be allotted			
10	<b>Hiriyadka:</b> Replacement of existing 1x10MVA, 110/33kV Power Transformer by 20MVA, 110/33kV Power Transformer at 110/33/11kV Hiriyadka Sub-station in Udupi Taluk & Dist.	MESCOM	Hassana	Udupi			212.1	2018	2019-20	0.0	50	Transformer to be allotted	162.1		
11	<b>Balligavi (Shiralkoppa):</b> Providing 1X20MVA, 110/11kV Spare Transformer at 220kV Balligavi (Shiralkoppa) Station.	MESCOM	Hassana	Shimoga			376.6		2019-20	0.0	50	To be tendered	326.6		
12	<b>Thogarsi:</b> Providing additional 1 x 10MVA, 110/11kV Power Transformer	MESCOM	Hassana	Shimoga			289.7	2018	2019-20	0.0	150	Tendered. Transformer to be allotted	139.7		
13	<b>Kumsi:</b> Replacement of 2nd 1x 10MVA 110/11kV Power transformer by 1 x 20 MVA, 110/11kV power transformer at existing 110/11kV Kumsi S/s in Shimogga Taluk	MESCOM	Hassana	Shimoga			312.1	2018	2019-20	0.0	50	Tendered. Transformer to be allotted	262.1		
14	<b>Hangal:</b> Providing additional 1X10MVA, 110/11kV Power Transformer at 110kV S/s Hangal	HESCOM	Bagalkote	Haveri			83.7	2018	2019-20	0.0	50	Work under progress Transformer to be allotted.	33.7		
15	<b>220KV Station, Indi:</b> Providing Additional 1x10MVA, 110/11kV transformer	HESCOM	Bagalkote	Bijapur			53.2	2018	2019-20	0.0	150	Tendered. Transformer to be allotted			
16	<b>Zalaki:</b> Replacement of 10MVA, 110/11kV by 20MVA, 110/11kV Transformer	HESCOM	Bagalkote	Bijapur			256.1	2018	2019-20	0.0	10	Tendered. Transformer to be allotted	246.1		

Ongoing works													Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
17	Chadachan: Replacement of 1x10MVA, 110/11kV Transformer by 1x20, 110/11kV Transformer	HESCOM	Bagalkote	Bijapur			254.5		2019-20	0.0	10	To be tendered	244.5		
18	Bevoor : Providing additional 1 x 10 MVA, 110/11 kV Power Transformer at Bevoor S/s	GESCOM	Kalaburagi	Koppal			243.7	2018	2019-20	0.0	50	Tendered. Transformer to be allotted	100.0	93.7	
19	Ganadal : Providing additional 1 x 10 MVA, 110/11 kV Power Transformer at Ganadal S/s	GESCOM	Kalaburagi	Koppal			241.5	2018	2019-20	0.0	50	Tendered. Transformer to be allotted	100.0	91.5	
20	Koppal: Providing spare 20 MVA, 110/33/11 kV Power Transformer at 110 kV S/S Koppal	GESCOM	Kalaburagi	Koppal			200.0		2019-20	0.0	50	To be tendered	100.0	50.0	
21	Enhancement of 10MVA, 110/33kV power Transformer NGEF Make) by 20MVA, 110/33 KV POWER Transformer at 110/33/11kV MUSS Betagera in Koppal Tq.	GESCOM	Kalaburagi	Koppal			200.5	2018	2019-20	0.0	100	Transformer to be allotted	100.5		
22	Venkatgiri : Enhancement of 10 MVA, 110/11kV Power Transformer by 20 MVA 110/11kV Power Transformer at 110/11kV S/s Venkatgiri.	GESCOM	Kalaburagi	Koppal			267.5		2019-20	0.0	50	To be tendered	100.0	117.5	
23	Enhancement of 10MVA, 110/11kV power Transformer NGEF Make) by 20MVA, 110/11kV POWER Transformer at 110/33kV MUSS Koppal in Koppal Tq, District.	GESCOM	Kalaburagi	Koppal			175.0		2019-20	0.0	50	To be tendered	100.0	25.0	
24	110KV Sriramnagar: Replacement of 1X10 MVA, 110/11kV by 1x20MVA 110/11kV Power Transformer at 110/11kV Sriram Nagar S/s.	GESCOM	Kalaburagi	Koppal			265.8		2019-20	0.0	50	DPR to be approved	100.0	115.8	
<b>Sub-station works-66 kV</b>															
1	Samanduru :a)Establishing 2x8MVA, 66/11kV Sub-Station.b) laying of 3cx300 Sqmm UG Cable from Anekal S/s to Samanduru s/s for a Route length of 8.64 Kms.	BESCOM	Bengaluru	Bengaluru Urban			2939.0	2014	2019-20	523.0	500	ROW issues for constructing transmission line. Alternate proposal of running UG Cable tendered.	1500.0	416.0	
2	Kumbarannahalli : Establishing 2X12.5MVA, 66/11kV Power Transformer at Kumbarannahalli	BESCOM	Bengaluru	Bengaluru Urban			694.6	2017	2019-20	0.0	1500	Target date is 07-Feb-2019			
3	Mandur: Establishing 1x12.5MVA, 66/11kV Sub-Station with 66kV D/C line from Budigere for a distance of 9.00 Km.	BESCOM	Bengaluru	Bengaluru Rural			615.1	2007	2019-20	439.7	10	ROW issues for constructing transmission line. Work terminated on 23-01.2017. Balance works to be tendered			
4	Sondekoppa: Establishing 2x8MVA, 66/11kV Sub-Station with 66kV tap from Dobbaspeta - Nelamangala SBT line for a distance of 12.50 Kms.	BESCOM	Bengaluru	Bengaluru Rural			824.3	2007	2019-20	598.6	124	ROW issues for constructing transmission line.	101.7		

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
5	Uragahalli: Establishing 2x8MVA, 66/11kV Sub-Station with associated line.	BESCOM	Bengaluru	Ramanagara			1193.1	2018	2019-20	0.0	400	Target date is 19-Dec-2018	555.2	237.9	
6	Kunur: Establishing 1x12.5MVA, 66/11kV S/s at Kunur	BESCOM	Bengaluru	Ramanagara			703.8	2018	2019-20	0.0	250	Target date is 20-Dec-2018	317.6	136.1	
7	Malladihalli: Establishing 2x8MVA, 66/11kV Sub-Station with associated line for a distance of 11.467 Kms.	BESCOM	Tumakuru	Chitradurga			702.8	2013	2019-20	582.4	150	ROW issues for constructing transmission line.			
8	Shettihalli: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 2.34 Kms.	CESC	Hassana	Hassana			416.5	2010	2019-20	278.6	50	ROW issues for constructing transmission line.	87.9		
9	Chandalli (Madapura) Village: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 5.668Kms	CESC	Mysuru	Mysuru			787.9	2018	2019-20	0.0	400	ROW issues for constructing transmission line. Case filed at DC court Mysuru.	387.9		
10	Jannur: Establishing 1x8MVA, 66/11kV Sub-Station with associated line for a distance of 8.63Kms	CESC	Mysuru	Chamarajanagara			819.7	2018	2019-20	0.0	400	Target date is 19-Dec-2018	419.7		
11	Channarayapattana: Establishing 2x8MVA, 66/11kV Sub-Station with associated line.	BESCOM	Bengaluru	Bengaluru Rural			854.57	2018	2019-20	0.0	710	Target date is 29-Mar-2019	144.6		
12	Sasalu(Sriramanahalli): Establishing 1x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	Bengaluru Rural			1118	2018	2019-20	0.0	10	Tendered on 26-Jul-2018	559.0	384.3	164.7
13	Sathanur(Achalu): Establishing 2x8MVA, 66/11kV Sub-Station with associated line	BESCOM	Bengaluru	Ramanagara			780.02	2018	2019-20	0.0	100	Target date is 30-Jul-2019	390.0	290.0	
14	Shivanahalli: Establishing. 1x8 MVA, 66/11kV S/s and associated line	BESCOM	Bengaluru	Ramanagara			601.87	2018	2019-20	0.0	100	Target date is 30-Jul-2019	300.9	200.9	
15	Vyasarajapura: Establishing 1x8 MVA 66/11kV Sub-Station with associated line for a distance of 3.498Kms	CESC	Mysuru	Mysuru			593.88	2018	2019-20	0.0	10	Target date is 04-Aug-2019	475.1	108.8	
16	Gargeshwari:Establishing 1x8MVA, 66/11kV Sub-station with associated line for a distance of 0.543Kms	CESC	Mysuru	Mysuru			780.89	2018	2019-20	0.0	50	Tendered on 24-May-2018	624.7	106.2	
17	Kadukothanahalli: Establishing 1x 8MVA, 66/11 KV Sub-Station with associated line for a distance of 0.08Kms	CESC	Mysuru	Mandya			507.3	2018	2019-20	0.0	200	Target date is 03-Apr-2019	316.7		
18	Hariyaldamma Temple: Establishing 1 x 8MVA, 66/11 KV Sub-Station with associated line for a distance of 8.591Kms	CESC	Mysuru	Mandya			770.09	2018	2019-20	0.0	300	Target date is 03-Apr-2019	385.0	85.0	
<b>Transmission line works-66 kV</b>															
1	Hebbal-IT: Replacing Coyote ACSr by HTLS Conductor from the existing 66kV line for a distance of 14.334 Kms.	BESCOM	Bengaluru	Bengaluru Urban			1679.1	2012	2019-20	934.5	300	Line commissioned on 25.01.2018 for 3.114Kms from Hebbal to yellarbande. Balance works under progress.	350.0	94.6	



Ongoing works															
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required		
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19		FY20	FY21	FY22
2	<b>BIAL to Vidyanagar:</b> Running 66kV SC 1000Sq mm XPLE copper UG Cable for a route length 9.5 Kms from 220/66/11kV Sub-station to 66/11kV Vidyanagar S/s	BESCOM	Bengaluru	Bengaluru Urban			5947.0	2015	2019-20	4364.2	755	Delay due to ROW issues	800.0	27.8	
3	<b>EPIP &amp; Yerandanahalli:</b> Strengthening of existing 66 kV line between EPIP & Yerandanahalli sub-station by replacing Coyote by Drake ACSR	BESCOM	Bengaluru	Bengaluru Urban			2177.3	2016	2019-20	1014.9	800	Delay due to ROW issues	300.0	62.4	
4	<b>Davanagere to Harapanahalli:</b> Construction of new 66kV SC line on DC towers for a distance of 45.40 kms.	BESCOM	Tumakuru	Davanagere			955.3	2014	2019-20	793.5	50	ROW issues for constructing transmission line.	100.0	11.8	
5	<b>Chikmagalur-Balehonur:</b> Construction of 66kV DC line with coyote ACSR in the existing corridor of 66kV SC line from chikmagalur to Balehonur (43.74 Kms)	MESCOM	Hassana	Chikmagaluru			1800.0	2006	2019-20	273.9	750	Work Short closed and Reawarded on 21-Aug-2018. ROW issues for constructing transmission line.	700.0	76.1	
6	<b>Somanahalli :</b> Replacing 66 kV North and South Strung bus by rigid bus at 220/66/11 kV Somanahalli sub-station	BESCOM	Bengaluru	Bengaluru Urban			657.0	2018	2019-20	0.0	300	To be tendered	357.0		
7	<b>Ranganadoddi Sub-Station:</b> Providing 66kV LILO arrangement to 66/11kV Sub-Station for a distance of 0.10 kms.	BESCOM	Bengaluru	Ramanagara			41.0		2019-20	0.0	5	To be tendered	36.0		
8	<b>Ramnagara Sub-Stn:</b> Constructing additional 66kV circuit from Bidadi - Bevoor line to provide LILO arrangements for a distance of 0.65 kms.	BESCOM	Bengaluru	Ramanagara			34.1	2018	2019-20	0.0	10	Tender finalized LOI to be issued.	24.1		
9	<b>Mosalehosahally:</b> Providing LILO arrangements at 66/11kV Mosalehosahally Sub-station in Hassana Taluk & District by constructing 66kV DC line for a distance of 130 meters from new SMT-1 line.	CESC	Hassana	Hassana			13.2		2019-20	0.0	13	To be tendered			
10	Establishing 1X12.5 MVA, 66/11 kV sub-station at <b>Mandur</b> in Bengaluru East Taluk, Bengaluru Urban District and construction of 66 kV SC line on DC towers from the proposed 66/11 kV Budigere sub-station and linking the line to the tower No. 39 of proposed 66 kV SC Hoskote-Mandur line for a distance of 9.0 Kms and construction of 66 kV TB at Budigere Sub-station for terminating the proposed 66 kV Hosakote – Mandur line - <b>Alternative routes by constructing 66 kV UG cable.</b>	BESCOM	Bengaluru	Bangalore Urban			5400.0		2019-20	0.0	0		1000.0	4400	

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
<b>Augmentation works-66 kV</b>															
1	Tavarekere: Replacing 2x8MVA, 66/11kV by 2x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Urban			432.9	2015	2019-20	178.8	2	2nd transformer to be allotted.	252.0		
2	Megalapura : Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	CESC	Mysuru	Mysuru			159.7	2018	2019-20	0.0	125	Transformer allotted on 24-Apr-2018 and commissioned on 07-Jun-2018	34.7		
3	Rajarajeshwarinagar: Replacement of 2X20MVA by 2X31.5MVA transformer at 66/11kV Rajarajeshwarinagar S/s	BESCOM	Bengaluru	Bengaluru Urban			700.0		2019-20	0.0	3	To be tendered	697.0		
4	Kumbalgodu: Replacement of 1x12.5MVA by 1x31.5MVA 66/11kV Transformer at 66/11kV Kumbalgodu Substation	BESCOM	Bengaluru	Bengaluru Urban			276.4		2019-20	0.0	3	To be tendered	273.4		
5	Prestige Shanthinikethan: Replacing 1X20MVA by 1X31.5MVA 66/11kV Power transformer at 66/11kV Prestige Shanthinikethan substation .	BESCOM	Bengaluru	Bengaluru Urban			248.9		2019-20	0.0	200	To be tendered	48.9		
6	Army Welfare Housing Organisation: Providing Additional 1X31.5MVA, 66/11kV Power Transformer	BESCOM	Bengaluru	Bengaluru Urban			400.0	2018	2019-20	0.0	80	Transformer to be allotted	320.0		
7	Attibele: Replacement of 1x20 MVA, 66/11 kV transformer by 1x31.5MVA 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Urban			319.1		2019-20	0.0	190	To be tendered	129.1		
8	Peenya: Augmentation of 2x20MVA, 66/11kV power transformer no. II & III by 2x31.5MVA, 66/11kV power transformer at SRS Peenya 220/66/11kV Substation	BESCOM	Bengaluru	Bengaluru Urban			597.3		2019-20	0.0	200	To be tendered	397.3		
9	IISC: Replacing of 2x20MVA, 66/11kV power transformer by 2x31.5MVA power transformer	BESCOM	Bengaluru	Bengaluru Urban			676.7		2019-20	0.0	85	To be tendered	591.7		
10	Byadarahally: Replacement of 1x20MVA, 66/11kV Power Transformer by 1x31.5MVA, 66/11kV power transformer	BESCOM	Bengaluru	Bengaluru Urban			351.0		2019-20	0.0	85	To be tendered	266.0		
11	Brindavaan: Replacement of 2x20MVA, 66/11kV Power Transformer II & III by 2x31.5MVA, 66/11kV power transformer	BESCOM	Bengaluru	Bengaluru Urban			635.3		2019-20	0.0	200	To be tendered	435.3		
12	Naganathapura : Replacing 2X20MVA by 2X31.5MVA 66/11kV Power transformer	BESCOM	Bengaluru	Bengaluru Urban			500.0		2019-20	0.0	200	To be tendered	300.0		
13	Adugodi: Replacing 3X20MVA by 3X31.5MVA 66/11kV Power transformer	BESCOM	Bengaluru	Bengaluru Urban			750.0		2019-20	0.0	200	To be tendered	550.0		
14	Widia S/s: Providing addnl 1X20MVA, 66/11kV Power Transformer.	BESCOM	Bengaluru	Bengaluru Urban			235.0	2018	2019-20	0.0	5	To be tendered	230.0		
15	Budigere: Replacing 1x8MVA, 66/11kV by 1x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Rural			224.5		2019-20	1.2	20	Transformer allotted on 25-Sep-2018 and commissioned on 17-nov-2018	203.3		
16	66/11KV S/s Volvo: Replacing of 1X6.3 MVA by 1X12.5 MVA Transformer at 66/11KV S/S Volvo	BESCOM	Bengaluru	Bengaluru Rural			139.4		2019-20	0.0	120	To be tendered	19.4		

Ongoing works													Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
17	Sulibete : Replacing of 2 x 12.5MVA Transformers by 2x 20MVA transformers	BESCOM	Bengaluru	Bengaluru Rural			206.9		2019-20	0.0	6	To be tendered	200.9		
18	Nanadagudi : Replacing 2 x12.5MVA Transformers by 2x 20 MVA Transformers	BESCOM	Bengaluru	Bengaluru Rural			397.4		2019-20	0.0	6	To be tendered	391.4		
19	CBPura(I/A): Replacing 1x12.5MVA NGEF make Tr-1, 66/11kV by 1x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Bengaluru Rural			202.6		2019-20	0.0	10	To be tendered	192.6		
20	Magadi: Replacing 1x12.5MVA by 1x20MVA, 66/11kV Pwer Transformer at 66/11kV Magadi	BESCOM	Bengaluru	Ramanagara			176.0		2019-20	0.0	5	To be tendered	171.0		
21	Gudemaranahalli: Replacing 2x8MVA by 2x20MVA 66/11kV Power Transformer	BESCOM	Bengaluru	Ramanagara			394.7		2019-20	0.0	3	To be tendered	391.7		
22	Bidadi:Providing additional 1x20 MVA Power Transformer at 220/66/11 kV Bidadi Sub-station	BESCOM	Bengaluru	Ramanagara			359.0	2018	2019-20	0.0	50	Tendered	309.0		
23	Hukunda:Providing additional 1x8MVA, 66/11kV Power Transformer at 66/11kV Hukunda Sub-station.	BESCOM	Bengaluru	Ramanagara			225.2	2018	2019-20	0.0	5	Tendered	220.2		
24	V.G.Doddi:Providing additional 1x8MVA, 66/11kV Power Transformer at 66/11kV V.G.Doddi Sub-station.	BESCOM	Bengaluru	Ramanagara			225.3	2018	2019-20	0.0	5	Tendered	220.3		
25	Replacement of second 12.5 MVA, by 20 MVA, Power Transformer at 66/11kV Ranganadoddi S/s	BESCOM	Bengaluru	Ramanagara			158.3		2019-20	0.0	3	To be tendered	155.3		
26	Dalasanur: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			121.6		2019-20	0.0	5	To be tendered	116.6		
27	S.M.Mangala: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			121.6		2019-20	0.0	3	To be tendered	118.6		
28	Masti: Replacing 2nd 2x12.5MVA, 66/11kV by 2x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			35.0		2019-20	134.2	3	To be tendered			
29	Kyalanur: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			117.0	2018	2019-20	0.0	3	Transformer allotted on 26-Sep-2018 and commissioned on 17-Nov-2018	114.0		
30	Anderdsonpet : Replacing 2x8MVA, 66/11kV by 2x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			269.6		2019-20	0.0	3	To be tendered	266.6		
31	Srinivasapura: Replacing 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			205.1		2019-20	0.0	3	To be tendered	202.1		
32	Addagal: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			142.2		2019-20	0.0	120	To be tendered	22.2		
33	Thayalur: Replacing 1x6.3MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			141.5		2019-20	0.0	3	To be tendered	138.5		

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19				
34	Malasandra: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	Kolar			140.9		2019-20	0.0	3	To be tendered	137.9		
35	M.G.Halli: Replacing 1x8MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	C.B.Pura			110.5		2019-20	0.0	3	To be tendered	107.5		
36	Cheemangala: Replacing 1x6.3MVA, 66/11kV by 1x12.5MVA, 66/11kV Transformer	BESCOM	Bengaluru	C.B.Pura			127.4		2019-20	0.4	5	To be tendered	121.9		
37	Irragampalli: Replacing 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV transformer	BESCOM	Bengaluru	C.B.Pura			204.7	2018	2019-20	0.0	3	Commissioned on 10-Dec-2018 (Repaired transformer allotted)	201.7		
38	Talagavara: Replacing second 1x12.5MVA, 66/11kV by 1x20MVA, 66/11kV transformer	BESCOM	Bengaluru	C.B.Pura			204.7		2019-20	0.0	3	To be tendered	201.7		
39	Cheemangala: Replacing second 1x6.3MVA, 66/11kV by 1x12.5MVA, 66/11kV transformer	BESCOM	Bengaluru	C.B.Pura			142.3		2019-20	0.0	3	To be tendered	139.3		
40	Replacing of 2x8 MVA by 2x12.5 MVA at Manchenahalli	BESCOM	Bengaluru	C.B.Pura			272.1		2019-20	0.0	3	1st Transformer commissioned on 17-Mar-17.	269.1		
41	Savalanga: Providing additional 1x8MVA, power Transformer at 66/11kV Savalanga S/S.	BESCOM	Tumakuru	Davanagere			223.5		2019-20	0.0	100	To be tendered	123.5		
42	Pandarahalli: Replacing 2nd 12.5 MVA, 66/11kV by 20MVA, 66/11kV Transformer.	BESCOM	Tumakuru	Chitradurga			203.9		2019-20	0.0	200	To be tendered	3.9		
43	CR Patna: Replacement of 1 X 12.5MVA, 66/11 KV power Transformer by 1 X 20 MVA, 66/11kV Power Transformer at CR Patna S/S	CESC	Hassana	Hassana			155.0		2019-20	135.9	155	Transformer allotted on 04-Dec-2018 and commissioned on 12-Dec-2018			
44	Salagame: Replacement of 2 X 8 MVA, 66/11 KV power Transformer by 2 X 12.5 MVA, 66/11kV Power Transformer at Salagame S/S in Hassana Taluk	CESC	Hassana	Hassana			275.3	2018	2019-20	0.0	150	Transformer to be allotted	125.3		
45	Shanthigrama: Replacement of 2 X 8 MVA, 66/11 KV power Transformer by 2 X 12.5 MVA, 66/11kV Power Transformer at Shanthigrama S/S in Hassana Taluk	CESC	Hassana	Hassana			275.3	2018	2019-20	0.0	150	Transformer allotted on and commissioned on 17-Dec-2018	125.3		
46	Juttanahally: Providing Additional 1x8MVA, 66/11kV Power Transformer at 66/11kV S/s Juttanahally in CR Patna Taluk	CESC	Hassana	Hassana			222.5	2018	2019-20	0.0	150	Tendered. Transformer to be allotted	72.5		
47	Chikkabommenahally: Augmentation of 1 X 8 MVA, 66/11 KV power Transformer by 1 X 12.5 MVA @ Chikkabommenahally S/S in Arkalagud Taluk	CESC	Hassana	Hassana			244.1	2018	2019-20	0.0	244	Transformer to be allotted	0.1		
48	Bychanahally: Providing additional 1x8MVA power transformer @ 66/11kV sub-station Bychanahally, in Arkalagud Taluk, Hassan District.	CESC	Hassana	Hassana			232.1	2018	2019-20	0.0	150	Repaired transformer allotted, work under progress.	82.1		
49	K.Byrapura: Providing additional 1x8MVA, 66/11kV power transformer at K.Byrapura sub-station.	CESC	Hassana	Hassana			209.3	2018	2019-20	0.0	150	Tendered. Transformer to be allotted	59.3		

Ongoing works														Budget required		
Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	FY20	FY21	FY22	
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19					
50	Arehalli :Providing additional 1x8 MVA, 66/11 kV power transformer at 66/11 kV Arehalli Sub station in Belur Taluk, Hassan District.	CESC	Hassana	Hassana			277.3	2018	2019-20	0.0	150	Tendered. Transformer to be allotted	127.3			
51	Tyvarachattalli: Replacement of existing 1x 6.3MVA 66/11KV Power transformer to 1x 12.5 MVA Power transformer at 66/11KV MUSS Tyavarechatnahalli	MESCOM	Hassana	Shimoga			176.1		2019-20	0.0	50	To be tendered	126.1			
52	Mudigere:Replacement of 2x6.3MVA, 66/11kV Power Transformers by 2x12.5MVA, 66/11kV Power Transformer at Mudigere S/s in Mudigere Taluk, Chikkamagaluru District	MESCOM	Hassana	Chikkamagaluru			574.3		2019-20	0.0	50	To be tendered	524.3			
53	Mudigere:Creating 33kV reference by installing 1x8MVA, 66/33kV Transformer at Mudigere S/s in Mudigere Taluk	MESCOM	Hassana	Chikkamagaluru			400.5		2019-20	0.0	5	To be tendered	395.5			
54	Chikkamagaluru: Replacing 2X12.5MVA, 66/11kV Transformer by 2X20MVA, 66/11kV transformer at 66kV Chikkamagaluru Substation.	MESCOM	Hassana	Chikkamagaluru			647.0		2019-20	0.0	150	To be tendered	497.0			
55	T.N.Pura : Repl 2X12.5MVA by 2X20 MVA 66/11kV Transformer	CESC	Mysuru	Mysuru			427.0	2018	2019-20	0.0	175	Transformer to be allotted	252.0			
56	Hullahalli : Replacement of 2 X 8 MVA by 2 X 12.5 MVA, 66/11kV Transformer.	CESC	Mysuru	Mysuru			285.2	2018	2019-20	98.7	125	1st Transformer Commissioned on 27-Mar-2018. 2nd transformer to be allotted.	160.2			

Sl.No	Name of the work	Beneficiary ESCOMs	Zone	District	As per DPR/DWA			As per Actuals				Reason for delay in commencement if any	Budget required		
					Year of commencement	Year of completion	Cost incurred	Year of commencement	Schedule Year of completion	Cost incurred up to 31/03/18	Budget for 2018-19		FY20	FY21	FY22
<b>Other works-66 kV</b>															
1	<b>66/11KV S/S Ujjini:</b> Construction of new control room building along with shifting of equipments from existing control to the proposed control with providing protection for the existing equipment . Proiding LLO arrangement for 66KV incoming Line (66KV Kottur-Kudigi-Ujjini) along with Constuction of TB at Ujjini.	GESCOM	Kalaburagi	Bellary			131.5		2019-20	0.0	5	To be tendered	100.0	26.5	
2	<b>Providing 12.1kV 2.9MVAR Capacitor Banks and</b> Other allied equipments to 57 Nos of existing KPTCL Sub-station in the jurisdiction of Tumakuru Transmission Zone	BESCOM	Tumakuru	Tumakuru			1600	2015	2019-20	605.2	541	Works under progress. Delay due to slow progress by the agency and line clear issues. Delay in siupply of 11kV Switchgears by MEI	453.8		
<b>TOTAL Rs. in Crores</b>										<b>447.9</b>	<b>883.7</b>		<b>1325.7</b>	<b>665.3</b>	<b>9.5</b>